

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0020	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0030	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0040	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	303	00120 REGULAR EXCAVATION	4,940.000 CY				
0060	305	00140 BORROW EXCAVATION	5,896.000 CY				
0070	302 504	00525 CONCRETE CLASS A3 MISC.	1.000 CY				
0080	509	00529 FLOWABLE BACKFILL	1.000 CY				
0090	501	00588 UNDERDRAIN UD-4	1,633.000 LF				
0100	302	01152 15" CONC. PIPE	1,119.000 LF				
0110	302	01182 18" CONC. PIPE	166.000 LF				
0120	302	01241 JACKED & BORED 24" PIPE	645.000 LF				
0130	302	01242 24" CONC. PIPE	668.000 LF				
0140	302	06241 24" END SECTION ES-1	2.000 EA				
0150	302	06748 DROP INLET DI-2B,L=6'	2.000 EA				

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0160	302	06749 DROP INLET DI-2B,L=8'	1.000 EA	_____	_____	_____	_____
0170	302	06765 DROP INLET DI-2C,L=6'	1.000 EA	_____	_____	_____	_____
0180	302	06816 DROP INLET DI-3AA	2.000 EA	_____	_____	_____	_____
0190	302	06818 DROP INLET DI-3B,L=6'	12.000 EA	_____	_____	_____	_____
0200	302	06826 DROP INLET DI-3BB,L=4'	1.000 EA	_____	_____	_____	_____
0210	302	06835 DROP INLET DI-3C,L=6'	2.000 EA	_____	_____	_____	_____
0220	302	06836 DROP INLET DI-3C,L=8'	1.000 EA	_____	_____	_____	_____
0230	302	07506 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0240	302	07508 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0250	302	09056 MANHOLE MH-1 OR 2	69.000 LF	_____	_____	_____	_____
0260	302	09057 FRAME & COVER MH-1	10.000 EA	_____	_____	_____	_____
0270	414	09150 EROSION CONTROL STONE CLASS I, EC-1	66.000 TON	_____	_____	_____	_____
0280	308	10128 AGGR. BASE MATL. TY. I NO. 21B	2,179.000 TON	_____	_____	_____	_____
0290	315	10607 ASPHALT CONCRETE TY. SM-12.5A	1,271.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0300	315	10610 ASPHALT CONCRETE TY. IM-19.0A	708.000 TON	_____	_____	_____	_____
0310	315	10642 ASPHALT CONCRETE TY. BM-25.0A	1,035.000 TON	_____	_____	_____	_____
0320	315	11070 SAW-CUT ASPH CONC FULL DEPTH	3,328.000 LF	_____	_____	_____	_____
0330	502	12020 STD. CURB CG-2	444.000 LF	_____	_____	_____	_____
0340	502	12022 RADIAL CURB CG-2	225.000 LF	_____	_____	_____	_____
0350	502	12600 STD. COMB. CURB & GUTTER CG-6	1,818.000 LF	_____	_____	_____	_____
0360	502	12610 RADIAL COMB. CURB & GUTTER CG-6	905.000 LF	_____	_____	_____	_____
0370	502	12940 ENTRANCE GUTTER CG-9D	162.000 SY	_____	_____	_____	_____
0380	504	13108 CG-12 DETECTABLE WARNING SURFACE	28.000 SY	_____	_____	_____	_____
0390	502	13114 ENTRANCE GUTTER CG-13	51.000 SY	_____	_____	_____	_____
0400	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	1,220.000 SY	_____	_____	_____	_____
0410	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	325.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	512	13611 IMPACT ATTENUATOR SERVICE TYPE I	1.000 EA	_____	_____	_____	_____
0430	ATTD	14120 REMOVE COMB. CURB AND GUTTER	62.000 LF	_____	_____	_____	_____
0440	ATTD	14260 CRUSHER RUN AGGREGATE NO. 25 OR 26	69.000 TON	_____	_____	_____	_____
0450	ATTD	14450 SAW CUT CURB, GUTTER AND ENTRANCES	23.000 LF	_____	_____	_____	_____
0460	ATTD	16149 AGGR. NO. 8	37.000 TON	_____	_____	_____	_____
0470	515	16522 FLEXIBLE PAVEMENT PLANING 0" - 2"	3,636.000 SY	_____	_____	_____	_____
0480	502	21020 MEDIAN STRIP MS-1	125.000 SY	_____	_____	_____	_____
0490	511	24100 ALLAYING DUST	400.000 HR	_____	_____	_____	_____
0500	512	24152 TYPE 3 BARRICADE 8'	5.000 EA	_____	_____	_____	_____
0510	512	24160 TEMPORARY (CONSTRUCTION) SIGN	1,188.300 SF	_____	_____	_____	_____
0520	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	150.000 DAY	_____	_____	_____	_____
0530	512	24278 GROUP 2 CHANNELIZING DEVICES	41,500.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	1,344.000 HR	_____	_____	_____	_____
0550	512	24281 ELECTRONIC ARROW BOARD	4,720.000 HR	_____	_____	_____	_____
0560	512	24282 FLAGGER SERVICE	500.000 HR	_____	_____	_____	_____
0570	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	1,084.000 SY	_____	_____	_____	_____
0580	510	24802 REMOVE EXIST. MANHOLE .	2.000 EA	_____	_____	_____	_____
0590	514	25505 FIELD OFFICE TY.I	16.000 MO	_____	_____	_____	_____
0600	602	27012 TOPSOIL CLASS A 2"	0.640 ACRE	_____	_____	_____	_____
0610	603	27101 TEMPORARY SEED	64.000 LB	_____	_____	_____	_____
0620	603	27102 REGULAR SEED	96.000 LB	_____	_____	_____	_____
0630	603	27103 OVERSEEDING	77.000 LB	_____	_____	_____	_____
0640	603	27111 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,634.000 SY	_____	_____	_____	_____
0650	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	5,337.000 SY	_____	_____	_____	_____
0660	603	27230 FERTILIZER NITROGEN - N	64.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	603	27231 FERTILIZER PHOSPHOROUS - P	45.000 LB	_____	_____	_____	_____
0680	603	27232 FERTILIZER POTASSIUM - K	45.000 LB	_____	_____	_____	_____
0690	603	27250 LIME	3.520 TON	_____	_____	_____	_____
0700	303	27415 CHECK DAM ROCK TY. II	8.000 EA	_____	_____	_____	_____
0710	303	27430 SILTATION CONTROL EXCAVATION	748.000 CY	_____	_____	_____	_____
0720	303	27451 INLET PROTECTION TYPE A	3.000 EA	_____	_____	_____	_____
0730	303	27461 INLET PROTECTION TYPE B	26.000 EA	_____	_____	_____	_____
0740	303	27504 TEMP. SILT FENCE TYPE B	98.000 LF	_____	_____	_____	_____
0750	303	27505 TEMP. SILT FENCE TYPE A	3,253.000 LF	_____	_____	_____	_____
0760	303	27545 STORM WATER MANAGEMENT BASIN EXCAVATION	61.000 CY	_____	_____	_____	_____
0770	ATTD	27553 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTATION	LUMP SUM	LUMP SUM	_____	_____	_____
0780	302	27568 STORM WATER MANAGEMENT RISER PIPE 60"	6.900 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	520	40003 1" WATER SERVICE LINE	262.000 LF	_____	_____	_____	_____
0800	520	40061 6" DI WATER MAIN	86.000 LF	_____	_____	_____	_____
0810	520	40081 8" DI WATER MAIN	78.000 LF	_____	_____	_____	_____
0820	520	40121 12" DI WATER MAIN	265.000 LF	_____	_____	_____	_____
0830	520	40161 16" DI WATER MAIN	700.000 LF	_____	_____	_____	_____
0840	520	40406 16" BEND	8.000 EA	_____	_____	_____	_____
0850	520	40422 16" BRANCH	5.000 EA	_____	_____	_____	_____
0860	520	40460 16" REDUCER	1.000 EA	_____	_____	_____	_____
0870	520	40916 16" OFFSET EXIST. PIPE	40.000 LF	_____	_____	_____	_____
0880	520	40992 WATER UTILITY 16" SOLID SLEEVE	2.000 EA	_____	_____	_____	_____
0890	520	41006 6" GATE VALVE & BOX	3.000 EA	_____	_____	_____	_____
0900	520	41008 8" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0910	520	41012 12" GATE VALVE & BOX	3.000 EA	_____	_____	_____	_____
0920	520	41018 16" BUTTERFLY VALVE & BOX	8.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	520	41820 FIRE HYDRANT	1.000 EA	_____	_____	_____	_____
0940	520	41967 5/8" WATER METER BOX & YOKE	8.000 EA	_____	_____	_____	_____
0950	510	41977 ADJUST EXIST. WATER METER BOX	1.000 EA	_____	_____	_____	_____
0960	520	42044 4" SANITARY SERVICE LATERAL CONNECTION	105.000 LF	_____	_____	_____	_____
0970	520	42064 6" SANITARY SERVICE LATERAL CONNECTION	9.000 LF	_____	_____	_____	_____
0980	520	42080 8" SAN. SEWER PIPE	476.000 LF	_____	_____	_____	_____
0990	520	42755 SANITARY SEWER MANHOLE	41.700 LF	_____	_____	_____	_____
1000	520	42764 MANHOLE FRAME & COVER F&C-1	5.000 EA	_____	_____	_____	_____
1010	510	42765 ADJUST EXIST FRAME & COVER	2.000 EA	_____	_____	_____	_____
1020	520	42845 4" SEWER CLEANOUT	5.000 EA	_____	_____	_____	_____
1025	520	45552 12" STEEL ENCASE. PIPE	54.000 LF	_____	_____	_____	_____
1030	520	42846 6" SEWER CLEANOUT	1.000 EA	_____	_____	_____	_____
1040	509	45640 FLOWABLE BACKFILL UTILITY	44.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01

Oversight/State Project No.: 0636-088-707, C501

Order No.: J03

Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	701	50108 SIGN PANEL	299.000 SF	_____	_____	_____	_____
1060	700	50300 REMOVE EXISTING 1 POST SIGN STRUCTURE	11.000 EA	_____	_____	_____	_____
1070	700	50430 SIGN POST STP-1, 2", 14 GAUGE	164.000 LF	_____	_____	_____	_____
1080	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	50.000 LF	_____	_____	_____	_____
1090	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	19.000 EA	_____	_____	_____	_____
1100	700	51170 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
1110	703	51185 TRAFFIC SIGNAL HEAD SECTION 12" HVS BACKPLATE	30.000 EA	_____	_____	_____	_____
1120	703	51199 PEDESTRIAN ACTUATION PA-3	6.000 EA	_____	_____	_____	_____
1130	700	51210 PEDESTAL POLE PF-2 10'	2.000 EA	_____	_____	_____	_____
1140	700	51238 CONCRETE FOUNDATION SIGNAL POLE PF-8	30.000 CY	_____	_____	_____	_____
1150	700	51240 CONCRETE FOUNDATION PF-2	2.000 EA	_____	_____	_____	_____
1160	ATTD, 700	51243 CONC FOUNDATION CONCRETE FOUNDATION CF-5 FOR ATC CABINET	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1170	700	51475 SIGNAL MAST ARM POLE MP-3, TYPE A	1.000 EA	_____	_____	_____	_____
1180	700	51479 SIGNAL MAST ARM POLE MP-3, TYPE D	1.000 EA	_____	_____	_____	_____
1190	700	51480 SIGNAL MAST ARM POLE MP-3, TYPE E1	1.000 EA	_____	_____	_____	_____
1200	700	51487 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
1210	700	51490 MAST ARM 70'	1.000 EA	_____	_____	_____	_____
1220	703	51524 EVP DETECTION SYSTEM 4-WAY	1.000 EA	_____	_____	_____	_____
1230	703	51525 EVP DETECTOR CABLE	1,055.000 LF	_____	_____	_____	_____
1240	703	51540 LOOP DETECTOR AMPLIFIER	11.000 EA	_____	_____	_____	_____
1250	700	51598 8/3 CONDUCTOR CABLE	590.000 LF	_____	_____	_____	_____
1260	700	51602 14/4 CONDUCTOR CABLE	1,130.000 LF	_____	_____	_____	_____
1270	700	51607 14/7 CONDUCTOR CABLE	2,525.000 LF	_____	_____	_____	_____
1280	700	51615 14/1 ENCLOSED COND. CABLE	3,256.000 LF	_____	_____	_____	_____
1290	700	51700 14/2 CONDUCTOR CABLE SHIELDED	4,280.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1300	703	51830 HANGER ASSEMBLY SM-3, ONE WAY	8.000 EA	_____	_____	_____	_____
1310	703	51912 LOOP SAW CUT 3/8"	1,230.000 LF	_____	_____	_____	_____
1320	703	51913 LOOP SAWCUT 5/8"	300.000 LF	_____	_____	_____	_____
1330	703	51933 REMOVE EXISTING POLE	3.000 EA	_____	_____	_____	_____
1340	703	51934 REMOVE EXISTING FOUNDATION	3.000 EA	_____	_____	_____	_____
1350	703	51935 REMOVE EXISTING SIGNAL HEAD	7.000 EA	_____	_____	_____	_____
1360	703	51936 REMOVE EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
1370	700	51955 TEMPORARY TRAFFIC CONTROL SIGNAL TEMPORARY TRAFFICE CONTROL SIGNAL, COURTHOUSE RD/HOOD DR/HOUSER DR	LUMP SUM	LUMP SUM	_____	_____	_____
1380	703	51994 UNINTERRUPTIBLE POWER SUPPLY TYPE 2	1.000 EA	_____	_____	_____	_____
1390	703	51995 UNINTERRUPTIBLE POWER SUPPLY BATTERY PACK	1.000 EA	_____	_____	_____	_____
1400	ATTD, 700	52002 TRAFFIC SIGNALIZATION ATC CABINET - 5 DOOR	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1410	ATTD, 700	52002 TRAFFIC SIGNALIZATION MCCAIN ATC 2070 CONTROLLER WITH D4 FIRMWARE	1.000 EA	_____	_____	_____	_____
1420	703	52404 PEDESTRIAN SIGNAL HEAD SP-9	6.000 EA	_____	_____	_____	_____
1430	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	6,394.000 LF	_____	_____	_____	_____
1440	704	54037 TYPE B CLASS I PVMT LINE MRKG 8"	97.000 LF	_____	_____	_____	_____
1450	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	951.000 LF	_____	_____	_____	_____
1460	ATTD	54219 INLAID PAVEMENT MARKER ASPHALT	4.000 EA	_____	_____	_____	_____
1470	704	54393 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	1.000 EA	_____	_____	_____	_____
1480	512	54466 TYPE E TEMP. PVMT MRKG 6"	405.000 LF	_____	_____	_____	_____
1490	512	54542 TYPE D, CLASS III TEMP. PVMT MRKG 4"	945.000 LF	_____	_____	_____	_____
1500	704	54575 PVMT SYMB MRKG SGL TURN ARROW TY B, CL II	13.000 EA	_____	_____	_____	_____
1510	704	54578 PVMT SYMB MRKG DBL TURN ARROW THRU/LT OR RT TY B, CL II	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1520	700	55126 CONDUCTOR CABLE, NO. 8 EGC	2,005.000 LF	_____	_____	_____	_____
1530	700	55179 LUMINAIRE ARM LUMINAIRE ARM ON SIGNAL POLE 18'	2.000 EA	_____	_____	_____	_____
1540	700	55179 LUMINAIRE ARM LUMINAIRE ARM ON SIGNAL POLE 24'	1.000 EA	_____	_____	_____	_____
1545	ATTD, 705	55505 LUMINAIRE CONVENTIONAL LED (200 WATT TYPE III)	3.000 EA	_____	_____	_____	_____
1550	700	55587 JUNCTION BOX JB-S2	10.000 EA	_____	_____	_____	_____
1560	700	55588 JUNCTION BOX JB-S3	1.000 EA	_____	_____	_____	_____
1570	700	56014 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
1580	700	56021 1" PVC CONDUIT	110.000 LF	_____	_____	_____	_____
1590	700	56022 1" METAL CONDUIT	4.000 LF	_____	_____	_____	_____
1600	700	56050 BORED CONDUIT 2"	760.000 LF	_____	_____	_____	_____
1610	700	56051 BORED CONDUIT 3"	200.000 LF	_____	_____	_____	_____
1620	700	56052 BORED CONDUIT 4"	160.000 LF	_____	_____	_____	_____
1630	700	56053 2" PVC CONDUIT	740.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000110987M01 Oversight/State Project No.: 0636-088-707, C501
 Order No.: J03 Federal Project No.: CMAQ-5111(359)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1640	700	56054 3" PVC CONDUIT	70.000 LF	_____	_____	_____	_____
1650	700	56055 4" PVC CONDUIT	75.000 LF	_____	_____	_____	_____
1660	700	56200 TRENCH EXCAVATION ECI-1	810.000 LF	_____	_____	_____	_____
1670	700	56205 TEST BORE	3.000 EA	_____	_____	_____	_____
1680	808	57203 FIBER OPTIC DROP CABLE 12 STRAND	10.000 LF	_____	_____	_____	_____
1690	808	57204 PRE-TERMINATED FIBER PATCH PANEL	1.000 EA	_____	_____	_____	_____
1700	809	57221 MANAGED FIELD ETHERNET SWITCH Gbps	1.000 EA	_____	_____	_____	_____
1710	809	57227 DISTRIBUTION SFP MODULE 1Gbps, LC, AND SHORT HAUL	2.000 EA	_____	_____	_____	_____
1720	ATTD	59003 LIGHTING RE-RUN EXISTING CONDUIT & CABLE	LUMP SUM	LUMP SUM	_____	_____	_____
1730	516	70000 DEMO. OF BLDG. D701	LUMP SUM	LUMP SUM	_____	_____	_____
1740	516	70000 DEMO. OF BLDG. D702	LUMP SUM	LUMP SUM	_____	_____	_____
1750	516	70000 DEMO. OF BLDG. D901	LUMP SUM	LUMP SUM	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____