

Schedule of Items

Proposal ID: C0000119067B44B Oversight/State Project No.: 0058-087-696, B644, C501
 Order No.: H62 Federal Project No.: NHPP-PM05(477)

Contractor: _____

SECTION: 0001 BRIDGE ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	305	00280 SELECT MATL. TY. II MIN. CBR-20	9.000 CY				
0030	ATTD	24265 MAINTENANCE OF TRAFFIC STRUCTURE NO. 087-1044	LUMP SUM	LUMP SUM			
0040	ATTD	24825 MODIFY EXIST. DECK DRAINAGE SYSTEM SCUPPER	6.000 EA				
0050	514	25507 FIELD OFFICE TY.III	15.000 MO				
0060	414	27401 EROSION CONTROL RIPRAP	4.000 TON				
0070	303	27500 GEOTEXTILE FABRIC	9.000 SY				
0080	303	27504 TEMP. SILT FENCE TYPE B	30.000 LF				
0090	704	54080 TYPE B CLASS VI CONTRAST PVMT MRKG 6"	3,000.000 LF				
0100	ATTD	60125 BRIDGE INSPECTION BY MEANS OF GROUND PENETRATING RADAR (GPR)	LUMP SUM	LUMP SUM			
0110	404	60490 BRIDGE DECK GROOVING	5,134.000 SY				
0120	404	60495 COVER DEPTH SURVEY	5,134.000 SY				

Schedule of Items

Proposal ID: C0000119067B44B Oversight/State Project No.: 0058-087-696, B644, C501
 Order No.: H62 Federal Project No.: NHPP-PM05(477)

Contractor: _____

SECTION: 0001 BRIDGE ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	420	62419 ADHESIVE BASED JOINT SEALER CLASS II, 3"	350.000 LF	_____	_____	_____	_____
0140	ATTD	66920 BRIDGE SUBSTRUCTURE FLOWABLE BACKFILL (SOUTHWEST EMBANKMENT)	3.000 CY	_____	_____	_____	_____
0150	412	68074 SHOTCRETE, TYPE A	100.000 SF	_____	_____	_____	_____
0160	412	68170 CRACK REPAIR TYPE A	91.000 LF	_____	_____	_____	_____
0170	412	68172 CRACK REPAIR TYPE B	68.000 LF	_____	_____	_____	_____
0180	412	68180 EMBEDDED GALVANIC ANODES	68.000 EA	_____	_____	_____	_____
0190	425	68258 REMOVE ASPHALT CONCRETE OVERLAY	5,134.000 SY	_____	_____	_____	_____
0200	412	68332 H.E.S. PATCHING TYPE C	445.000 SY	_____	_____	_____	_____
0210	ATTD	68571 RECONSTR. EXPAN. JOINT (LOW SHRINKAGE CLASS A4 MODIFIED CONCRETE)	574.000 LF	_____	_____	_____	_____
0220	412	68573 RECONSTRUCT EXPANSION JOINT, HES	574.000 LF	_____	_____	_____	_____
0230	412	68579 RECONSTRUCT BACK WALL, HES	115.000 LF	_____	_____	_____	_____
0240	412	68580 BEAM END REPAIR	38.000 EA	_____	_____	_____	_____

Proposal ID: C0000119067B44B Oversight/State Project No.: 0058-087-696, B644, C501
 Order No.: H62 Federal Project No.: NHPP-PM05(477)

Contractor: _____

SECTION: 0001 BRIDGE ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	412	68590 JACKING AND BLOCKING BEAM	48.000 EA	_____	_____	_____	_____
0260	412	68600 CONCRETE SUPERSTRUCT. SURFACE REPAIR	3.000 SY	_____	_____	_____	_____
0270	425	68609 PLACE CLASS A4 BRIDGE DECK CONCRETE OVERLAY	5,134.000 SY	_____	_____	_____	_____
0280	ATTD	68623 FURNISH CLASS A4 BRIDGE DECK CONCRETE LOW SHRINKAGE CLASS A4 MODIFIED BRIDGE DECK CONCRETE (4"-6")	813.000 CY	_____	_____	_____	_____
0290	ATTD	68648 TYPE B HYDRO-DEMOLITION (TYPE B)	5,134.000 SY	_____	_____	_____	_____
0300	412	69500 CONCRETE SUBSTRUCT. SURFACE REPAIR	9.000 SY	_____	_____	_____	_____
0310	ATTD	69822 RECONSTRUCT BRIDGE SEAT (HES)	10.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	