

Schedule of Items

Proposal ID: C0000111052M01 Oversight/State Project No.: 0682-082-870,M501

Order No.: J51

Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	00120 REGULAR EXCAVATION	7,005.000 CY				
0050	305	00140 BORROW EXCAVATION	5,988.000 CY				
0060	303	00211 MINOR STRUCTURE EXCAV. PIPE CULVERT	12.000 CY				
0070	305	00306 SELECT MATERIAL TY. I	1,063.000 TON				
0080	305	00355 GEOTEXTILE SUBGRADE STABILIZATION	3,326.000 SY				
0090	501	00585 UNDERDRAIN UD-2	500.000 LF				
0100	501	00588 UNDERDRAIN UD-4	805.000 LF				
0110	501	00591 CROSSDRAIN CD-2	64.000 LF				
0120	501	00595 OUTLET PIPE	40.000 LF				
0130	302	00596 ENDWALL EW-12	3.000 EA				
0140	302	01150 15" PIPE	98.000 LF				

Schedule of Items

Proposal ID: C0000111052M01 Oversight/State Project No.: 0682-082-870,M501

Order No.: J51

Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	01482 48" CONC. PIPE	84.000 LF	_____	_____	_____	_____
0160	302	06495 END SECTION ENDWALL EW-2 48"	2.000 EA	_____	_____	_____	_____
0170	414	09148 EROSION CONTROL STONE CLASS A1 EC-1	10.000 TON	_____	_____	_____	_____
0180	414	09150 EROSION CONTROL STONE CLASS I, EC-1	24.000 TON	_____	_____	_____	_____
0190	308	10100 AGGR. MATL. NO. 21B	1,200.000 TON	_____	_____	_____	_____
0200	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	850.000 SY	_____	_____	_____	_____
0210	315	10635 ASPHALT CONC.TY. SM-9.5A	285.000 TON	_____	_____	_____	_____
0220	315	10642 ASPHALT CONCRETE TY. BM-25.0A	561.000 TON	_____	_____	_____	_____
0230	315	11070 SAW-CUT ASPH CONC FULL DEPTH	289.000 LF	_____	_____	_____	_____
0240	503	13212 R/W MONUMENT RM-2	21.000 EA	_____	_____	_____	_____
0250	505	13280 GUARDRAIL GR-MGS1	425.000 LF	_____	_____	_____	_____
0260	505	13286 GUARDRAIL TERMINAL GR-MGS2	4.000 EA	_____	_____	_____	_____
0270	505	13349 GUARDRAIL TERMINAL SITE PREPARATION	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111052M01 Oversight/State Project No.: 0682-082-870,M501

Order No.: J51

Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	507	23560 TEMP. SAFETY FENCE 4'	250.000 LF	_____	_____	_____	_____
0290	511	24100 ALLAYING DUST	200.000 HR	_____	_____	_____	_____
0300	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0310	512	24160 TEMPORARY (CONSTRUCTION) SIGN	200.000 SF	_____	_____	_____	_____
0320	ATTD	24262 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	100.000 DAY	_____	_____	_____	_____
0330	512	24278 GROUP 2 CHANNELIZING DEVICES	24,000.000 DAY	_____	_____	_____	_____
0340	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	5,000.000 HR	_____	_____	_____	_____
0350	512	24282 FLAGGER SERVICE	1,000.000 HR	_____	_____	_____	_____
0360	508	24400 OBSCURING ROADWAY	19.000 UNIT	_____	_____	_____	_____
0370	508	24430 DEMOLITION OF PAVEMENT FLEXIBLE	2,900.000 SY	_____	_____	_____	_____
0380	514	25506 FIELD OFFICE TY.II	12.000 MO	_____	_____	_____	_____
0390	ATTD	26100 ROCKFILL	100.000 TON	_____	_____	_____	_____
0400	602	27024 TOPSOIL CLASS B 3"	1.030 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111052M01      Oversight/State Project No.: 0682-082-870,M501  
 Order No.: J51      Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001      ALL BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	603	27101 TEMPORARY SEED	40.000 LB	_____	_____	_____	_____
0420	603	27102 REGULAR SEED	247.000 LB	_____	_____	_____	_____
0430	603	27103 OVERSEEDING	206.000 LB	_____	_____	_____	_____
0440	603	27112 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	9,390.000 SY	_____	_____	_____	_____
0450	603	27230 FERTILIZER NITROGEN - N	87.000 LB	_____	_____	_____	_____
0460	603	27231 FERTILIZER PHOSPHOROUS - P	112.000 LB	_____	_____	_____	_____
0470	603	27232 FERTILIZER POTASSIUM - K	56.000 LB	_____	_____	_____	_____
0480	603	27250 LIME	4.010 TON	_____	_____	_____	_____
0490	606	27320 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	1,600.000 SY	_____	_____	_____	_____
0500	303	27415 CHECK DAM ROCK TY. II	36.000 EA	_____	_____	_____	_____
0510	303	27419 CHECK DAM ROCK TYPE I TEMPORARY	8.000 EA	_____	_____	_____	_____
0520	303	27430 SILTATION CONTROL EXCAVATION	359.000 CY	_____	_____	_____	_____
0530	303	27505 TEMP. SILT FENCE TYPE A	1,800.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111052M01 Oversight/State Project No.: 0682-082-870,M501

Order No.: J51

Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001 ALL BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	701	50108 SIGN PANEL	104.750 SF	_____	_____	_____	_____
0550	700	50340 RELOCATE EXISTING 1 POST GROUND MOUNTED SIGN PANEL	1.000 EA	_____	_____	_____	_____
0560	700	50430 SIGN POST STP-1, 2", 14 GAUGE	110.500 LF	_____	_____	_____	_____
0570	700	50436 SIGN POST STP-1, 2 1/2", 12 GAUGE	10.500 LF	_____	_____	_____	_____
0580	700	50485 CONCRETE SIGN FOUNDATION STP-1, TYPE A	16.000 EA	_____	_____	_____	_____
0590	700	50488 CONCRETE SIGN FOUNDATION STP-1, TYPE D	1.000 EA	_____	_____	_____	_____
0600	700	51930 REMOVE EXISTING SIGN STRUCTURE TY. 1	6.000 EA	_____	_____	_____	_____
0610	703	51934 REMOVE EXISTING FOUNDATION	1.000 EA	_____	_____	_____	_____
0620	704	54032 TYPE B CLASS I PVMT LINE MRKG 4"	2,300.000 LF	_____	_____	_____	_____
0630	704	54034 TYPE B CLASS I PVMT LINE MRKG 6"	2,170.000 LF	_____	_____	_____	_____
0640	704	54044 TYPE B CLASS II PAVE. LINE MARKING 6"	20.000 LF	_____	_____	_____	_____
0650	704	54048 TYPE B CLASS II PAVE. LINE MARKING 24"	20.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000111052M01      Oversight/State Project No.: 0682-082-870,M501  
 Order No.: J51      Federal Project No.: STP-5115(259)

Contractor: \_\_\_\_\_

SECTION: 0001      ALL BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	512	54105 ERADICATE EXIST. LINEAR PVMT MARKING	100.000 LF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____