

Schedule of Items

Proposal ID: C0000118788B25 Oversight/State Project No.: 6759-000-912, B625

Order No.: J69

Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	513	00100 MOBILIZATION	LUMP SUM	LUMP SUM			
0020	517	00101 CONSTRUCTION SURVEYING CONSTRUCTION	LUMP SUM	LUMP SUM			
0030	301	00110 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	ATTD	02112 DRAINAGE CLEAN EXISTING INLET	4.000 EA				
0050	308	10128 AGGR. BASE MATL. TY. I NO. 21B	21.000 TON				
0060	515	10628 FLEXIBLE PAVEMENT PLANING 0" - 2"	212.000 SY				
0070	315	10635 ASPHALT CONC.TY. SM-9.5A	26.000 TON				
0080	504	13220 HYDRAULIC CEMENT CONC. SIDEWALK 4"	96.000 SY				
0090	512	13496 TRAF. BARR. SER. CONC. DOUBLE FACE PAR.MB-11A	2,352.000 LF				
0100	512	13604 IMPACT ATTEN. SER. TY. 1 TL-3, >=40 MPH	4.000 EA				
0110	512	13605 IMPACT ATTEN. SER. TY. 1 TL-2, <40 MPH	2.000 EA				
0120	ATTD	14100 REMOVE SIDEWALK AND ENTRANCE	96.000 SY				

Schedule of Items

Proposal ID: C0000118788B25 Oversight/State Project No.: 6759-000-912, B625
 Order No.: J69 Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	507	23560 TEMP. SAFETY FENCE 4'	300.000 LF	_____	_____	_____	_____
0140	512	24150 TYPE 3 BARRICADE 4'	9.000 EA	_____	_____	_____	_____
0150	512	24152 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0160	512	24160 TEMPORARY (CONSTRUCTION) SIGN	940.000 SF	_____	_____	_____	_____
0170	512	24272 TRUCK MOUNTED ATTENUATOR	768.000 HR	_____	_____	_____	_____
0180	512	24278 GROUP 2 CHANNELIZING DEVICES	17,352.000 DAY	_____	_____	_____	_____
0190	512	24279 PORTABLE CHANGEABLE MESSAGE SIGN	6,452.000 HR	_____	_____	_____	_____
0200	512	24281 ELECTRONIC ARROW BOARD	807.000 HR	_____	_____	_____	_____
0210	505	24600 REMOVE EXISTING GUARDRAIL	157.000 LF	_____	_____	_____	_____
0220	ATTD	25565 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM		_____	_____
0230	ATTD	25567 PROGRESS SCHEDULE UPDATES	12.000 EA	_____	_____	_____	_____
0240	602	27022 TOPSOIL CLASS B 2"	0.200 ACRE	_____	_____	_____	_____
0250	603	27101 TEMPORARY SEED	185.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118788B25

Oversight/State Project No.: 6759-000-912, B625

Order No.: J69

Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	603	27102 REGULAR SEED	62.000 LB	_____	_____	_____	_____
0270	603	27103 OVERSEEDING	38.000 LB	_____	_____	_____	_____
0280	603	27230 FERTILIZER NITROGEN - N	198.000 LB	_____	_____	_____	_____
0290	603	27250 LIME	0.700 TON	_____	_____	_____	_____
0300	ATTD	27275 EROSION CONTROL CLEAN EXISTING PIPE	94.000 LF	_____	_____	_____	_____
0310	303	27451 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0320	303	27461 INLET PROTECTION TYPE B	4.000 EA	_____	_____	_____	_____
0330	303	27505 TEMP. SILT FENCE TYPE A	557.000 LF	_____	_____	_____	_____
0340	ATTD	49013 UTILITIES TEMPORARY SUPPORT/PROTECTION OF UTILITIES	LUMP SUM	LUMP SUM	_____	_____	_____
0350	701	50108 SIGN PANEL	9.000 SF	_____	_____	_____	_____
0360	704	54020 TYPE A PVMT LINE MRKG 4"	918.000 LF	_____	_____	_____	_____
0370	704	54022 TYPE A PVMT LINE MRKG 6"	34.000 LF	_____	_____	_____	_____
0380	512	54240 TEMP. PAVE. MARKER 1 WAY	878.000 EA	_____	_____	_____	_____
0390	512	54466 TYPE E TEMP. PVMT MRKG 6"	17,240.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118788B25 Oversight/State Project No.: 6759-000-912, B625
 Order No.: J69 Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	512	54543 TYPE D, CLASS III TEMP. PVMT MRKG 6"	1,526.000 LF	_____	_____	_____	_____
0410	512	54544 TYPE D, CLASS III TEMP. PVMT MRKG 8"	14,581.000 LF	_____	_____	_____	_____
0420	404	68090 BRIDGE DECK GROOVING	1,130.000 SY	_____	_____	_____	_____
0430	406	68091 CORROSION RESISTANT REINF. STEEL CL. I	14,410.000 LB	_____	_____	_____	_____
0440	412	68172 CRACK REPAIR TYPE B	200.000 LF	_____	_____	_____	_____
0450	412	68180 EMBEDDED GALVANIC ANODES	486.000 EA	_____	_____	_____	_____
0460	426	68192 REPLACE BEARING	24.000 EA	_____	_____	_____	_____
0470	428	68197 CONCRETE SURFACE PENETRANT SEALER	373.000 SY	_____	_____	_____	_____
0480	425	68316 TYPE A MILLING 1-3/4"	220.000 SY	_____	_____	_____	_____
0490	412	68339 DECK SLAB CLOSURE	24.000 SY	_____	_____	_____	_____
0500	416	68406 WATERPROOFING - EPOXY RESIN TYPE EP-3B/EP-3T	603.000 SY	_____	_____	_____	_____
0510	ATTD	68465 ZONE COAT. EX. STR. (STR. NO. 5037, TYPE A)	LUMP SUM	LUMP SUM	_____	_____	_____
0520	ATTD	68474 ENV. PROT. & HEALTH & SAFETY (STR. NO. 5037)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000118788B25 Oversight/State Project No.: 6759-000-912, B625
 Order No.: J69 Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	ATTD	68490 DISPOSAL OF MATERIAL (STR. NO. 5037, TYPE A)	LUMP SUM	LUMP SUM			
0540	420	68529 ADHESIVE BASED JOINT SEALER CLASS I, 2"	53.000 LF				
0550	420	68530 ADHESIVE BASED JOINT SEALER CLASS I, 2 1/2"	53.000 LF				
0560	412	68573 RECONSTRUCT EXPANSION JOINT, HES	106.000 LF				
0570	412	68590 JACKING AND BLOCKING BEAM	24.000 EA				
0580	425	68605 FURNISH LATEX MODIFIED CONCRETE 1-1/4" - 1-3/4"	10.700 CY				
0590	425	68609 PLACE CLASS A4 BRIDGE DECK CONCRETE OVERLAY	864.000 SY				
0600	425	68615 PLACE HIGH EARLY STRENGTH LATEX MODIFIED CONCRETE OVERLAY	220.000 SY				
0610	425	68622 FURNISH CLASS A4 BRIDGE DECK CONCRETE 4"- 4-1/2"	96.000 CY				
0620	425, ATTD	68910 SUPERSTR. WID./REPAIR TYPE B HYDRO-DEMOLITION 4"	864.000 SY				
0630	412	69815 RECONSTRUCT BRIDGE SEAT TYPE A	12.000 EA				

Schedule of Items

Proposal ID: C0000118788B25 Oversight/State Project No.: 6759-000-912, B625
 Order No.: J69 Federal Project No.: NHPP-5B01(339)

Contractor: _____

SECTION: 0001 Bridge Rehab Bid Items

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	412	69816 RECONSTRUCT BRIDGE SEAT TYPE B	6.000 EA	_____	_____	_____	_____
0650	412, ATTD	69908 BR. SUBSTR. WID./REPAIR CONCRETE SUBSTRUCT. SURFACE REPAIR	63.000 SY	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____