

Schedule of Items

Proposal ID: CM423PMH121276 Oversight/State Project No.: 0036-116-222, P401

Order No.: J85

Federal Project No.: STP-5B27(001)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0029 SILTATION CONTROL EXCAVATION	34.000 CY	_____	_____	_____	_____
0020	ATTD	305SP20-0003 AGR.BASE MAT.TY.I OR II NO. 21A OR21B	134.000 TON	_____	_____	_____	_____
0030	310	310SD20-0001 TACK COAT	9,759.000 GAL	_____	_____	_____	_____
0040	315	315SD20-0029 ASPH. CONC. TY. SM-9.5D MAINT	4,050.760 TON	_____	_____	_____	_____
0050	315	315SD20-0034 ASPH. CONC. TY. SM-12.5D MAINT	5,462.990 TON	_____	_____	_____	_____
0060	ATTD	315SX20-0011 SAW-CUT ASPH CONC ASPH. CONC. FULL DEPTH	1,198.000 LF	_____	_____	_____	_____
0070	ATTD	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	1,117.400 TON	_____	_____	_____	_____
0080	502	502SD20-0011 CURB, STD. CG-2	1,303.000 LF	_____	_____	_____	_____
0090	502	502SD20-0012 CURB, RADIAL CG-2	256.000 LF	_____	_____	_____	_____
0100	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	760.000 LF	_____	_____	_____	_____
0110	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	134.000 LF	_____	_____	_____	_____
0120	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	88.880 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM423PMH121276 Oversight/State Project No.: 0036-116-222, P401

Order No.: J85

Federal Project No.: STP-5B27(001)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	562.630 SY	_____	_____	_____	_____
0140	ATTD	510SX20-0002 REMOVE COMB. CURB AND GUTTER	1,267.000 LF	_____	_____	_____	_____
0150	ATTD	510SX20-0038 REMOVE EXIST. REMOVE HYDRAULIC CEMENT CONCRETE	713.620 SY	_____	_____	_____	_____
0160	ATTD	510SX20-0046 ADJUST EXIST. EXIST TRAFFIC JUNCTION BOX	9.000 EA	_____	_____	_____	_____
0170	ATTD	510SX20-0046 ADJUST EXIST. EXIST VALVE	1.000 EA	_____	_____	_____	_____
0180	512	512SD20-0027 FLAGGER SERVICE	1,135.000 HR	_____	_____	_____	_____
0190	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	66,984.000 LF	_____	_____	_____	_____
0200	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	2,800.000 LF	_____	_____	_____	_____
0210	512	512SD20-0048 TEMP. PVMT MRKG TY. A, 8"	3,340.000 LF	_____	_____	_____	_____
0220	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	971.000 LF	_____	_____	_____	_____
0230	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	90.000 DAY	_____	_____	_____	_____
0240	512	512SP20-0002 MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM	_____	_____	_____
0250	512	512SX20-0045 SAFETY UNIFORM FLAGGERS	705.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM423PMH121276 Oversight/State Project No.: 0036-116-222, P401

Order No.: J85

Federal Project No.: STP-5B27(001)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	512	513SX20-0001 MOBILIZATION, UPC: 121275	1.000 EA	_____	_____	_____	_____
0270	512	513SX20-0001 MOBILIZATION, UPC: 121276	1.000 EA	_____	_____	_____	_____
0280	512	513SX20-0001 MOBILIZATION, UPC: 121277	1.000 EA	_____	_____	_____	_____
0290	512	513SX20-0001 MOBILIZATION, UPC: 121278	1.000 EA	_____	_____	_____	_____
0300	512	513SX20-0001 MOBILIZATION, UPC: 121279	1.000 EA	_____	_____	_____	_____
0310	512	513SX20-0001 MOBILIZATION, UPC: 121280	1.000 EA	_____	_____	_____	_____
0320	512	513SX20-0001 MOBILIZATION, UPC: 121281	1.000 EA	_____	_____	_____	_____
0330	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	97,562.040 SY	_____	_____	_____	_____
0340	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	3,384.000 LF	_____	_____	_____	_____
0350	700	700SD20-0182 CONDUIT PVC 1"	110.000 LF	_____	_____	_____	_____
0360	703	703SD20-0042 LOOP SAW CUT 3/8"	1,128.000 LF	_____	_____	_____	_____
0370	703	703SD20-0043 LOOP SAW CUT 5/8"	110.000 LF	_____	_____	_____	_____
0380	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	37,154.000 LF	_____	_____	_____	_____
0390	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	2,274.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM423PMH121276 Oversight/State Project No.: 0036-116-222, P401

Order No.: J85

Federal Project No.: STP-5B27(001)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	4,330.000 LF	_____	_____	_____	_____
0410	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	2,271.000 LF	_____	_____	_____	_____
0420	704	704SD20-0035 PVMT MSG. MARK. "ONLY" TY B, CL. I, 6'	1.000 EA	_____	_____	_____	_____
0430	704	704SD20-0044 PVMT SYMB MRKG THRU ARROW TY B, CL I	11.000 EA	_____	_____	_____	_____
0440	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	32.000 EA	_____	_____	_____	_____
0450	704	704SD20-0050 DBL TURN ARR. THRU/LT OR RT TY B, CL I	19.000 EA	_____	_____	_____	_____
0460	704	704SD20-0083 PVMT SYMB MRKG YIELD 1' X 1.5' TY B CL I	6.000 EA	_____	_____	_____	_____
0470	704	704SD20-0092 MRKG INT'L ACCESSIBILITY SYMB TY B CL I	1.000 EA	_____	_____	_____	_____
0480	704	704SD20-0107 PVMT MSG. MARK. "ONLY" TY B, CL. I, 8'	7.000 EA	_____	_____	_____	_____

Section: 0001

Total: _____

Schedule of Items

Proposal ID: CM423PMH121276 Oversight/State Project No.: 0036-116-222, P401

Order No.: J85

Federal Project No.: STP-5B27(001)

Contractor: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: _____ Cat Alt Mbr ID: _____

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0490	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:		_____	_____
				Total Bid:		_____	_____