

Schedule of Items

Proposal ID: CM824PMH123331 Oversight/State Project No.: PM8H-968-F24,N501

Order No.: 839

Federal Project No.: PM08(469)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	753.420 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	10,500.000 GAL	_____	_____	_____	_____
0030	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	5,800.000 LF	_____	_____	_____	_____
0040	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	10,569.910 TON	_____	_____	_____	_____
0050	ATTD	315SX20-0004 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	80.000 SY	_____	_____	_____	_____
0060	512	512SD20-0027 FLAGGER SERVICE	311.000 HR	_____	_____	_____	_____
0070	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	3,000.000 SF	_____	_____	_____	_____
0080	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	19,410.000 LF	_____	_____	_____	_____
0090	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	57,850.000 LF	_____	_____	_____	_____
0100	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	1,400.000 LF	_____	_____	_____	_____
0110	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	18.000 EA	_____	_____	_____	_____
0120	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT FOR UPC 123331	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: CM824PMH123331 Oversight/State Project No.: PM8H-968-F24,N501

Order No.: 839

Federal Project No.: PM08(469)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	512SX20-0006 TEMP. PVMT MRKG TEMP. SCHOOL ZONE	2.000 EA	_____	_____	_____	_____
0140	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	1,136.000 SY	_____	_____	_____	_____
0150	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	69,720.000 SY	_____	_____	_____	_____
0160	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	19,410.000 LF	_____	_____	_____	_____
0170	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	57,850.000 LF	_____	_____	_____	_____
0180	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	1,200.000 LF	_____	_____	_____	_____
0190	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	700.000 LF	_____	_____	_____	_____
0200	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	230.000 EA	_____	_____	_____	_____
0210	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	18.000 EA	_____	_____	_____	_____
0220	704	704SD20-0111 PVMT MSG. MARK. "SCHOOL" TY B, CL II, 8'	2.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

Schedule of Items

Proposal ID: CM824PMH123331    Oversight/State Project No.: PM8H-968-F24,N501  
 Order No.: 839    Federal Project No.: PM08(469)

Contractor: \_\_\_\_\_

SECTION: 0002    ALTERNATE ITEM

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0230	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____