

Schedule of Items

Proposal ID: CM124PMJ123133 Oversight/State Project No.: PM1J-961-F24, N501

Order No.: 131

Federal Project No.: PM01(352)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0010 | ATTD | 305SP20-0003 AGR. BASE MAT. TY. I OR II NO. 21A OR 21B | 2,470.330 TON | _____ | _____ | _____ | _____ |
| 0020 | 310 | 310SD20-0001 TACK COAT | 23,705.000 GAL | _____ | _____ | _____ | _____ |
| 0030 | 315 | 315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT | 10,780.000 LF | _____ | _____ | _____ | _____ |
| 0040 | 315 | 315SD20-0036 ASPH. CONC. TY. SM-12.5E MAINT | 26,676.850 TON | _____ | _____ | _____ | _____ |
| 0050 | 512 | 512SD20-0027 FLAGGER SERVICE | 750.000 HR | _____ | _____ | _____ | _____ |
| 0060 | 512 | 512SD20-0046 TEMP. PVMT MRKG TY. A, 4" | 181,400.000 LF | _____ | _____ | _____ | _____ |
| 0070 | 512 | 512SD20-0047 TEMP. PVMT MRKG TY. A, 6" | 79,850.000 LF | _____ | _____ | _____ | _____ |
| 0080 | ATTD | 512SP20-0002 MAINTENANCE OF TRAFFIC PLANT MIX | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0090 | 515 | 515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2" | 1,155.730 SY | _____ | _____ | _____ | _____ |
| 0100 | 515 | 515SD20-0013 FLEXIBLE PAVE. PLANING 0"- 2" | 105,705.590 SY | _____ | _____ | _____ | _____ |
| 0110 | 704 | 704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4" | 181,400.000 LF | _____ | _____ | _____ | _____ |
| 0120 | 704 | 704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6" | 79,850.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: CM124PMJ123133 Oversight/State Project No.: PM1J-961-F24, N501
 Order No.: 131 Federal Project No.: PM01(352)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0130 | 704 | 704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24" | 110.000 LF | _____ | _____ | _____ | _____ |
| 0140 | ATTD | 704SD20-0032 INLAID PAVEMENT MARKER ASPHALT | 460.000 EA | _____ | _____ | _____ | _____ |
| 0150 | 704 | 704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I | 10.000 EA | _____ | _____ | _____ | _____ |
| 0160 | 704 | 704SD20-0123 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 10' | 1.000 EA | _____ | _____ | _____ | _____ |

Section: 0001 Total: _____

SECTION: 0002 ALTERNATE ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0170 | ATTD | 305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL | 1.000 TON | _____ | _____ | _____ | _____ |

Section: 0002 Total: _____

Total Bid: _____