

Schedule of Items

Proposal ID: CM624PMW122935 Oversight/State Project No.: PM6W-966-F24,P401

Order No.: 639

Federal Project No.: PM06(406)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0006 EXTRA EXCAVATION	30.000 CY	_____	_____	_____	_____
0020	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	132.000 TON	_____	_____	_____	_____
0030	310	310SD20-0001 TACK COAT	21,640.000 GAL	_____	_____	_____	_____
0040	315	315SD20-0040 ASPH. CONC. TY. IM-19.0A MAINT	44.000 TON	_____	_____	_____	_____
0050	315	315SD20-0052 RUMBLE STRIP SINUSOIDAL ASPHALT	73,602.000 LF	_____	_____	_____	_____
0060	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	61,225.000 LF	_____	_____	_____	_____
0070	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	22,967.360 TON	_____	_____	_____	_____
0080	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0A	436.000 TON	_____	_____	_____	_____
0090	412	412SD20-0044 SAW CUTTING	220.000 LF	_____	_____	_____	_____
0100	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	100.000 SY	_____	_____	_____	_____
0110	512	512SD20-0027 FLAGGER SERVICE	550.000 HR	_____	_____	_____	_____
0120	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	249,882.000 LF	_____	_____	_____	_____
0130	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM	_____	_____	_____

## Schedule of Items

Proposal ID: CM624PMW122935 Oversight/State Project No.: PM6W-966-F24,P401

Order No.: 639

Federal Project No.: PM06(406)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	202,237.460 SY	_____	_____	_____	_____
0150	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	3,896.000 LF	_____	_____	_____	_____
0160	700	700SD20-0182 CONDUIT PVC 1"	140.000 LF	_____	_____	_____	_____
0170	703	703SD20-0042 LOOP SAW CUT 3/8"	1,464.000 LF	_____	_____	_____	_____
0180	703	703SD20-0043 LOOP SAW CUT 5/8"	252.000 LF	_____	_____	_____	_____
0190	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	77,883.000 LF	_____	_____	_____	_____
0200	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	47,058.000 LF	_____	_____	_____	_____
0210	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	1,542.000 LF	_____	_____	_____	_____
0220	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	766.000 EA	_____	_____	_____	_____
0230	704	704SD20-0044 PVMT SYMB MRKG THRU ARROW TY B, CL I	5.000 EA	_____	_____	_____	_____
0240	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	59.000 EA	_____	_____	_____	_____
0250	704	704SD20-0050 DBL TURN ARR.THUR/LT OR RT TY B, CL I	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM624PMW122935    Oversight/State Project No.: PM6W-966-F24,P401  
 Order No.: 639    Federal Project No.: PM06(406)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	704	704SD20-0059 SYMB MRKG LANE REDUCTION ARR TY B CL I	2.000 EA	_____	_____	_____	_____
0270	704	704SD20-0123 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 10'	2.000 EA	_____	_____	_____	_____
0280	704	704SX20-0005 PAVE. MESSAGE MARKING STOP	3.000 EA	_____	_____	_____	_____

Section: 0001    Total: \_\_\_\_\_

SECTION: 0002    ALTERNATE ITEM

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____

Section: 0002    Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_