

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0010 | ATTD | 108SP20-0001 BASELINE PROGRESS SCHEDULE | LUMP SUM | LUMP SUM | | | |
| 0020 | ATTD | 108SP20-0002 PROGRESS SCHEDULE UPDATES | 24.000 EA | | | | |
| 0030 | 301 | 301SD20-0001 CLEARING AND GRUBBING | LUMP SUM | LUMP SUM | | | |
| 0040 | ATTD | 302SD20-0002 BEDDING MATL. AGGR. NO. 57 | 3,301.500 TON | | | | |
| 0050 | 302, 406 | 302SD20-0005 REINF. STEEL | 1,280.000 LB | | | | |
| 0060 | 302 | 302SD20-0013 ENDWALL EW-12 | 33.000 EA | | | | |
| 0070 | 302 | 302SD20-0023 15" PIPE | 28.000 LF | | | | |
| 0080 | 302 | 302SD20-0025 15" CONC. PIPE | 242.000 LF | | | | |
| 0090 | 302 | 302SD20-0028 18" PIPE | 15.000 LF | | | | |
| 0100 | 302 | 302SD20-0030 18" CONC. PIPE | 41.000 LF | | | | |
| 0110 | 302 | 302SD20-0049 30" CONC. PIPE | 10.000 LF | | | | |
| 0120 | 302 | 302SD20-0057 36" PIPE | 30.000 LF | | | | |
| 0130 | 302 | 302SD20-0059 36" CONC. PIPE | 27.000 LF | | | | |
| 0140 | 302 | 302SD20-0069 48" CONC. PIPE | 63.000 LF | | | | |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0150 | 302 | 302SD20-0081 60" CONC. PIPE | 57.000 LF | _____ | _____ | _____ | _____ |
| 0160 | 302 | 302SD20-0198 15" END SECTION ES-1 OR 2 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0170 | 302 | 302SD20-0208 30" END SECTION ES-1 OR 2 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0180 | 302 | 302SD20-0214 48" END SECTION ES-1 OR 2 | 3.000 EA | _____ | _____ | _____ | _____ |
| 0190 | 302 | 302SD20-0242 DROP INLET DI-2B,L=6' | 2.000 EA | _____ | _____ | _____ | _____ |
| 0200 | 302 | 302SD20-0259 DROP INLET DI-2C,L=6' | 2.000 EA | _____ | _____ | _____ | _____ |
| 0210 | 302 | 302SD20-0662 MANHOLE MH-1 OR 2 | 9.400 LF | _____ | _____ | _____ | _____ |
| 0220 | 302 | 302SD20-0663 FRAME & COVER MH-1 | 1.000 EA | _____ | _____ | _____ | _____ |
| 0230 | 303 | 303SD20-0001 REGULAR EXCAVATION | 32,745.000 CY | _____ | _____ | _____ | _____ |
| 0240 | 303 | 303SD20-0013 GEOTEXTILE EMBANKMENT STAB. | 8,453.000 SY | _____ | _____ | _____ | _____ |
| 0250 | 303 | 303SD20-0016 MINOR STR. EXCAV. PIPE CULVERT | 201.000 CY | _____ | _____ | _____ | _____ |
| 0260 | 303 | 303SD20-0018 SLOPE DRAIN | 5.000 EA | _____ | _____ | _____ | _____ |
| 0270 | 303 | 303SD20-0019 EROSION CONTROL MULCH | 2,338.000 SY | _____ | _____ | _____ | _____ |
| 0280 | 303 | 303SD20-0021 TEMPORARY DIVERSION DIKE | 1,852.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01
 Order No.: K60

Oversight/State Project No.: 0095-020-818, B660, C501
 Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0290 | 303 | 303SD20-0022 CHECK DAM ROCK TY. I | 17.000 EA | _____ | _____ | _____ | _____ |
| 0300 | 303 | 303SD20-0023 CHECK DAM ROCK TY. II | 67.000 EA | _____ | _____ | _____ | _____ |
| 0310 | 303 | 303SD20-0028 DEWATERING BASIN EC-8 | 21.000 EA | _____ | _____ | _____ | _____ |
| 0320 | 303 | 303SD20-0029 SILTATION CONTROL EXCAVATION | 1,041.000 CY | _____ | _____ | _____ | _____ |
| 0330 | 303 | 303SD20-0030 INLET PROTECTION TYPE A | 10.000 EA | _____ | _____ | _____ | _____ |
| 0340 | 303 | 303SD20-0031 INLET PROTECTION TYPE B | 4.000 EA | _____ | _____ | _____ | _____ |
| 0350 | 303 | 303SD20-0033 TEMP. SILT FENCE TYPE B | 619.000 LF | _____ | _____ | _____ | _____ |
| 0360 | 303 | 303SD20-0034 TEMP. SILT FENCE TYPE A | 1,980.000 LF | _____ | _____ | _____ | _____ |
| 0370 | 303 | 303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION | 561.000 CY | _____ | _____ | _____ | _____ |
| 0380 | ATTD | 303SX20-0024 TEMP.VEH.WATERCOURSE CROSSING | 1.000 EA | _____ | _____ | _____ | _____ |
| 0390 | 305 | 305SD20-0001 BORROW EXCAVATION | 19,369.000 CY | _____ | _____ | _____ | _____ |
| 0400 | 305 | 305SD20-0005 SELECT MATL. TY. I MIN. CBR-30 | 8,062.000 TON | _____ | _____ | _____ | _____ |
| 0410 | 305 | 305SD20-0009 GEOTEXTILE SUBGRADE STAB. | 6,031.000 SY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0420 | 306 | 306SD20-0001 LIME | 47.000 TON | _____ | _____ | _____ | _____ |
| 0430 | 307 | 307SD20-0001 HYDRAULIC CEMENT | 368.000 TON | _____ | _____ | _____ | _____ |
| 0440 | ATTD | 308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26 | 66.000 TON | _____ | _____ | _____ | _____ |
| 0450 | 313 | 313SD20-0001 ASPH-STAB. OPEN-GRADED MATERIAL | 1,985.000 TON | _____ | _____ | _____ | _____ |
| 0460 | 315 | 315SD20-0002 ASPHALT CONCRETE TY. SM-12.5D CONST | 5,283.000 TON | _____ | _____ | _____ | _____ |
| 0470 | 315 | 315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST | 1,835.000 TON | _____ | _____ | _____ | _____ |
| 0480 | 315 | 315SD20-0011 ASPHALT CONCRETE TY. BM-25.0D CONST | 9,705.000 TON | _____ | _____ | _____ | _____ |
| 0490 | 315 | 315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT | 9,333.000 LF | _____ | _____ | _____ | _____ |
| 0500 | 315 | 315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST | 7.300 TON | _____ | _____ | _____ | _____ |
| 0510 | 591 | 315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH | 9,607.000 LF | _____ | _____ | _____ | _____ |
| 0520 | 307 | 315SX20-0013 FULL DEPTH RECLAMATION NS FULL DEPTH RECLAMATION | 22,058.000 SY | _____ | _____ | _____ | _____ |
| 0530 | 316 | 316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST. | 48.800 CY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0540 | 316 | 316SD20-0036 REINF. STEEL BRIDGE APPR. SLAB CONST. | 8,000.000 LB | _____ | _____ | _____ | _____ |
| 0550 | 317 | 317SP20-0004 STONE MATRIX ASPH. SMA- 12.5 64E-22 | 7,755.000 TON | _____ | _____ | _____ | _____ |
| 0560 | 317 | 317SP20-0006 STONE MATRIX ASPH. SMA- 19.0 64E-22 | 1,367.000 TON | _____ | _____ | _____ | _____ |
| 0570 | 401 | 401SD20-0001 STRUCTURE EXCAVATION CONST. | 921.000 CY | _____ | _____ | _____ | _____ |
| 0580 | 401 | 401SD20-0002 SELECT BACKFILL ABUTMENT ZONE | 2,712.000 TON | _____ | _____ | _____ | _____ |
| 0590 | 401 | 401SD20-0004 GEOCOMPOSITE WALL DRAIN | 259.000 SY | _____ | _____ | _____ | _____ |
| 0600 | 401 | 401SD20-0005 PIPE UNDERDRAIN 6" CONST. | 356.000 LF | _____ | _____ | _____ | _____ |
| 0610 | 403 | 403SD20-0006 STEEL PILES 12" | 2,593.000 LF | _____ | _____ | _____ | _____ |
| 0620 | 403 | 403SD20-0034 PILE POINT FOR 12" STEEL PILE | 83.000 EA | _____ | _____ | _____ | _____ |
| 0630 | 403 | 403SD20-0036 DRIVING TEST FOR 12" STEEL PILE | 359.000 LF | _____ | _____ | _____ | _____ |
| 0640 | ATTD | 403SX20-0001 DYNAMIC PILE TEST END BEARING PILES | 8.000 EA | _____ | _____ | _____ | _____ |
| 0650 | 403 403 | 403SX20-0016 PREBORING PILE 403 403 | 220.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0660 | 404 | 404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST. | 57.000 CY | _____ | _____ | _____ | _____ |
| 0670 | 404 | 404SD20-0009 BRIDGE DECK GROOVING CONST. | 1,170.000 SY | _____ | _____ | _____ | _____ |
| 0680 | 404 | 404SD20-0010 COVER DEPTH SURVEY CONST. | 204.000 SY | _____ | _____ | _____ | _____ |
| 0690 | 404 | 404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST. | 365.500 CY | _____ | _____ | _____ | _____ |
| 0700 | 406 | 406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST. | 16,210.000 LB | _____ | _____ | _____ | _____ |
| 0710 | 406 | 406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST. | 17,430.000 LB | _____ | _____ | _____ | _____ |
| 0720 | 406 | 406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST. | 18,490.000 LB | _____ | _____ | _____ | _____ |
| 0730 | 407 | 407SD20-0006 STR.STEEL PLATE GIRDER ASTM A709 GRADE50 | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0740 | 410 | 410SD20-0006 CONCRETE PARAPET 42" CONST. | 230.000 LF | _____ | _____ | _____ | _____ |
| 0750 | 411 | 411SX20-0002 ZONE COAT. EX. STR. ZONE COAT. EX. STR. | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0760 | 411 | 411SX20-0003 PRE. & OVERCOAT EX. STR. PRE. & OVERCOAT EX. STR. | LUMP SUM | LUMP SUM | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01 Oversight/State Project No.: 0095-020-818, B660, C501
 Order No.: K60 Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0770 | 411 | 411SX20-0005 ENV. PROT. & HEALTH & SAFETY ENV. PROT. & HEALTH & SAFETY | LUMP SUM | LUMP SUM | | | |
| 0780 | 411 | 411SX20-0006 DISPOSAL OF MATERIAL DISPOSAL OF MATERIAL | LUMP SUM | LUMP SUM | | | |
| 0790 | 412 | 412SD20-0034 H.E.S. PATCHING TYPE B | 18.000 SY | | | | |
| 0800 | 412 | 412SD20-0036 H.E.S. PATCHING TYPE C | 18.000 SY | | | | |
| 0810 | 412 | 412SD20-0040 RECONSTR. EXPAN. JOINT EXPANSION JOINT RECONSTRUCTION VES | 26.000 LF | | | | |
| 0820 | 412 | 412SD20-0042 EXPANSION JOINT RECONSTRUCTION HES | 225.000 LF | | | | |
| 0830 | 412 | 412SD20-0046 BACK WALL RECONSTRUCTION HES | 226.000 LF | | | | |
| 0840 | ATTD | 412SX20-0001 CONC. SURF. COLOR COATING | 714.000 SY | | | | |
| 0850 | 412 | 412SX20-0015 SUPERSTR. WID./REPAIR NS BR. SUPERSTR. WID./REPAIR V.E.S. PATCHING TYPE B | 2.000 SY | | | | |
| 0860 | 412 | 412SX20-0015 SUPERSTR. WID./REPAIR NS BR. SUPERSTR. WID./REPAIR V.E.S. PATCHING TYPE C | 2.000 SY | | | | |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0870 | ATTD | 412SX20-0017 BR. SUBSTR. WID./REPAIR RECONSTRUCT BACK WALL VES. | 26.000 LF | _____ | _____ | _____ | _____ |
| 0880 | 413 | 413SX20-0005 REM. PORT.OF EX.STR. REM. PORT.OF EX.STR. | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 0890 | 414 | 414SD20-0003 EROSION CTRL. STONE CL. I, EC-1 | 451.000 TON | _____ | _____ | _____ | _____ |
| 0900 | 414 | 414SD20-0008 DRY RIPRAP CL. AI | 50.000 TON | _____ | _____ | _____ | _____ |
| 0910 | 400 | 414SX20-0007 RIPRAP DRY RIPRAP CL. I HAND PLACED | 991.000 TON | _____ | _____ | _____ | _____ |
| 0920 | 415 | 415SD20-0002 CONCRETE SLAB SLOPE PROTECTION 4" | 114.000 SY | _____ | _____ | _____ | _____ |
| 0930 | 420 | 420SD20-0005 ADHESIVE BASED JT. SEALER CL. I, 3" CONST. | 313.000 LF | _____ | _____ | _____ | _____ |
| 0940 | 425 | 425SD20-0001 REMOVE ASPHALT CONCRETE OVERLAY | 966.000 SY | _____ | _____ | _____ | _____ |
| 0950 | 425 | 425SD20-0002 TYPE A MILLING 1/2" | 989.000 SY | _____ | _____ | _____ | _____ |
| 0960 | 425 | 425SD20-0014 PLC.HIGH EARLY MOD.CONC.OVERLAY | 895.000 SY | _____ | _____ | _____ | _____ |
| 0970 | 425 | 425SD20-0015 PLACE VERY EARLY MOD.CONC.OVERLAY | 95.000 SY | _____ | _____ | _____ | _____ |
| 0980 | 425 | 425SD20-0022 TYPE A HYDRO-DEMOLITION 1/2" | 989.000 SY | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 0990 | 425 425 | 425SX20-0003 FURN. HIGH EARLY LATEX MOD.CONC. 425 425 | 99.500 CY | _____ | _____ | _____ | _____ |
| 1000 | 425 425 | 425SX20-0004 FURN VERY EARLY LATEX MOD CONC. 425 425 | 10.600 CY | _____ | _____ | _____ | _____ |
| 1010 | 430 | 430SX20-0001 NBIS ACCESS, UNDER BRIDGE (STR. NO. 2003) | 1.000 DAY | _____ | _____ | _____ | _____ |
| 1020 | 501 | 501SD20-0004 UNDERDRAIN UD-4 | 8,344.000 LF | _____ | _____ | _____ | _____ |
| 1030 | 501 | 501SD20-0006 CROSSDRAIN CD-1 | 481.480 LF | _____ | _____ | _____ | _____ |
| 1040 | 501 | 501SD20-0009 OUTLET PIPE | 332.000 LF | _____ | _____ | _____ | _____ |
| 1050 | 502 | 502SD20-0003 PAVED DITCH PG-2A | 105.000 SY | _____ | _____ | _____ | _____ |
| 1060 | 502 | 502SD20-0004 PAVED DITCH PG-5 | 38.000 SY | _____ | _____ | _____ | _____ |
| 1070 | 502 | 502SD20-0020 CURB, ASPHALT MC-3B | 175.000 LF | _____ | _____ | _____ | _____ |
| 1080 | 502 | 502SD20-0036 MEDIAN BARRIER MB-7D | 40.000 LF | _____ | _____ | _____ | _____ |
| 1090 | 302, 504 | 504SD20-0001 CONCRETE CLASS A3 MISC. | 69.180 CY | _____ | _____ | _____ | _____ |
| 1100 | 504 | 504SD20-0005 GEOTEXTILE DRAINAGE FABRIC | 2,000.000 SY | _____ | _____ | _____ | _____ |
| 1110 | 505 | 505SD20-0011 GUARDRAIL GR-MGS1 | 5,285.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1120 | 505 | 505SD20-0013 GUARDRAIL GR-MGS1, 9' POST | 2,708.000 LF | _____ | _____ | _____ | _____ |
| 1130 | 505 | 505SD20-0017 GUARDRAIL TERMINAL GR- MGS2 | 1.000 EA | _____ | _____ | _____ | _____ |
| 1140 | 505 | 505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3 | 2.000 EA | _____ | _____ | _____ | _____ |
| 1150 | 505 | 505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4 | 4.000 EA | _____ | _____ | _____ | _____ |
| 1160 | 505 | 505SD20-0040 GUARDRAIL GR-10 | 129.000 LF | _____ | _____ | _____ | _____ |
| 1170 | 505 | 505SD20-0053 FIXED OBJECT ATTACH. GR- FOA-2 TY. I | 2.000 EA | _____ | _____ | _____ | _____ |
| 1180 | 505 | 505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II | 2.000 EA | _____ | _____ | _____ | _____ |
| 1190 | 505 | 505SD20-0073 REMOVE EXISTING GUARDRAIL | 6,813.000 LF | _____ | _____ | _____ | _____ |
| 1200 | ATTD | 506SX20-0004 WALL ANCHOR WALL | 296.000 LF | _____ | _____ | _____ | _____ |
| 1210 | 507 | 507SD20-0002 FENCE FE-W2 | 6,779.000 LF | _____ | _____ | _____ | _____ |
| 1220 | 507 | 507SD20-0016 LINE BRACE UNIT FE-B | 19.000 EA | _____ | _____ | _____ | _____ |
| 1230 | 507 | 507SD20-0017 CORNER BRACE UNIT FE-B | 22.000 EA | _____ | _____ | _____ | _____ |
| 1240 | 507 | 507SD20-0024 WATER GATE FE-4 TY.I | 4.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|---|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1250 | 507 | 507SD20-0025 WATER GATE FE-4 TY.II | 1.000 EA | _____ | _____ | _____ | _____ |
| 1260 | 507 | 507SD20-0026 WATER GATE FE-4 TY.III | 14.000 LF | _____ | _____ | _____ | _____ |
| 1270 | 507 | 507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET | 465.000 LF | _____ | _____ | _____ | _____ |
| 1280 | 508 | 508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE | 12,564.000 SY | _____ | _____ | _____ | _____ |
| 1290 | 510 | 510SX20-0016 REMOVE EXIST. FENCE BARBED & WOVEN WIRE FENCE | 7,015.000 LF | _____ | _____ | _____ | _____ |
| 1300 | ATTD | 510SX20-0022 RESET EXIST. NON STANDARD REMOVE FIBER OPTIC CABLE | 1,650.000 LF | _____ | _____ | _____ | _____ |
| 1310 | ATTD | 510SX20-0042 RELOCATE NON STANDARD RELOCATE POWER/CABLE POLE LINES | 1.000 EA | _____ | _____ | _____ | _____ |
| 1320 | 511 | 511SD20-0001 ALLAYING DUST | 200.000 HR | _____ | _____ | _____ | _____ |
| 1330 | 512 | 512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A | 17,810.000 LF | _____ | _____ | _____ | _____ |
| 1340 | 512 | 512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH | 9.000 EA | _____ | _____ | _____ | _____ |
| 1350 | 512 | 512SD20-0012 TYPE 3 BARRICADE 4' | 16.000 EA | _____ | _____ | _____ | _____ |
| 1360 | 512 | 512SD20-0013 TYPE 3 BARRICADE 8' | 10.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1370 | 512 | 512SD20-0014 TEMPORARY SIGN | 3,932.000 SF | _____ | _____ | _____ | _____ |
| 1380 | 512 | 512SD20-0023 TRUCK MOUNTED ATTENUATOR | 1,824.000 HR | _____ | _____ | _____ | _____ |
| 1390 | 512 | 512SD20-0024 GROUP 2 CHANNELIZING DEVICES | 13,190.000 DAY | _____ | _____ | _____ | _____ |
| 1400 | 512 | 512SD20-0025 PORT.CHANGEABLE MESS. SIGN | 2,240.000 HR | _____ | _____ | _____ | _____ |
| 1410 | 512 | 512SD20-0026 ELECTRONIC ARROW BOARD | 2,688.000 HR | _____ | _____ | _____ | _____ |
| 1420 | 512 | 512SD20-0029 WARNING LIGHT TY. B | 1,672.000 DAY | _____ | _____ | _____ | _____ |
| 1430 | 512 | 512SD20-0042 ERADICATE LINEAR PVMT MRKG | 84,927.000 LF | _____ | _____ | _____ | _____ |
| 1440 | 512 | 512SD20-0044 TEMP. PAVE. MARKER 1 WAY | 2,950.000 EA | _____ | _____ | _____ | _____ |
| 1450 | 512 | 512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6" | 9,940.000 LF | _____ | _____ | _____ | _____ |
| 1460 | 512 | 512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8" | 93,242.000 LF | _____ | _____ | _____ | _____ |
| 1470 | 510 | 512SX20-0019 TRAFFIC CONTROL TRUCKS ENTERING HIGHWAY SYSTEM | 18.000 EA | _____ | _____ | _____ | _____ |
| 1480 | 513 | 513SD20-0001 MOBILIZATION | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1490 | 514 | 514SD20-0001 FIELD OFFICE TY.I | 24.000 MO | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1500 | 515 | 515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2" | 57,808.000 SY | _____ | _____ | _____ | _____ |
| 1510 | 515 | 515SD20-0005 FLEXIBLE PAVE. PLANING ABOVE 2"-4" | 11,267.000 SY | _____ | _____ | _____ | _____ |
| 1520 | 517 | 517SD20-0001 CONSTRUCTION SURVEYING CONSTR. | LUMP SUM | LUMP SUM | _____ | _____ | _____ |
| 1530 | 521 | 521SD20-0001 MAILBOX POST, SINGLE | 1.000 EA | _____ | _____ | _____ | _____ |
| 1540 | 602 | 602SD20-0004 TOPSOIL CLASS B | 3,345.000 CY | _____ | _____ | _____ | _____ |
| 1550 | 603 | 603SD20-0002 TEMPORARY SEED | 1,255.000 LB | _____ | _____ | _____ | _____ |
| 1560 | 603 | 603SD20-0003 REGULAR SEED | 2,519.000 LB | _____ | _____ | _____ | _____ |
| 1570 | 603 | 603SD20-0004 OVERSEEDING | 2,015.000 LB | _____ | _____ | _____ | _____ |
| 1580 | 603 | 603SD20-0005 LEGUME SEED | 11.000 LB | _____ | _____ | _____ | _____ |
| 1590 | 603 | 603SD20-0006 LEGUME OVERSEEDING | 9.000 LB | _____ | _____ | _____ | _____ |
| 1600 | 603 | 603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2 | 3,557.000 SY | _____ | _____ | _____ | _____ |
| 1610 | 603 | 603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3 | 94,804.000 SY | _____ | _____ | _____ | _____ |
| 1620 | 603 | 603SD20-0014 FERTILIZER NITROGEN - N | 748.000 LB | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1630 | 603 | 603SD20-0015 FERTILIZER PHOSPHOROUS - P | 562.000 LB | _____ | _____ | _____ | _____ |
| 1640 | 603 | 603SD20-0016 FERTILIZER POTASSIUM - K | 562.000 LB | _____ | _____ | _____ | _____ |
| 1650 | 606 | 606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3 | 3,684.000 SY | _____ | _____ | _____ | _____ |
| 1660 | 606 | 606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1 | 690.000 SY | _____ | _____ | _____ | _____ |
| 1670 | 606 | 606SD20-0006 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2 | 1,340.000 SY | _____ | _____ | _____ | _____ |
| 1680 | 606 | 606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3 | 16.000 SY | _____ | _____ | _____ | _____ |
| 1690 | 700 | 700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE | 8.000 EA | _____ | _____ | _____ | _____ |
| 1700 | 700 | 700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE | 2.000 EA | _____ | _____ | _____ | _____ |
| 1710 | 700 | 700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL | 10.000 EA | _____ | _____ | _____ | _____ |
| 1720 | 700 | 700SD20-0008 REMOVE EXISTING 2 POST SIGN PANEL | 3.000 EA | _____ | _____ | _____ | _____ |
| 1730 | 700 | 700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL | 2.000 EA | _____ | _____ | _____ | _____ |
| 1740 | 700 | 700SD20-0018 VA SIGN POST W4 X 13 | 64.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1750 | 700 | 700SD20-0031 VIA SIGN POST W12 X 22 | 37.000 LF | _____ | _____ | _____ | _____ |
| 1760 | 700 | 700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE | 6.000 LF | _____ | _____ | _____ | _____ |
| 1770 | 700 | 700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE | 15.000 LF | _____ | _____ | _____ | _____ |
| 1780 | 700 | 700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE | 32.000 LF | _____ | _____ | _____ | _____ |
| 1790 | 700 | 700SD20-0038 CONC. FOUND. STP-1, TY. A | 2.000 EA | _____ | _____ | _____ | _____ |
| 1800 | 700 | 700SD20-0039 CONC. FOUND. STP-1, TY. B | 1.000 EA | _____ | _____ | _____ | _____ |
| 1810 | 700 | 700SD20-0046 CONC. FOUND. SSP-VA, 1'9" DIA. X 4'6" DEEP | 4.000 EA | _____ | _____ | _____ | _____ |
| 1820 | 700 | 700SD20-0049 CONC. FOUND. SSP-VIA, 3' DIA. X 7' DEEP | 2.000 EA | _____ | _____ | _____ | _____ |
| 1830 | 700 | 700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE | 140.000 CY | _____ | _____ | _____ | _____ |
| 1840 | 700 | 700SD20-0199 TEST BORE | 7.000 EA | _____ | _____ | _____ | _____ |
| 1850 | ATTD 700 | 700SX20-0003 SIGN STRUCTURE, OVERHEAD CANT. OVERHEAD SIGN STRUCTURE | 7.000 EA | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------|----------|--|--------------------------------|------------|-------|------------|-------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1860 | 510 | 700SX20-0016 RELOCATE EX. OVRHD SGN STR. SGN.PANEL RELOCATE EXISTING OVERHEAD SIGN STRUCTURE SIGN PANEL | 1.000 EA | _____ | _____ | _____ | _____ |
| 1870 | 700 | 700SX20-0019 TRAFFIC SIGN U-CHANNEL SIGN POST | 10.000 LF | _____ | _____ | _____ | _____ |
| 1880 | 510 | 700SX20-0021 TRAFFIC SIGN REMOVE AND DISPOSE CANTILEVER SIGN STRUCTURE AND SIGN PANEL | 5.000 EA | _____ | _____ | _____ | _____ |
| 1890 | 510 | 700SX20-0021 TRAFFIC SIGN REMOVE AND DISPOSE OVERHEAD SIGN STRUCTURE AND SIGN PANEL | 1.000 EA | _____ | _____ | _____ | _____ |
| 1900 | 701 | 701SD20-0001 SIGN PANEL | 2,228.000 SF | _____ | _____ | _____ | _____ |
| 1910 | 701 | 701SD20-0002 OVERLAY SIGN PANEL | 75.000 SF | _____ | _____ | _____ | _____ |
| 1920 | 704 | 704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6" | 26,715.000 LF | _____ | _____ | _____ | _____ |
| 1930 | 704 | 704SD20-0028 TYPE B CLASS VI PVMT LINE MRKG 8" | 3,225.000 LF | _____ | _____ | _____ | _____ |
| 1940 | 704 | 704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12" | 320.000 LF | _____ | _____ | _____ | _____ |
| 1950 | 704 | 704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6" | 760.000 LF | _____ | _____ | _____ | _____ |

Schedule of Items

Proposal ID: C0000111466C01

Oversight/State Project No.: 0095-020-818, B660, C501

Order No.: K60

Federal Project No.: NHFP-095-1(364)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

| Proposal Line Number | Spec No. | Item ID Description | Approximate Quantity and Units | Unit Price | | Bid Amount | |
|----------------------------|-------------|--|--------------------------------------|-------------------|--------|------------|--------|
| | | | | Dollars | Cents | Dollars | Cents |
| 1960 | ATTD | 704SD20-0032 INLAID PAVEMENT MARKER ASPHALT | 3,460.000 EA | _____. | _____. | _____. | _____. |
| 1970 | 704 | 704SX20-0001 PAVEMENT MARKING TYPE B CLASS VI PAVEMENT LINE MARKING 8" CONTRAST | 80.000 LF | _____. | _____. | _____. | _____. |
| Section: 0001 | | | | Total: | | _____. | |
| | | | | Total Bid: | | _____. | |