

Schedule of Items

Proposal ID: C000113030B08B      Oversight/State Project No.: 0178-001-704, B608, M501  
 Order No.: K49      Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	19.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	303	303SD20-0001 REGULAR EXCAVATION	276.000 CY				
0050	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM			
0060	303	303SD20-0014 SURCHARGE PLACEMENT & REMOVAL	880.000 CY				
0070	303	303SD20-0015 SETTLEMENT PLATE	4.000 EA				
0080	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA				
0090	303	303SD20-0029 SILTATION CONTROL EXCAVATION	270.000 CY				
0100	303	303SD20-0033 TEMP. SILT FENCE TYPE B	1,560.000 LF				
0110	303	303SX20-0022 EROSION CONTROL TURBIDITY CURTAIN, PERVIOUS	1,330.000 LF				
0120	305	305SD20-0001 BORROW EXCAVATION	1,000.000 CY				
0130	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	235.000 SY				

Schedule of Items

Proposal ID: C000113030B08B      Oversight/State Project No.: 0178-001-704, B608, M501  
 Order No.: K49      Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	308	308SD20-0001 AGGR. MATL. NO. 1	70.000 TON	_____	_____	_____	_____
0150	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	490.000 TON	_____	_____	_____	_____
0160	310	310SD20-0001 TACK COAT	1.000 GAL	_____	_____	_____	_____
0170	311	311SD20-0002 COVER MATL. AGGR. NO. 68	10.000 TON	_____	_____	_____	_____
0180	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	120.000 TON	_____	_____	_____	_____
0190	315	315SD20-0010 ASPHALT CONCRETE TY. BM-25.0A CONST	480.000 TON	_____	_____	_____	_____
0200	315	315SX20-0011 SAW-CUT ASPH CONC (7.5" AVERAGE DEPTH)	45.000 LF	_____	_____	_____	_____
0210	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	68.800 CY	_____	_____	_____	_____
0220	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	468.000 CY	_____	_____	_____	_____
0230	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	610.000 TON	_____	_____	_____	_____
0240	401	401SD20-0003 POROUS BACKFILL	36.000 CY	_____	_____	_____	_____
0250	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	22.000 SY	_____	_____	_____	_____
0260	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	94.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000113030B08B      Oversight/State Project No.: 0178-001-704, B608, M501  
 Order No.: K49      Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0280	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0290	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0300	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0310	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0320	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
0330	403	401SX20-0005 BRIDGE SUBSTRUCTURE DRIVING TEST -12" PSC CFRP STRAND PILE	108.000 LF	_____	_____	_____	_____
0340	402	402SD20-0001 SHEET PILES STEEL	22,291.000 SF	_____	_____	_____	_____
0350	403	403SD20-0004 DYNAMIC PILE TEST	4.000 EA	_____	_____	_____	_____
0360	403	403SD20-0023 PRESTR. CONC CFRP STRAND PILES 12"	348.000 LF	_____	_____	_____	_____
0370	403	403SD20-0027 PRESTR. CONC CFRP STRAND PILES 24"	326.000 LF	_____	_____	_____	_____
0380	403	403SD20-0053 DRIVING TEST -24" PSC CFRP STRAND PILE	100.000 LF	_____	_____	_____	_____
0390	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	115.200 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000113030B08B

Oversight/State Project No.: 0178-001-704, B608, M501

Order No.: K49

Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	497.000 SY	_____	_____	_____	_____
0410	404	404SD20-0010 COVER DEPTH SURVEY CONST.	364.000 SY	_____	_____	_____	_____
0420	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	51.400 CY	_____	_____	_____	_____
0430	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	37,185.000 LB	_____	_____	_____	_____
0440	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	4,700.000 LB	_____	_____	_____	_____
0450	407	407SX20-0004 STRUCT. STEEL STRUCTURAL STEEL PLATE GIRDER GRADE 50W-HDG	57,000.000 LB	_____	_____	_____	_____
0460	410	410SD20-0011 RAILING CPSR 2 RAIL CONST.	253.000 LF	_____	_____	_____	_____
0470	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY WORK BARGE	LUMP SUM	LUMP SUM	_____	_____	_____
0480	413	413SX20-0002 DISM.& REM. EX. STR. NO. 1007	LUMP SUM	LUMP SUM	_____	_____	_____
0490	414	414SX20-0004 DUMPED RIPRAP DRY CL. I 26"	931.000 SY	_____	_____	_____	_____
0500	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE B608	1.000 DAY	_____	_____	_____	_____
0510	ATTD	432SD20-0001 ELASTIC INCLUSION	10.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000113030B08B

Oversight/State Project No.: 0178-001-704, B608, M501

Order No.: K49

Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	502	502SD20-0014 CURB, STD. CG-3	110.000 LF	_____	_____	_____	_____
0530	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	3.000 EA	_____	_____	_____	_____
0540	505	505SD20-0011 GUARDRAIL GR-MGS1	1,040.000 LF	_____	_____	_____	_____
0550	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	3.000 EA	_____	_____	_____	_____
0560	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	3.000 EA	_____	_____	_____	_____
0570	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	4.000 EA	_____	_____	_____	_____
0580	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	1,080.000 LF	_____	_____	_____	_____
0590	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	110.000 LF	_____	_____	_____	_____
0600	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,295.000 SY	_____	_____	_____	_____
0610	510	510SX20-0041 REMOVE EXIST. PIER	LUMP SUM	LUMP SUM	_____	_____	_____
0620	511	511SD20-0001 ALLAYING DUST	65.000 HR	_____	_____	_____	_____
0630	512	512SD20-0012 TYPE 3 BARRICADE 4'	6.000 EA	_____	_____	_____	_____
0640	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000113030B08B

Oversight/State Project No.: 0178-001-704, B608, M501

Order No.: K49

Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	512	512SD20-0014 TEMPORARY SIGN	573.000 SF	_____	_____	_____	_____
0660	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	675.000 HR	_____	_____	_____	_____
0670	512	512SD20-0029 WARNING LIGHT TY. B	4,560.000 DAY	_____	_____	_____	_____
0680	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	40.000 LF	_____	_____	_____	_____
0690	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0700	514	514SD20-0003 FIELD OFFICE TY.III	19.000 MO	_____	_____	_____	_____
0710	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0720	602	602SD20-0003 TOPSOIL CLASS B 2"	0.210 ACRE	_____	_____	_____	_____
0730	602	602SX20-0005 TOPSOIL CLASS A 3"	0.190 ACRE	_____	_____	_____	_____
0740	603	603SD20-0002 TEMPORARY SEED	54.000 LB	_____	_____	_____	_____
0750	603	603SD20-0003 REGULAR SEED	70.000 LB	_____	_____	_____	_____
0760	603	603SD20-0004 OVERSEEDING	56.000 LB	_____	_____	_____	_____
0770	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,763.000 SY	_____	_____	_____	_____
0780	603	603SD20-0014 FERTILIZER NITROGEN - N	39.000 LB	_____	_____	_____	_____

Proposal ID: C000113030B08B

Oversight/State Project No.: 0178-001-704, B608, M501

Order No.: K49

Federal Project No.: NHPP-001-5 (064)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR ITEMS

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	54.000 LB	_____	_____	_____	_____
0800	603	603SD20-0016 FERTILIZER POTASSIUM - K	27.000 LB	_____	_____	_____	_____
0810	603	603SD20-0017 LIME	1.840 TON	_____	_____	_____	_____
0820	603	605SX20-0017 SEED MIXTURE WETLAND SEEDING	3.000 LB	_____	_____	_____	_____
0830	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	40.000 SY	_____	_____	_____	_____
0840	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	18.000 EA	_____	_____	_____	_____
0850	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	60.000 LF	_____	_____	_____	_____
0860	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	5.000 EA	_____	_____	_____	_____
0870	701	701SD20-0001 SIGN PANEL	50.000 SF	_____	_____	_____	_____
0880	704	704SD20-0026 TYPE B CLASS VI PVMT LINE MRKG 4"	2,000.000 LF	_____	_____	_____	_____
0890	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	610.000 LF	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	