

Schedule of Items

Proposal ID: C000110798C01B Oversight/State Project No.: 0011-119-811, C501
 Order No.: K56 Federal Project No.: STP-5119(130)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	302SD20-0001 BEDDING MATL.AGGR.NO. 25 OR 26	33.000 TON	_____	_____	_____	_____
0020	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0030	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. BEDDING MATL. FINE AGGR. TYPE A NATURAL SAND	0.500 TON	_____	_____	_____	_____
0040	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM		_____	_____
0050	303	303SD20-0029 SILTATION CONTROL EXCAVATION	40.000 CY	_____	_____	_____	_____
0060	303	303SD20-0030 INLET PROTECTION TYPE A	3.000 EA	_____	_____	_____	_____
0070	303	303SD20-0031 INLET PROTECTION TYPE B	5.000 EA	_____	_____	_____	_____
0080	ATTD	303SX20-0013 UTILITY TEST PIT ASPHALT CONCRETE	10.000 EA	_____	_____	_____	_____
0090	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	48.000 TON	_____	_____	_____	_____
0100	315	315SD20-0003 ASPHALT CONCRETE TY. SM-12.5E CONST	266.000 TON	_____	_____	_____	_____
0110	315	315SD20-0010 ASPHALT CONCRETE TY. BM-25.0A CONST	25.000 TON	_____	_____	_____	_____
0120	315	315SX20-0011 SAW-CUT ASPH CONC SAW-CUT ASPH CONC (18" DEPTH)	167.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000110798C01B Oversight/State Project No.: 0011-119-811, C501
 Order No.: K56 Federal Project No.: STP-5119(130)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	315	315SX20-0011 SAW-CUT ASPH CONC SAW-CUT ASPH CONC (3" DEPTH)	41.000 LF	_____	_____	_____	_____
0140	316	316SX20-0010 SAW-CUT HYDR.CEM.CONC.PAVE. SAW CUT CURB GUTTER AND ENTRANCES	18.000 LF	_____	_____	_____	_____
0150	316	316SX20-0010 SAW-CUT HYDR.CEM.CONC.PAVE. SAW CUT SIDEWALK	125.000 LF	_____	_____	_____	_____
0160	502	502SD20-0011 CURB, STD. CG-2	63.300 LF	_____	_____	_____	_____
0170	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	58.500 LF	_____	_____	_____	_____
0180	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	77.200 LF	_____	_____	_____	_____
0190	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	5.500 SY	_____	_____	_____	_____
0200	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	129.000 SY	_____	_____	_____	_____
0210	ATTD	504SX20-0009 SIDEWALK SIDEWALK RELAY EX. BRICK	10.000 SY	_____	_____	_____	_____
0220	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	32.000 SY	_____	_____	_____	_____
0230	302	510SX20-0034 ADJUST EXIST. MANHOLE ADJUST EXIST. MANHOLE FRAME AND COVER	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000110798C01B Oversight/State Project No.: 0011-119-811, C501
 Order No.: K56 Federal Project No.: STP-5119(130)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0240	512	512SD20-0012 TYPE 3 BARRICADE 4'	8.000 EA	_____	_____	_____	_____
0250	512	512SD20-0013 TYPE 3 BARRICADE 8'	9.000 EA	_____	_____	_____	_____
0260	512	512SD20-0014 TEMPORARY SIGN	562.000 SF	_____	_____	_____	_____
0270	512	512SD20-0016 TEMPORARY CURB RAMP	1.000 EA	_____	_____	_____	_____
0280	512	512SD20-0022 GROUP 2 LONGITUDINAL CHANNELIZING DEVICE	33.000 LF	_____	_____	_____	_____
0290	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	775.000 DAY	_____	_____	_____	_____
0300	512	512SD20-0027 FLAGGER SERVICE	500.000 HR	_____	_____	_____	_____
0310	512	512SD20-0029 WARNING LIGHT TY. B	8.000 DAY	_____	_____	_____	_____
0320	ATTD	512SX20-0045 SAFETY UNIFORMED FLAGGERS	120.000 HR	_____	_____	_____	_____
0330	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0340	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	2,340.000 SY	_____	_____	_____	_____
0350	516	516SX20-0008 DEMO. OF BLDG. DEMO. OF BLDG. PARCEL 001 D-1	LUMP SUM	LUMP SUM	_____	_____	_____
0360	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C000110798C01B Oversight/State Project No.: 0011-119-811, C501
 Order No.: K56 Federal Project No.: STP-5119(130)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	700	700SD20-0010 REMOVE EXIST OVERHEAD SIGNAL SIGN PANEL	1.000 EA	_____	_____	_____	_____
0380	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	30.000 LF	_____	_____	_____	_____
0390	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	1.000 EA	_____	_____	_____	_____
0400	700	700SD20-0066 PEDESTAL POLE PF-2, 10'	3.000 EA	_____	_____	_____	_____
0410	700	700SD20-0069 CONC. FOUND. PF-2	3.000 EA	_____	_____	_____	_____
0420	700	700SD20-0112 14/4 CONDUCTOR CABLE	700.000 LF	_____	_____	_____	_____
0430	700	700SD20-0120 14/2 CONDUCTOR CABLE SHIELDED	700.000 LF	_____	_____	_____	_____
0440	700	700SD20-0176 JUNCTION BOX JB-R2	3.000 EA	_____	_____	_____	_____
0450	700	700SD20-0192 BORED CONDUIT 3"	350.000 LF	_____	_____	_____	_____
0460	700	700SD20-0195 CONDUIT PVC 3"	50.000 LF	_____	_____	_____	_____
0470	700	700SD20-0197 TRENCH EXCAVATION ECI-1	100.000 LF	_____	_____	_____	_____
0480	701	701SD20-0001 SIGN PANEL	54.000 SF	_____	_____	_____	_____
0490	703	703SD20-0009 TRAF. SIG. HEAD SECT. 12" BLACK BACKPLATE	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C000110798C01B Oversight/State Project No.: 0011-119-811, C501
 Order No.: K56 Federal Project No.: STP-5119(130)

Contractor: _____

SECTION: 1 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	703	703SD20-0011 PEDESTRIAN ACTUATION PA-2	4.000 EA	_____	_____	_____	_____
0510	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	1.000 EA	_____	_____	_____	_____
0520	703	703SD20-0039 HANGER ASSEMBLY SMB-3, ONE WAY	2.000 EA	_____	_____	_____	_____
0530	703	703SD20-0040 HANGER ASSEMBLY SMB-3, TWO WAY	1.000 EA	_____	_____	_____	_____
0540	703	703SD20-0046 REMOVE EXISTING SIGNAL HEAD	1.000 EA	_____	_____	_____	_____
0550	703	703SD20-0060 PEDESTRIAN SIGNAL HEAD SP-8	4.000 EA	_____	_____	_____	_____
0560	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	1,500.000 LF	_____	_____	_____	_____
0570	704	704SD20-0014 TYPE B CLASS II PVMT LINE MRKG 12"	500.000 LF	_____	_____	_____	_____
0580	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	100.000 LF	_____	_____	_____	_____
0590	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	8.000 EA	_____	_____	_____	_____
0600	704	704SD20-0051 DBL TURN ARR. THRU/LT OR RT TY B, CL II	2.000 EA	_____	_____	_____	_____

Section: 1 Total: _____

Total Bid: _____