

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	24.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	302	302SD20-0023 15" PIPE	85.000 LF				
0050	302	302SD20-0027 15" STORM SEWER PIPE	592.000 LF				
0060	302	302SD20-0032 18" STORM SEWER PIPE	7.000 LF				
0070	302	302SD20-0037 24" PIPE	302.000 LF				
0080	302	302SD20-0041 24" STORM SEWER PIPE	120.000 LF				
0090	302	302SD20-0051 30" STORM SEWER PIPE	8.000 LF				
0100	302	302SD20-0061 36" STORM SEWER PIPE	122.000 LF				
0110	302	302SD20-0198 15" END SECTION ES-1 OR 2	13.000 EA				
0120	302	302SD20-0309 DROP INLET DI-3A	7.000 EA				
0130	302	302SD20-0312 DROP INLET DI-3B,L=6'	10.000 EA				
0140	302	302SD20-0329 DROP INLET DI-3C,L=6'	4.000 EA				

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0382 DROP INLET DI-4AA	2.000 EA	_____	_____	_____	_____
0160	302	302SD20-0400 DROP INLET DI-4C,L=10'	1.000 EA	_____	_____	_____	_____
0170	302	302SD20-0446 DROP INLET DI-5	2.000 EA	_____	_____	_____	_____
0180	302	302SD20-0670 TEMP. DIVE. CHANNEL LINING CL. A	360.000 SY	_____	_____	_____	_____
0190	302	302SD20-0672 TEMP. DIVE. CHANNEL EXCAVATION	90.000 CY	_____	_____	_____	_____
0200	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. 57	98.000 TON	_____	_____	_____	_____
0210	ATTD	302SX20-0022 DRAINAGE LEVEL SPREADER	18.000 EA	_____	_____	_____	_____
0220	ATTD	302SX20-0022 DRAINAGE PERMANENT ROCK CHECK DAM	1.000 EA	_____	_____	_____	_____
0230	ATTD	302SX20-0022 DRAINAGE SPECIAL DESIGN TRENCH DRAIN L=18'	2.000 EA	_____	_____	_____	_____
0240	ATTD	302SX20-0022 DRAINAGE SPECIAL DESIGN TRENCH DRAIN L=20'	3.000 EA	_____	_____	_____	_____
0250	303	303SD20-0001 REGULAR EXCAVATION	19,799.000 CY	_____	_____	_____	_____
0260	303	303SD20-0013 GEOTEXTILE EMBANKMENT STAB.	32,435.000 SY	_____	_____	_____	_____
0270	303	303SD20-0016 MINOR STR. EXCAV. PIPE CULVERT	49.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	303	303SD20-0022 CHECK DAM ROCK TY. I	5.000 EA	_____	_____	_____	_____
0290	303	303SD20-0023 CHECK DAM ROCK TY. II	57.000 EA	_____	_____	_____	_____
0300	303	303SD20-0028 DEWATERING BASIN EC-8	21.000 EA	_____	_____	_____	_____
0310	303	303SD20-0029 SILTATION CONTROL EXCAVATION	4,312.000 CY	_____	_____	_____	_____
0320	303	303SD20-0030 INLET PROTECTION TYPE A	5.000 EA	_____	_____	_____	_____
0330	303	303SD20-0031 INLET PROTECTION TYPE B	46.000 EA	_____	_____	_____	_____
0340	303	303SD20-0033 TEMP. SILT FENCE TYPE B	18,519.000 LF	_____	_____	_____	_____
0350	303	303SD20-0034 TEMP. SILT FENCE TYPE A	4,654.000 LF	_____	_____	_____	_____
0360	303	303SX20-0006 BORROW EXCAVATION MIN. CBR-15	34,397.000 CY	_____	_____	_____	_____
0370	ATTD	303SX20-0024 TEMP.VEH.WATERCOURSE CROSSING	2.000 EA	_____	_____	_____	_____
0380	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	4,610.000 SY	_____	_____	_____	_____
0390	306	306SD20-0001 LIME	19.970 TON	_____	_____	_____	_____
0400	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	7,354.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	387.000 TON	_____	_____	_____	_____
0420	ATTD	309SX20-0001 AGGR. MATERIAL (SELF COMPACTING FILL)	1,026.000 TON	_____	_____	_____	_____
0430	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	1,889.000 TON	_____	_____	_____	_____
0440	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	451.000 TON	_____	_____	_____	_____
0450	315	315SD20-0010 ASPHALT CONCRETE TY. BM-25.0A CONST	3,920.000 TON	_____	_____	_____	_____
0460	315	315SX20-0011 SAW-CUT ASPH CONC ASPHALT PAVEMENT AVERAGE DEPTH 7"	204.000 LF	_____	_____	_____	_____
0470	315	315SX20-0011 SAW-CUT ASPH CONC COMBINATION PAVEMENT AVERAGE DEPTH 21"	1,516.000 LF	_____	_____	_____	_____
0480	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	31.000 TON	_____	_____	_____	_____
0490	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	15.000 TON	_____	_____	_____	_____
0500	501	501SD20-0002 UNDERDRAIN UD-2	379.000 LF	_____	_____	_____	_____
0510	501	501SD20-0004 UNDERDRAIN UD-4	387.000 LF	_____	_____	_____	_____
0520	501	501SD20-0009 OUTLET PIPE	6.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	502	502SD20-0003 PAVED DITCH PG-2A	10.000 SY	_____	_____	_____	_____
0540	502	502SD20-0004 PAVED DITCH PG-5	46.600 SY	_____	_____	_____	_____
0550	502	502SD20-0014 CURB, STD. CG-3	57.000 LF	_____	_____	_____	_____
0560	502	502SD20-0015 CURB, RADIAL CG-3	13.000 LF	_____	_____	_____	_____
0570	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	8,707.000 LF	_____	_____	_____	_____
0580	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	169.000 LF	_____	_____	_____	_____
0590	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	418.000 LF	_____	_____	_____	_____
0600	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	433.000 LF	_____	_____	_____	_____
0610	502	502SD20-0029 ENTRANCE GUTTER CG-9D	132.000 SY	_____	_____	_____	_____
0620	502	502SD20-0052 DIRECTIONAL ISLAND CURB SI-3	137.000 LF	_____	_____	_____	_____
0630	502	502SD20-0058 MEDIAN STRIP MS-2	832.000 LF	_____	_____	_____	_____
0640	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	10.100 CY	_____	_____	_____	_____
0650	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	3.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	31.000 SY	_____	_____	_____	_____
0670	508	508SD20-0001 OBSCURING ROADWAY	15.000 UNIT	_____	_____	_____	_____
0680	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	569.000 SY	_____	_____	_____	_____
0690	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	637.000 SY	_____	_____	_____	_____
0700	509	509SD20-0001 FLOWABLE BACKFILL	36.000 CY	_____	_____	_____	_____
0710	510	510SX20-0016 REMOVE EXIST. FENCE .	535.000 LF	_____	_____	_____	_____
0720	510	510SX20-0033 ADJUST EXIST. DROP INLET CONNECT PIPE	1.000 EA	_____	_____	_____	_____
0730	511	511SD20-0001 ALLAYING DUST	250.000 HR	_____	_____	_____	_____
0740	512	512SD20-0012 TYPE 3 BARRICADE 4'	3.000 EA	_____	_____	_____	_____
0750	512	512SD20-0013 TYPE 3 BARRICADE 8'	7.000 EA	_____	_____	_____	_____
0760	512	512SD20-0014 TEMPORARY SIGN	1,503.000 SF	_____	_____	_____	_____
0770	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	5,933.000 HR	_____	_____	_____	_____
0780	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	81,921.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001

ROADWAY BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	512	512SD20-0026 ELECTRONIC ARROW BOARD	4,484.000 HR	_____	_____	_____	_____
0800	512	512SD20-0027 FLAGGER SERVICE	1,449.000 HR	_____	_____	_____	_____
0810	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	400.000 LF	_____	_____	_____	_____
0820	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	102.000 SF	_____	_____	_____	_____
0830	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	12,976.000 LF	_____	_____	_____	_____
0840	512	512SD20-0065 TEMP. PVMT MRKG TY. D, CL. III, 24"	552.000 LF	_____	_____	_____	_____
0850	512	512SD20-0066 TRAFFIC BARRIER SERVICE CONC.	80.000 LF	_____	_____	_____	_____
0860	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	242.000 DAY	_____	_____	_____	_____
0870	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0880	514	514SD20-0001 FIELD OFFICE TY.I	25.000 MO	_____	_____	_____	_____
0890	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	2,798.000 SY	_____	_____	_____	_____
0900	516	516SX20-0008 DEMO. OF BLDG. REMOVAL OF EXISTING BUILDING (D-1)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001

ROADWAY BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	516	516SX20-0008 DEMO. OF BLDG. REMOVAL OF EXISTING PROPANE TANK (D-900)	LUMP SUM	LUMP SUM			
0920	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0930	520	520SD20-0002 3/4" WATER SERVICE LINE	5.000 LF				
0940	520	520SD20-0014 6" DI WATER MAIN	8.000 LF				
0950	520	520SD20-0024 16" DI WATER MAIN	641.000 LF				
0960	520	520SD20-0041 16" BEND	8.000 EA				
0970	520	520SD20-0049 16" BRANCH	1.000 EA				
0980	520	520SD20-0089 6" GATE VALVE & BOX	1.000 EA				
0990	520	520SD20-0162 FIRE HYDRANT	1.000 EA				
1000	520	520SD20-0170 5/8" WATER METER & BOX	1.000 EA				
1010	520	520SD20-0201 16" SANITARY SEWER FORCE MAIN	624.000 LF				
1020	520	520SD20-0227 16" BEND FORCE MAIN	6.000 EA				
1030	ATTD	522SP20-0001 WETLAND NONTIDAL WETLAND TEMPORARY WETLAND SEEDING	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001

ROADWAY BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	601	601SD20-0001 SEL TREE REMOVAL TRIM AND CLEAN	0.050 ACRE	_____	_____	_____	_____
1050	602	602SD20-0003 TOPSOIL CLASS B 2"	3.360 ACRE	_____	_____	_____	_____
1060	603	603SD20-0002 TEMPORARY SEED	821.000 LB	_____	_____	_____	_____
1070	603	603SD20-0003 REGULAR SEED	588.000 LB	_____	_____	_____	_____
1080	603	603SD20-0004 OVERSEEDING	470.000 LB	_____	_____	_____	_____
1090	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	13,371.000 SY	_____	_____	_____	_____
1100	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	46,694.000 SY	_____	_____	_____	_____
1110	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	34,764.000 LF	_____	_____	_____	_____
1120	603	603SD20-0014 FERTILIZER NITROGEN - N	412.000 LB	_____	_____	_____	_____
1130	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	623.000 LB	_____	_____	_____	_____
1140	603	603SD20-0016 FERTILIZER POTASSIUM - K	311.000 LB	_____	_____	_____	_____
1150	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	1,131.000 SY	_____	_____	_____	_____
1160	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	43.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001

ROADWAY BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1170	608	608SD20-0001 MOWING	200.000 HR	_____	_____	_____	_____
1180	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	19.000 EA	_____	_____	_____	_____
1190	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
1200	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	31.000 EA	_____	_____	_____	_____
1210	700	700SD20-0008 REMOVE EXISTING 2 POST SIGN PANEL	5.000 EA	_____	_____	_____	_____
1220	700	700SD20-0013 RELOCATE EX. 2 POST GRND MOUNT SGN PANEL	5.000 EA	_____	_____	_____	_____
1230	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	109.000 LF	_____	_____	_____	_____
1240	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	162.000 LF	_____	_____	_____	_____
1250	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	429.000 LF	_____	_____	_____	_____
1260	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	180.000 LF	_____	_____	_____	_____
1270	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	27.000 EA	_____	_____	_____	_____
1280	700	700SD20-0041 CONC. FOUND. STP-1, TY. D	7.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501
 Order No.: K79 Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1290	700	700SD20-0042 CONC. FOUND. STP-1, TY. E	15.000 EA	_____	_____	_____	_____
1300	700	700SD20-0068 CONC. FOUND. PF-8	27.000 CY	_____	_____	_____	_____
1310	700	700SD20-0095 SIGNAL MAST ARM POLE MP-3, TY. E1	1.000 EA	_____	_____	_____	_____
1320	700	700SD20-0097 SIGNAL MAST ARM POLE MP-3, TY. F	1.000 EA	_____	_____	_____	_____
1330	700	700SD20-0100 MAST ARM 49'	1.100 EA	_____	_____	_____	_____
1340	700	700SD20-0101 MAST ARM 60'	1.000 EA	_____	_____	_____	_____
1350	700	700SD20-0104 MAST ARM 75', CASE 1 LOADING	1.000 EA	_____	_____	_____	_____
1360	700	700SD20-0108 8/3 CONDUCTOR CABLE	40.000 LF	_____	_____	_____	_____
1370	700	700SD20-0114 14/7 CONDUCTOR CABLE	2,130.000 LF	_____	_____	_____	_____
1380	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	4,440.000 LF	_____	_____	_____	_____
1390	700	700SD20-0120 14/2 CONDUCTOR CABLE SHIELDED	4,995.000 LF	_____	_____	_____	_____
1400	700	700SD20-0133 ELECTRICAL SERVICE SE-3, TY. B	1.000 EA	_____	_____	_____	_____
1410	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501
 Order No.: K79 Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	700	700SD20-0177 JUNCTION BOX JB-S1	2.000 EA	_____	_____	_____	_____
1430	700	700SD20-0178 JUNCTION BOX JB-S2	15.000 EA	_____	_____	_____	_____
1440	700	700SD20-0179 JUNCTION BOX JB-S3	5.000 EA	_____	_____	_____	_____
1450	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
1460	700	700SD20-0182 CONDUIT PVC 1"	105.000 LF	_____	_____	_____	_____
1470	700	700SD20-0191 BORED CONDUIT 2"	450.000 LF	_____	_____	_____	_____
1480	700	700SD20-0192 BORED CONDUIT 3"	790.000 LF	_____	_____	_____	_____
1490	700	700SD20-0194 CONDUIT PVC 2"	2,300.000 LF	_____	_____	_____	_____
1500	700	700SD20-0195 CONDUIT PVC 3"	1,940.000 LF	_____	_____	_____	_____
1510	700	700SD20-0197 TRENCH EXCAVATION ECI-1	2,555.000 LF	_____	_____	_____	_____
1520	700	700SD20-0199 TEST BORE	2.000 EA	_____	_____	_____	_____
1530	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION ATC CABINET 4-DOOR CONFIGURATION (16 CHANNEL, LV.)	1.000 EA	_____	_____	_____	_____
1540	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION McCAIN ATC 2070 CONTROLLER WITH D-4 FIRMWARE	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01

Oversight/State Project No.: 0669-046-682,C501

Order No.: K79

Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001

ROADWAY BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1550	ATTD	700SX20-0022 CONC FOUNDATION CONCRETE FOUNDATION CF-5	1.000 EA	_____	_____	_____	_____
1560	701	701SD20-0001 SIGN PANEL	541.000 SF	_____	_____	_____	_____
1570	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	32.000 EA	_____	_____	_____	_____
1580	703	703SD20-0022 EVP DETECTION SYSTEM 3-WAY	1.000 EA	_____	_____	_____	_____
1590	703	703SD20-0024 EVP DETECTOR CABLE	940.000 LF	_____	_____	_____	_____
1600	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	10.000 EA	_____	_____	_____	_____
1610	703	703SD20-0042 LOOP SAW CUT 3/8"	1,416.000 LF	_____	_____	_____	_____
1620	703	703SD20-0043 LOOP SAW CUT 5/8"	175.000 LF	_____	_____	_____	_____
1630	703	703SD20-0053 UNINTERRUPT. PWR SUPPLY TYPE 2	1.000 EA	_____	_____	_____	_____
1640	ATTD	703SX20-0003 DETECTOR LONG LOOP DETECTOR AMPLIFIER	14.000 EA	_____	_____	_____	_____
1650	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	11,370.000 LF	_____	_____	_____	_____
1660	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	4,250.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000109314C01 Oversight/State Project No.: 0669-046-682,C501
 Order No.: K79 Federal Project No.: STP-5B03(384)

Contractor: _____

SECTION: 0001 ROADWAY BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1670	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	210.000 LF	_____	_____	_____	_____
1680	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	11.000 EA	_____	_____	_____	_____
1690	704, ATTD	704SX20-0005 PAVE. MESSAGE MARKING TEMP PAVEMENT MESSAGE ARROW TYPE D, CLASS III	32.000 EA	_____	_____	_____	_____
1700	808	808SD20-0002 FIBER OPTIC CABLE 48 STRAND	2,780.000 LF	_____	_____	_____	_____
1710	808	808SD20-0004 FIBER OPTIC DROP CABLE 12 STRAND	1,555.000 LF	_____	_____	_____	_____
1720	808	808SD20-0005 PRE-TERMINATED FIBER PATCH PANEL	2.000 EA	_____	_____	_____	_____
1730	808	808SD20-0006 UNDERGROUND SPLICE ENCLOSURE	4.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____