

Schedule of Items

Proposal ID: C0000121349B86      Oversight/State Project No.: 0646-013-008, B686  
 Order No.: L19      Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEM

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0001 REGULAR EXCAVATION	431.000 CY				
0030	303	303SD20-0023 CHECK DAM ROCK TY. II	1.000 EA				
0040	303	303SD20-0028 DEWATERING BASIN EC-8	4.000 EA				
0050	303	303SD20-0029 SILTATION CONTROL EXCAVATION	73.000 CY				
0060	303	303SD20-0034 TEMP. SILT FENCE TYPE A	356.000 LF				
0070	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	365.000 TON				
0080	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	51.000 TON				
0090	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	49.500 TON				
0100	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	12.500 TON				
0110	315	315SD20-0010 ASPHALT CONCRETE BM-25.0A CONST	75.000 TON				
0120	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE	36.000 LF				
0130	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	321.000 CY				

Schedule of Items

Proposal ID: C0000121349B86 Oversight/State Project No.: 0646-013-008, B686

Order No.: L19

Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEM

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	270.000 TON	_____	_____	_____	_____
0150	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	26.000 SY	_____	_____	_____	_____
0160	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	108.000 LF	_____	_____	_____	_____
0170	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0180	ATTD	401SX20-0009 BRIDGE SUBSTRUCTURE CHOKING MATERIAL	62.000 TON	_____	_____	_____	_____
0190	402	402SD20-0001 SHEET PILES STEEL	620.000 SF	_____	_____	_____	_____
0200	403	403SD20-0006 STEEL PILES 12"	328.000 LF	_____	_____	_____	_____
0210	ATTD	403SX20-0016 PREBORING PILE .	310.000 LF	_____	_____	_____	_____
0220	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	33.000 CY	_____	_____	_____	_____
0230	ATTD, 404	404SP20-0003 VA ADJACENT MEMBER CONN. BLOCK-OUTS	72.000 CF	_____	_____	_____	_____
0240	405	405SD20-0011 PREST.CONC.SLAB 3'X18"X(+35'-40')	10.000 EA	_____	_____	_____	_____
0250	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	380.000 LB	_____	_____	_____	_____
0260	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	4,910.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121349B86

Oversight/State Project No.: 0646-013-008, B686

Order No.: L19

Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY DETOUR BRIDGE	LUMP SUM	LUMP SUM			
0280	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING	LUMP SUM	LUMP SUM			
0290	413	413SX20-0002 DISM.& REM. EX. STR. (STR. NO. 6084)	LUMP SUM	LUMP SUM			
0300	411	413SX20-0004 MATERIAL DISPOSAL (STR. NO. 6084)	LUMP SUM	LUMP SUM			
0310	414	414SD20-0012 DRY RIPRAP CL.I 26"	195.000 TON				
0320	ATTD	432SD20-0001 ELASTIC INCLUSION	7.200 CY				
0330	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	50.000 LF				
0340	505	505SD20-0074 GUARDRAIL, THRIE BEAM	78.000 LF				
0350	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	331.000 SY				
0360	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	40.000 LF				
0370	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA				
0380	512	512SD20-0014 TEMPORARY SIGN	269.000 SF				

Schedule of Items

Proposal ID: C0000121349B86

Oversight/State Project No.: 0646-013-008, B686

Order No.: L19

Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	56.000 HR	_____	_____	_____	_____
0400	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	1,776.000 DAY	_____	_____	_____	_____
0410	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	128.000 HR	_____	_____	_____	_____
0420	512	512SD20-0027 FLAGGER SERVICE	80.000 HR	_____	_____	_____	_____
0430	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0440	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0450	520	520SD20-0002 3/4" WATER SERVICE LINE	56.000 LF	_____	_____	_____	_____
0460	520	520SD20-0090 8" GATE VALVE & BOX	4.000 EA	_____	_____	_____	_____
0470	520	520SD20-0167 5/8" WATER METER BOX & YOKE	1.000 EA	_____	_____	_____	_____
0480	602	602SD20-0002 TOPSOIL CLASS A	81.000 CY	_____	_____	_____	_____
0490	603	603SD20-0002 TEMPORARY SEED	400.000 LB	_____	_____	_____	_____
0500	603	603SD20-0003 REGULAR SEED	83.000 LB	_____	_____	_____	_____
0510	603	603SD20-0004 OVERSEEDING	66.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121349B86      Oversight/State Project No.: 0646-013-008, B686  
 Order No.: L19      Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEM

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	603	603SD20-0005 LEGUME SEED	1.000 LB	_____	_____	_____	_____
0530	603	603SD20-0006 LEGUME OVERSEEDING	1.000 LB	_____	_____	_____	_____
0540	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,210.000 SY	_____	_____	_____	_____
0550	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	10,285.000 SY	_____	_____	_____	_____
0560	603	603SD20-0014 FERTILIZER NITROGEN - N	64.000 LB	_____	_____	_____	_____
0570	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	55.000 LB	_____	_____	_____	_____
0580	603	603SD20-0016 FERTILIZER POTASSIUM - K	55.000 LB	_____	_____	_____	_____
0590	603	603SD20-0017 LIME	5.050 TON	_____	_____	_____	_____
0600	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	4.000 EA	_____	_____	_____	_____
0610	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	30.000 LF	_____	_____	_____	_____
0620	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	4.000 EA	_____	_____	_____	_____
0630	701	701SD20-0001 SIGN PANEL	12.000 SF	_____	_____	_____	_____
0640	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	400.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000121349B86  
Order No.: L19

Oversight/State Project No.: 0646-013-008, B686  
Federal Project No.: STP-BR01(399)

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_