

Schedule of Items

Proposal ID: CM225PMK125708 Oversight/State Project No.: PM2K-962-F25, P401

Order No.: 261

Federal Project No.: PM02(492)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	827.400 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	11,853.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	6,390.000 LF	_____	_____	_____	_____
0040	315	315SD20-0019 LIQUID ASPHALT COATING (RUMBLE STRIP)	1,065.000 SY	_____	_____	_____	_____
0050	315	315SD20-0043 ASPH. CONC. TY. IM-19.0D MAINT	2,583.010 TON	_____	_____	_____	_____
0060	315	315SD20-0100 ASPHALT CONCRETE BASE COURSE BM-25.0	518.360 TON	_____	_____	_____	_____
0070	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	49,843.000 LF	_____	_____	_____	_____
0080	315	315SP20-0048 ASPH. CONC. BMD P+VO SM- 9.5A	9,083.040 TON	_____	_____	_____	_____
0090	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	1,711.310 TON	_____	_____	_____	_____
0100	512	512SD20-0027 FLAGGER SERVICE	2,300.000 HR	_____	_____	_____	_____
0110	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	161,194.000 LF	_____	_____	_____	_____
0120	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	113,774.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM225PMK125708 Oversight/State Project No.: PM2K-962-F25, P401
 Order No.: 261 Federal Project No.: PM02(492)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC PLANT MIX	LUMP SUM	LUMP SUM			
0140	ATTD	512SX20-0005 TEMP. PVMT MRKG TEMP. PAVE. MESS. MARK (STOP BAR 12")	31.000 LF				
0150	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	80,189.630 SY				
0160	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	17,661.600 SY				
0170	515	515SD20-0015 FLEXIBLE PAVEMENT PLANING ABOVE 4"	1,742.400 SY				
0180	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	137,600.000 LF				
0190	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	31.000 LF				
Section: 0001				Total:			

SECTION: 0002 ALTERNATE BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0200	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON				
Section: 0002				Total:			

Total Bid: _____.