

Schedule of Items

Proposal ID: CM425PMD125589 Oversight/State Project No.: PM4D-964-F25, P401

Order No.: 469

Federal Project No.: PM04(531)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	1,873.660 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	29,745.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0043 ASPH. CONC. TY. IM-19.0D MAINT	2,129.600 TON	_____	_____	_____	_____
0040	315	315SD20-0052 RUMBLE STRIP SINUSOIDAL ASPHALT	41,983.000 LF	_____	_____	_____	_____
0050	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	64,596.000 LF	_____	_____	_____	_____
0060	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	10,127.170 TON	_____	_____	_____	_____
0070	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	17,218.630 TON	_____	_____	_____	_____
0080	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	1,757.390 TON	_____	_____	_____	_____
0090	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	583,309.000 LF	_____	_____	_____	_____
0100	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	145.000 LF	_____	_____	_____	_____
0110	512	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM	_____	_____	_____
0120	512	512SX20-0045 SAFETY NS SAFETY SHORT TERM ALTERNATING LANE CLOSURE FLAGGING/AFAD SERVICE	2,675.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM425PMD125589 Oversight/State Project No.: PM4D-964-F25, P401

Order No.: 469

Federal Project No.: PM04(531)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"-2"	258,711.940 SY	_____	_____	_____	_____
0140	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	19,360.000 SY	_____	_____	_____	_____
0150	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	225,903.000 LF	_____	_____	_____	_____
0160	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	65,722.000 LF	_____	_____	_____	_____
0170	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	356.000 LF	_____	_____	_____	_____
0180	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	145.000 LF	_____	_____	_____	_____
0190	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	222.000 EA	_____	_____	_____	_____
0200	704	704SD20-0041 PVMT MSG. MARK. R/R CROSSING TY. B, CL. I	1.000 EA	_____	_____	_____	_____
0210	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	9.000 EA	_____	_____	_____	_____
0220	704	704SD20-0110 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 8'	1.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>	_____	_____	_____

Schedule of Items

Proposal ID: CM425PMD125589 Oversight/State Project No.: PM4D-964-F25, P401

Order No.: 469

Federal Project No.: PM04(531)

Contractor: \_\_\_\_\_

SECTION: 0002 ALTERNATE BID ITEM

Cat Alt Set ID: \_\_\_\_\_ Cat Alt Mbr ID: \_\_\_\_\_

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0230	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
<b>Section: 0002</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____