

Schedule of Items

Proposal ID: C0000122865N01

Oversight/State Project No.: 9999-962-828, N501

Order No.: M11

Federal Project No.: HSIP-962-2(146)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0023 CHECK DAM ROCK TY. II	18.000 EA				
0030	303	303SD20-0029 SILTATION CONTROL EXCAVATION	1,690.000 CY				
0040	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA				
0050	303	303SD20-0031 INLET PROTECTION TYPE B	7.000 EA				
0060	303	303SD20-0034 TEMP. SILT FENCE TYPE A	9,543.000 LF				
0070	ATTD	303SX20-0008 GEOTEXTILE EMBANKMENT STABILIZATION	693.000 SY				
0080	ATTD	303SX20-0008 GEOTEXTILE GEOGRID	5,200.000 SY				
0090	ATTD	303SX20-0012 UTILITY TEST PIT UNPAVED	9.000 EA				
0100	ATTD	303SX20-0013 UTILITY TEST PIT ASPHALT CONCRETE	9.000 EA				
0110	ATTD	305SX20-0002 AGGR. MATL NO. 3	25.000 TON				
0120	ATTD	305SX20-0006 SELECT MATERIAL TY. I. MIN. CBR-30	1,100.000 TON				
0130	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	4,885.000 TON				

Schedule of Items

Proposal ID: C0000122865N01 Oversight/State Project No.: 9999-962-828, N501
 Order No.: M11 Federal Project No.: HSIP-962-2(146)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	4,134.000 SY	_____	_____	_____	_____
0150	315	315SD20-0029 ASPH. CONC. TY. SM-9.5D MAINT	2,303.000 TON	_____	_____	_____	_____
0160	315	315SD20-0052 RUMBLE STRIP SINUSOIDAL ASPHALT	62,947.000 LF	_____	_____	_____	_____
0170	321	321SD20-0002 ASPH. CONC. TY. IM-19.0D T MAINT	3,768.000 TON	_____	_____	_____	_____
0180	321	321SD20-0003 ASPH. CONC. TY. BM-25.0 T MAINT	4,728.000 TON	_____	_____	_____	_____
0190	322	322SD20-0002 CRACK SEALANT/FILLER TYPE B	13,862.000 LB	_____	_____	_____	_____
0200	ATTD	414SX20-0007 RIPRAP DRY RIPRAP CL. I 26"	203.000 TON	_____	_____	_____	_____
0210	505	505SD20-0008 ADJUST EXISTING GUARDRAIL BEAM	225.000 LF	_____	_____	_____	_____
0220	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	31.000 EA	_____	_____	_____	_____
0230	505	505SD20-0011 GUARDRAIL GR-MGS1	4,791.500 LF	_____	_____	_____	_____
0240	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	2,976.000 LF	_____	_____	_____	_____
0250	505	505SD20-0017 GUARDRAIL TERMINAL GR-MGS2	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122865N01

Oversight/State Project No.: 9999-962-828, N501

Order No.: M11

Federal Project No.: HSIP-962-2(146)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	14.000 EA	_____	_____	_____	_____
0270	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	7.000 EA	_____	_____	_____	_____
0280	505	505SD20-0038 ALT.BREAKAWAY CABLE TERM. GR-9	3.000 EA	_____	_____	_____	_____
0290	505	505SD20-0071 GUARDRAIL BEAM	50.000 LF	_____	_____	_____	_____
0300	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	9,033.000 LF	_____	_____	_____	_____
0310	ATTD	505SX20-0001 HAND DIG GUARDRAIL POST .	20.000 EA	_____	_____	_____	_____
0320	ATTD	505SX20-0004 GUARDRAIL TERMINAL SITE PREPARATION (4' MODERATE)	3.000 EA	_____	_____	_____	_____
0330	ATTD	505SX20-0004 GUARDRAIL TERMINAL SITE PREPARATION (6' MODERATE)	6.000 EA	_____	_____	_____	_____
0340	508	508SD20-0003 DEMO. OF PAVEMENT RIGID	5.000 SY	_____	_____	_____	_____
0350	510	510SD20-0001 REMOVE GR-7 TERMINAL	2.000 EA	_____	_____	_____	_____
0360	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	2,825.000 LF	_____	_____	_____	_____
0370	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122865N01

Oversight/State Project No.: 9999-962-828, N501

Order No.: M11

Federal Project No.: HSIP-962-2(146)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	512	512SD20-0014 TEMPORARY SIGN	896.000 SF	_____	_____	_____	_____
0390	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,560.000 HR	_____	_____	_____	_____
0400	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	6,300.000 DAY	_____	_____	_____	_____
0410	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	2,016.000 HR	_____	_____	_____	_____
0420	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,560.000 HR	_____	_____	_____	_____
0430	512	512SD20-0027 FLAGGER SERVICE	200.000 HR	_____	_____	_____	_____
0440	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	800.000 LF	_____	_____	_____	_____
0450	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	1,800.000 LF	_____	_____	_____	_____
0460	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	1,980.000 LF	_____	_____	_____	_____
0470	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0480	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	10,331.000 SY	_____	_____	_____	_____
0490	521	521SD20-0001 MAILBOX POST, SINGLE	18.000 EA	_____	_____	_____	_____
0500	603	603SD20-0002 TEMPORARY SEED	62.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122865N01

Oversight/State Project No.: 9999-962-828, N501

Order No.: M11

Federal Project No.: HSIP-962-2(146)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	603	603SD20-0003 REGULAR SEED	148.000 LB	_____	_____	_____	_____
0520	603	603SD20-0004 OVERSEEDING	117.000 LB	_____	_____	_____	_____
0530	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,816.000 SY	_____	_____	_____	_____
0540	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,977.000 SY	_____	_____	_____	_____
0550	603	603SD20-0014 FERTILIZER NITROGEN - N	44.000 LB	_____	_____	_____	_____
0560	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	30.000 LB	_____	_____	_____	_____
0570	603	603SD20-0016 FERTILIZER POTASSIUM - K	30.000 LB	_____	_____	_____	_____
0580	603	603SD20-0017 LIME	2.500 TON	_____	_____	_____	_____
0590	ATTD	605SX20-0011 LANDSCAPE ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	1,560.000 SY	_____	_____	_____	_____
0600	701	701SD20-0001 SIGN PANEL	3.000 SF	_____	_____	_____	_____
0610	702	702SD20-0003 ROAD EDGE DEL. ED-2	1.000 EA	_____	_____	_____	_____
0620	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	41,625.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____

