

Schedule of Items

Proposal ID: C0000122644B15 Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0001 REGULAR EXCAVATION	529.000 CY				
0030	303	303SD20-0019 EROSION CONTROL MULCH	2,586.000 SY				
0040	303	303SD20-0022 CHECK DAM ROCK TY. I	6.000 EA				
0050	303	303SD20-0025 CHECK DAM SEDIMENT RETENTION ROLL 20"	12.000 EA				
0060	303	303SD20-0030 INLET PROTECTION TYPE A	4.000 EA				
0070	303	303SD20-0031 INLET PROTECTION TYPE B	2.000 EA				
0080	303	303SD20-0034 TEMP. SILT FENCE TYPE A	4,642.000 LF				
0090	ATTD	303SP20-0001 AGGREGATE MATERIAL NO.3	30.000 TON				
0100	305	305SD20-0006 SELECT MATL. TY. II MIN. CBR-20	265.000 CY				
0110	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	457.000 TON				
0120	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	180.000 TON				
0130	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	500.000 TON				

Schedule of Items

Proposal ID: C0000122644B15

Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	400.000 LF	_____	_____	_____	_____
0150	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	56.000 CY	_____	_____	_____	_____
0160	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	288.000 CY	_____	_____	_____	_____
0170	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	562.000 TON	_____	_____	_____	_____
0180	404	404SD20-0007 CONC. CL. A4 MOD. LTWT LOW SHRINK., SPR. STRUCT. CONST.	353.000 CY	_____	_____	_____	_____
0190	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	1,192.000 SY	_____	_____	_____	_____
0200	404	404SD20-0010 COVER DEPTH SURVEY CONST.	1,424.000 SY	_____	_____	_____	_____
0210	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	15.000 CY	_____	_____	_____	_____
0220	406	406SD20-0003 CR REINF. STEEL CL. I SPR. STRUCT. CONST.	12,040.000 LB	_____	_____	_____	_____
0230	406	406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST.	91,780.000 LB	_____	_____	_____	_____
0240	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	1,380.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122644B15 Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	410	410SD20-0006 CONCRETE PARAPET 42" CONST.	578.000 LF	_____	_____	_____	_____
0260	411	411SX20-0001 PRE. & SPOT COAT EX. STR. STR. NO. 1025. TYPE.B	5,000.000 SF	_____	_____	_____	_____
0270	412	412SD20-0013 CRACK REPAIR TYPE B	50.000 LF	_____	_____	_____	_____
0280	412	412SD20-0017 EMBEDDED GALVANIC ANODES	175.000 EA	_____	_____	_____	_____
0290	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR	5.000 SY	_____	_____	_____	_____
0300	413	413SX20-0003 ENV.& WORKER PROTECT. STR. NO. 1025	LUMP SUM	LUMP SUM	_____	_____	_____
0310	413	413SX20-0004 MATERIAL DISPOSAL STR. NO. 1025, Type B	LUMP SUM	LUMP SUM	_____	_____	_____
0320	413	413SX20-0005 REM. PORT.OF EX.STR. STR. NO. 1025	LUMP SUM	LUMP SUM	_____	_____	_____
0330	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	5.500 TON	_____	_____	_____	_____
0340	415	415SD20-0004 CONC. SLAB SLOPE PROTECTION 4"	84.000 SY	_____	_____	_____	_____
0350	420	420SD20-0001 ADHESIVE BASED JT. SEALER CL. I, 1" CONST.	285.000 LF	_____	_____	_____	_____
0360	426	426SD20-0001 REPLACE BEARING	64.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122644B15

Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	426	426SD20-0028 JACKING AND BLOCKING BEAM	64.000 EA	_____	_____	_____	_____
0380	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE STR. NO. 1025	1.000 DAY	_____	_____	_____	_____
0390	502	502SD20-0007 PAVED DITCH PG-6B	41.000 SY	_____	_____	_____	_____
0400	502	502SD20-0011 CURB, STD. CG-2	150.000 LF	_____	_____	_____	_____
0410	502	502SD20-0014 CURB, STD. CG-3	112.000 LF	_____	_____	_____	_____
0420	502	502SD20-0053 MEDIAN STRIP MS-1	764.000 SY	_____	_____	_____	_____
0430	505	505SD20-0011 GUARDRAIL GR-MGS1	408.000 LF	_____	_____	_____	_____
0440	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	4.000 EA	_____	_____	_____	_____
0450	505	505SD20-0055 FIXED OBJECT ATTACH. GR-FOA-5	4.000 EA	_____	_____	_____	_____
0460	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	516.000 LF	_____	_____	_____	_____
0470	508	508SD20-0003 DEMO. OF PAVEMENT RIGID	500.000 SY	_____	_____	_____	_____
0480	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	500.000 SY	_____	_____	_____	_____
0490	512	512SD20-0008 IMPACT ATTEN.SER. TY. I TL-2, <40 MPH	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122644B15 Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	512	512SD20-0013 TYPE 3 BARRICADE 8'	5.000 EA	_____	_____	_____	_____
0510	512	512SD20-0014 TEMPORARY SIGN	1,147.000 SF	_____	_____	_____	_____
0520	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	90,338.000 DAY	_____	_____	_____	_____
0530	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	26,280.000 HR	_____	_____	_____	_____
0540	512	512SD20-0029 WARNING LIGHT TY. B	5,475.000 DAY	_____	_____	_____	_____
0550	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	6,800.000 LF	_____	_____	_____	_____
0560	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	98.000 EA	_____	_____	_____	_____
0570	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4" White	1,600.000 LF	_____	_____	_____	_____
0580	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4" Yellow	1,600.000 LF	_____	_____	_____	_____
0590	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8" White	1,600.000 LF	_____	_____	_____	_____
0600	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8" Yellow	1,600.000 LF	_____	_____	_____	_____
0610	512	512SD20-0066 TRAFFIC BARRIER SERVICE CONC.	980.000 LF	_____	_____	_____	_____
0620	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000122644B15

Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0630	514	514SD20-0002 FIELD OFFICE TY.II	18.000 MO	_____	_____	_____	_____
0640	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	1,164.000 SY	_____	_____	_____	_____
0650	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0660	603	603SD20-0002 TEMPORARY SEED	54.000 LB	_____	_____	_____	_____
0670	603	603SD20-0003 REGULAR SEED	94.000 LB	_____	_____	_____	_____
0680	603	603SD20-0004 OVERSEEDING	75.000 LB	_____	_____	_____	_____
0690	603	603SD20-0005 LEGUME SEED	7.000 LB	_____	_____	_____	_____
0700	603	603SD20-0006 LEGUME OVERSEEDING	6.000 LB	_____	_____	_____	_____
0710	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,586.000 SY	_____	_____	_____	_____
0720	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	105.000 LF	_____	_____	_____	_____
0730	700	700SD20-0042 CONC. FOUND. STP-1, TY. E	7.000 EA	_____	_____	_____	_____
0740	701	701SD20-0001 SIGN PANEL	36.000 SF	_____	_____	_____	_____
0750	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4" White	3,000.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122644B15

Oversight/State Project No.: 0134-099-711,B615

Order No.: M49

Federal Project No.: STP-5B03(191)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0760	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4" Yellow	3,000.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	