

Schedule of Items

Proposal ID: C0000115459C01 Oversight/State Project No.: 0103-070-719, C501
 Order No.: M58 Federal Project No.: STP-070-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____	_____
0020	302	302SD20-0025 15" CONC. PIPE	59.000 LF	_____	_____	_____	_____
0030	302	302SD20-0030 18" CONC. PIPE	68.000 LF	_____	_____	_____	_____
0040	302	302SD20-0039 24" CONC. PIPE	43.000 LF	_____	_____	_____	_____
0050	302	302SD20-0199 15" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0060	302	302SD20-0201 18" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0070	302	302SD20-0205 24" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0080	303	303SD20-0001 REGULAR EXCAVATION	1,182.000 CY	_____	_____	_____	_____
0090	303	303SD20-0022 CHECK DAM ROCK TY. I	7.000 EA	_____	_____	_____	_____
0100	303	303SD20-0023 CHECK DAM ROCK TY. II	26.000 EA	_____	_____	_____	_____
0110	303	303SD20-0029 SILTATION CONTROL EXCAVATION	88.000 CY	_____	_____	_____	_____
0120	303	303SD20-0034 TEMP. SILT FENCE TYPE A	215.000 LF	_____	_____	_____	_____
0130	308	305SX20-0002 AGGR. MATL NO. 1 STONE	557.000 TON	_____	_____	_____	_____
0140	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	417.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115459C01

Oversight/State Project No.: 0103-070-719, C501

Order No.: M58

Federal Project No.: STP-070-2(039)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	307.000 TON	_____	_____	_____	_____
0160	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	178.000 TON	_____	_____	_____	_____
0170	315	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	419.000 LF	_____	_____	_____	_____
0180	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	6.300 TON	_____	_____	_____	_____
0190	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	0.300 CY	_____	_____	_____	_____
0200	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	911.000 SY	_____	_____	_____	_____
0210	509	509SD20-0001 FLOWABLE BACKFILL	10.114 CY	_____	_____	_____	_____
0220	511	511SD20-0001 ALLAYING DUST	150.000 HR	_____	_____	_____	_____
0230	512	512SD20-0014 TEMPORARY SIGN	600.000 SF	_____	_____	_____	_____
0240	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	2,520.000 DAY	_____	_____	_____	_____
0250	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	336.000 HR	_____	_____	_____	_____
0260	512	512SD20-0027 FLAGGER SERVICE	1,920.000 HR	_____	_____	_____	_____
0270	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	120.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115459C01 Oversight/State Project No.: 0103-070-719, C501
 Order No.: M58 Federal Project No.: STP-070-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
0290	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	838.000 SY				
0300	515	515SD20-0005 FLEXIBLE PAVE. PLANING ABOVE 2"-4"	838.000 SY				
0310	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0320	602	602SD20-0004 TOPSOIL CLASS B 3"	165.000 CY				
0330	603	603SD20-0002 TEMPORARY SEED	119.000 LB				
0340	603	603SD20-0003 REGULAR SEED	131.000 LB				
0350	603	603SD20-0004 OVERSEEDING	105.000 LB				
0360	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	666.000 SY				
0370	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,799.000 SY				
0380	603	603SD20-0014 FERTILIZER NITROGEN - N	41.000 LB				
0390	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	29.000 LB				
0400	603	603SD20-0016 FERTILIZER POTASSIUM - K	29.000 LB				

Schedule of Items

Proposal ID: C0000115459C01 Oversight/State Project No.: 0103-070-719, C501
 Order No.: M58 Federal Project No.: STP-070-2(039)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	603	603SD20-0017 LIME	2.300 TON	_____	_____	_____	_____
0420	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	764.000 SY	_____	_____	_____	_____
0430	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	441.000 SY	_____	_____	_____	_____
0440	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
0450	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	20.000 LF	_____	_____	_____	_____
0460	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	64.000 LF	_____	_____	_____	_____
0470	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	8.000 EA	_____	_____	_____	_____
0480	701	701SD20-0001 SIGN PANEL	111.200 SF	_____	_____	_____	_____
0490	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	990.000 LF	_____	_____	_____	_____
0500	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	60.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____