

Schedule of Items

Proposal ID: C0000118817B08B Oversight/State Project No.: 0699-053-231, B608

Order No.: M53

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0023 CHECK DAM ROCK TY. II	2.000 EA	_____	_____	_____	_____
0020	303	303SD20-0029 SILTATION CONTROL EXCAVATION	15.000 CY	_____	_____	_____	_____
0030	303	303SD20-0034 TEMP. SILT FENCE TYPE A	79.000 LF	_____	_____	_____	_____
0040	307	307SD20-0004 CEM. STAB. AGGR. BASE. MATL. TY. I NO. 21A	97.000 TON	_____	_____	_____	_____
0050	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	94.000 TON	_____	_____	_____	_____
0060	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	79.000 TON	_____	_____	_____	_____
0070	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE SAWCUT	238.000 LF	_____	_____	_____	_____
0080	ATTD	401SX20-0006 BRIDGE SUBSTRUCTURE MASONRY POINTING	900.000 SF	_____	_____	_____	_____
0090	ATTD	401SX20-0006 BRIDGE SUBSTRUCTURE MASONRY RECONSTRUCTION	25.000 SF	_____	_____	_____	_____
0100	ATTD	410SX20-0007 BRIDGE SUPERSTRUCTURE GROUTED ANCHOR STRENGTHENING SYSTEM (STR. 1003)	LUMP SUM	LUMP SUM	_____	_____	_____
0110	ATTD	410SX20-0007 BRIDGE SUPERSTRUCTURE PRECAST BARRIER SYSTEM	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000118817B08B Oversight/State Project No.: 0699-053-231, B608

Order No.: M53

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0120	ATTD	410SX20-0014 BRIDGE INCIDENTALS REMOVE EXISTING BARRIER (STR. NO. 1003)	LUMP SUM	LUMP SUM			
0130	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY WALKWAY CANOPY	LUMP SUM	LUMP SUM			
0140	ATTD	410SX20-0015 BRIDGE INCIDENTALS BRIDGE CLEANING AND WASHING - SUPERSTRUCTURE	322.000 SY				
0150	414	414SD20-0008 DRY RIPRAP CL. AI	57.000 TON				
0160	502	502SD20-0014 CURB, STD. CG-3	56.000 LF				
0170	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	100.000 LF				
0180	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	1.000 EA				
0190	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	2.000 EA				
0200	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	2.000 EA				
0210	505	505SD20-0068 IMPACT ATTENUATOR IA-2	2.000 EA				
0220	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	240.000 LF				

Schedule of Items

Proposal ID: C0000118817B08B Oversight/State Project No.: 0699-053-231, B608

Order No.: M53

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0230	505	505SX20-0070 IMPACT ATTENUATOR TL-2 GR-MGS2 25' LONG REQ'D	1.000 EA	_____	_____	_____	_____
0240	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	160.000 SY	_____	_____	_____	_____
0250	511	511SD20-0001 ALLAYING DUST	128.000 HR	_____	_____	_____	_____
0260	512	512SD20-0012 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0270	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0280	512	512SD20-0014 TEMPORARY SIGN	654.000 SF	_____	_____	_____	_____
0290	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,792.000 HR	_____	_____	_____	_____
0300	512	512SD20-0027 FLAGGER SERVICE	80.000 HR	_____	_____	_____	_____
0310	512	512SD20-0066 TRAFFIC BARRIER SERVICE CONC.	40.000 LF	_____	_____	_____	_____
0320	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0330	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	355.000 SY	_____	_____	_____	_____
0340	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0350	603	603SD20-0002 TEMPORARY SEED	6.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118817B08B Oversight/State Project No.: 0699-053-231, B608

Order No.: M53

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0360	603	603SD20-0003 REGULAR SEED	6.000 LB	_____	_____	_____	_____
0370	603	603SD20-0004 OVERSEEDING	5.000 LB	_____	_____	_____	_____
0380	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	242.000 SY	_____	_____	_____	_____
0390	603	603SD20-0014 FERTILIZER NITROGEN - N	4.000 LB	_____	_____	_____	_____
0400	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	5.000 LB	_____	_____	_____	_____
0410	603	603SD20-0016 FERTILIZER POTASSIUM - K	3.000 LB	_____	_____	_____	_____
0420	603	603SD20-0017 LIME	0.200 TON	_____	_____	_____	_____
0430	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	6.000 EA	_____	_____	_____	_____
0440	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
0450	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	12.500 LF	_____	_____	_____	_____
0460	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	1.000 EA	_____	_____	_____	_____
0470	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	904.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____