

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	22.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	302	302SD20-0013 ENDWALL EW-12	3.000 EA				
0050	302	302SD20-0027 15" STORM SEWER PIPE	39.000 LF				
0060	302	302SD20-0656 DROP INLET DI-13 TY.II	1.000 EA				
0070	303	303SD20-0001 REGULAR EXCAVATION	4,312.000 CY				
0080	303	303SD20-0021 TEMPORARY DIVERSION DIKE (EC-9)	232.000 LF				
0090	303	303SD20-0023 CHECK DAM ROCK TY. II	18.000 EA				
0100	303	303SD20-0028 DEWATERING BASIN EC-8	4.000 EA				
0110	303	303SD20-0029 SILTATION CONTROL EXCAVATION	513.000 CY				
0120	303	303SD20-0030 INLET PROTECTION TYPE A	4.000 EA				
0130	303	303SD20-0031 INLET PROTECTION TYPE B	1.000 EA				
0140	303	303SD20-0032 GEOTEXTILE FABRIC	103.000 SY				

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0034 TEMP. SILT FENCE TYPE A	2,984.000 LF	_____	_____	_____	_____
0160	ATTD	303SX20-0008 GEOTEXTILE (GEOGRID)	5,913.000 SY	_____	_____	_____	_____
0170	ATTD	303SX20-0010 ACCESS ROAD (CONSTRUCTION ACCESS)	LUMP SUM	LUMP SUM	_____	_____	_____
0180	ATTD	303SX20-0012 UTILITY TEST PIT UNPAVED	3.000 EA	_____	_____	_____	_____
0190	308	308SD20-0001 AGGR. MATL. NO. 1	29,198.000 TON	_____	_____	_____	_____
0200	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	2,703.000 TON	_____	_____	_____	_____
0210	310	310SD20-0001 TACK COAT	2,051.000 GAL	_____	_____	_____	_____
0220	315	315SD20-0003 ASPHALT CONCRETE TY. SM- 12.5E CONST	2,698.000 TON	_____	_____	_____	_____
0230	315	315SD20-0006 ASPHALT CONCRETE TY. IM- 19.0E CONST	562.000 TON	_____	_____	_____	_____
0240	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	1,808.000 TON	_____	_____	_____	_____
0250	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	5,874.000 LF	_____	_____	_____	_____
0260	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	979.000 SY	_____	_____	_____	_____
0270	315	315SX20-0011 SAW-CUT ASPH CONC (Full Depth)	4,331.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	164.100 CY	_____	_____	_____	_____
0290	316	316SD20-0036 REINF. STEEL BRIDGE APPR. SLAB CONST.	29,290.000 LB	_____	_____	_____	_____
0300	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	320.000 CY	_____	_____	_____	_____
0310	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	1,266.000 TON	_____	_____	_____	_____
0320	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	176.000 SY	_____	_____	_____	_____
0330	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	199.000 LF	_____	_____	_____	_____
0340	ATTD	401SX20-0011 BRIDGE SUBSTRUCTURE (TEMPORARY SHORING)	LUMP SUM	LUMP SUM		_____	_____
0350	403	403SD20-0006 STEEL PILES 12"	1,134.000 LF	_____	_____	_____	_____
0360	ATTD	403SX20-0016 PREBORING PILE FOR STEEL PILES	352.000 LF	_____	_____	_____	_____
0370	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	396.100 CY	_____	_____	_____	_____
0380	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	1,176.000 SY	_____	_____	_____	_____
0390	404	404SD20-0010 COVER DEPTH SURVEY CONST.	868.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	54.410 CY	_____	_____	_____	_____
0410	ATTD	404SP20-0004 ELASTIC INCLUSION 15"	27.000 SY	_____	_____	_____	_____
0420	405	405SD20-0072 PREST.CONC.BEAM,BULB- T69"DPTH +110'-120'	6.000 EA	_____	_____	_____	_____
0430	406	406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST.	63,890.000 LB	_____	_____	_____	_____
0440	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	7,760.000 LB	_____	_____	_____	_____
0450	410	410SD20-0056 CONCRETE PARAPET BPB-4	244.000 LF	_____	_____	_____	_____
0460	ATTD	410SX20-0001 ARCHITECTURAL TREATMENT FOR MSE PANELS	1,009.000 SY	_____	_____	_____	_____
0470	411	411SX20-0005 ENV. PROT. & HEALTH & SAFETY NS ENVIRONMENTAL PROTECTION AND HEALTH AND SAFETY	LUMP SUM	LUMP SUM	_____	_____	_____
0480	413	413SX20-0002 DISM.& REM. EX. STR. NS DISMANTLE AND REMOVE EXISTING STRUCTURE (STR. NO. 2804)	LUMP SUM	LUMP SUM	_____	_____	_____
0490	413	413SX20-0004 MATERIAL DISPOSAL NS DISPOSAL OF MATERIAL	LUMP SUM	LUMP SUM	_____	_____	_____
0500	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	3.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	414	414SD20-0007 DRY RIPRAP CL. AI	103.000 SY				
0520	414	414SD20-0057 DRY RIPRAP CL.II 38"	249.000 TON				
0530	415	415SD20-0004 CONC. SLAB SLOPE PROTECTION 4"	165.000 SY				
0540	419	419SX20-0008 BRG. CONDUIT SYSTEM (BRIDGE)	LUMP SUM	LUMP SUM			
0550	501	501SD20-0004 UNDERDRAIN UD-4	482.000 LF				
0560	501	501SD20-0009 OUTLET PIPE	14.000 LF				
0570	502	502SD20-0006 PAVED DITCH PG-6A	59.000 SY				
0580	502	502SD20-0014 CURB, STD. CG-3	109.000 LF				
0590	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC. (15" ENDWALL EW-1)	0.520 CY				
0600	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	2.000 EA				
0610	505	505SD20-0011 GUARDRAIL GR-MGS1	1,382.000 LF				
0620	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	330.000 LF				
0630	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	2.000 EA				

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0650	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	3.000 EA	_____	_____	_____	_____
0660	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	4.000 EA	_____	_____	_____	_____
0670	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	2,354.000 LF	_____	_____	_____	_____
0680	505	505SX20-0057 GUARDRAIL (ST'D BR-GR-4D)	200.000 LF	_____	_____	_____	_____
0690	ATTD	506SX20-0002 WALL MECHANICALLY STABILIZED EARTH WALL	11,397.000 SF	_____	_____	_____	_____
0700	507	507SD20-0001 FENCE FE-W1	435.000 LF	_____	_____	_____	_____
0710	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	4.000 EA	_____	_____	_____	_____
0720	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	2.000 EA	_____	_____	_____	_____
0730	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	5,166.000 SY	_____	_____	_____	_____
0740	510	510SX20-0016 REMOVE EXIST. FENCE (ROADWAY)	763.000 LF	_____	_____	_____	_____
0750	511	511SD20-0001 ALLAYING DUST	90.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0760	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	4,021.000 LF	_____	_____	_____	_____
0770	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	4.000 EA	_____	_____	_____	_____
0780	512	512SD20-0008 IMPACT ATTEN.SER. TY. I TL- 2, <40 MPH	4.000 EA	_____	_____	_____	_____
0790	512	512SD20-0013 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0800	512	512SD20-0014 TEMPORARY SIGN	5,410.000 SF	_____	_____	_____	_____
0810	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	2,264.000 HR	_____	_____	_____	_____
0820	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	14,308.000 DAY	_____	_____	_____	_____
0830	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	672.000 HR	_____	_____	_____	_____
0840	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,160.000 HR	_____	_____	_____	_____
0850	512	512SD20-0027 FLAGGER SERVICE	4,000.000 HR	_____	_____	_____	_____
0860	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	5,995.000 LF	_____	_____	_____	_____
0870	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	301.000 EA	_____	_____	_____	_____
0880	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	9,700.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0890	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	11,649.000 LF	_____	_____	_____	_____
0900	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0910	514	514SD20-0001 FIELD OFFICE TY.I	22.000 MO	_____	_____	_____	_____
0920	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	7,926.000 SY	_____	_____	_____	_____
0930	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0940	602	602SD20-0002 TOPSOIL CLASS A (3 IN.)	404.000 CY	_____	_____	_____	_____
0950	602	602SD20-0004 TOPSOIL CLASS B (3 IN.)	404.000 CY	_____	_____	_____	_____
0960	603	603SD20-0002 TEMPORARY SEED	300.000 LB	_____	_____	_____	_____
0970	603	603SD20-0003 REGULAR SEED	425.000 LB	_____	_____	_____	_____
0980	603	603SD20-0004 OVERSEEDING	340.000 LB	_____	_____	_____	_____
0990	603	603SD20-0005 LEGUME SEED	13.000 LB	_____	_____	_____	_____
1000	603	603SD20-0006 LEGUME OVERSEEDING	10.000 LB	_____	_____	_____	_____
1010	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	6,050.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1020	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	9,680.000 SY	_____	_____	_____	_____
1030	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	6,050.000 SY	_____	_____	_____	_____
1040	603	603SD20-0014 FERTILIZER NITROGEN - N	200.000 LB	_____	_____	_____	_____
1050	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	140.000 LB	_____	_____	_____	_____
1060	603	603SD20-0016 FERTILIZER POTASSIUM - K	140.000 LB	_____	_____	_____	_____
1070	603	603SD20-0017 LIME	11.000 TON	_____	_____	_____	_____
1080	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	425.000 SY	_____	_____	_____	_____
1090	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1100	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
1110	700	700SD20-0025 VIA SIGN POST W14 X 26	48.000 LF	_____	_____	_____	_____
1120	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	31.000 LF	_____	_____	_____	_____
1130	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	28.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116160B01

Oversight/State Project No.: 0081-119-833, C501, B601

Order No.: N20

Federal Project No.: NHPP-081-1(436)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1140	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	14.000 LF	_____	_____	_____	_____
1150	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	3.000 EA	_____	_____	_____	_____
1160	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	2.000 EA	_____	_____	_____	_____
1170	700	700SD20-0049 CONC. FOUND. SSP-VIA, 3' DIA. X 7' DEEP	2.000 EA	_____	_____	_____	_____
1180	700	700SD20-0180 JUNCTION BOX JB-S4	4.000 EA	_____	_____	_____	_____
1190	700	700SD20-0194 CONDUIT PVC 2"	100.000 LF	_____	_____	_____	_____
1200	701	701SD20-0001 SIGN PANEL	203.000 SF	_____	_____	_____	_____
1210	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	4,867.000 LF	_____	_____	_____	_____
1220	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	346.000 LF	_____	_____	_____	_____
1230	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	415.000 LF	_____	_____	_____	_____
1240	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	48.000 EA	_____	_____	_____	_____
1250	510	704SP20-0001 REMOVAL OF SRPM	29.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____