

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION .	LUMP SUM	LUMP SUM		_____.	_____
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM		_____.	_____
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	78.000 EA		_____.	_____.	_____
0040	301	301SD20-0002 CLEARING AND GRUBBING	13.300 ACRE		_____.	_____.	_____
0050	ATTD	302SD20-0001 BEDDING MATL.AGGR.NO. 25 OR 26	1,807.000 TON		_____.	_____.	_____
0060	ATTD	302SD20-0002 BEDDING MATL. AGGR. NO. 57	564.000 TON		_____.	_____.	_____
0070	302, 406	302SD20-0005 REINF. STEEL	21,304.000 LB		_____.	_____.	_____
0080	406	302SD20-0006 CORROSION RESISTANT REINF.STEEL CL. I	26,096.000 LB		_____.	_____.	_____
0090	302	302SD20-0013 ENDWALL EW-12	15.000 EA		_____.	_____.	_____
0100	302	302SD20-0023 15" PIPE	42.000 LF		_____.	_____.	_____
0110	302	302SD20-0027 15" STORM SEWER PIPE	9,539.000 LF		_____.	_____.	_____
0120	302	302SD20-0029 18" JACKED & BORED PIPE	207.000 LF		_____.	_____.	_____
0130	302	302SD20-0032 18" STORM SEWER PIPE	13,499.000 LF		_____.	_____.	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	302SD20-0036 21" STORM SEWER PIPE	495.000 LF	_____	_____	_____	_____
0150	302	302SD20-0037 24" PIPE	328.000 LF	_____	_____	_____	_____
0160	302	302SD20-0038 24" JACKED & BORED PIPE	1,131.000 LF	_____	_____	_____	_____
0170	302	302SD20-0041 24" STORM SEWER PIPE	2,894.000 LF	_____	_____	_____	_____
0180	302	302SD20-0047 30" PIPE	103.000 LF	_____	_____	_____	_____
0190	302	302SD20-0051 30" STORM SEWER PIPE	861.000 LF	_____	_____	_____	_____
0200	302	302SD20-0057 36" PIPE	346.000 LF	_____	_____	_____	_____
0210	302	302SD20-0061 36" STORM SEWER PIPE	12.000 LF	_____	_____	_____	_____
0220	302	302SD20-0079 60" PIPE	11.000 LF	_____	_____	_____	_____
0230	302	302SD20-0198 15" END SECTION ES-1 OR 2	12.000 EA	_____	_____	_____	_____
0240	302	302SD20-0199 15" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0250	302	302SD20-0200 18" END SECTION ES-1 OR 2	12.000 EA	_____	_____	_____	_____
0260	302	302SD20-0204 24" END SECTION ES-1 OR 2	8.000 EA	_____	_____	_____	_____
0270	302	302SD20-0205 24" END SECTION ES-1	4.000 EA	_____	_____	_____	_____
0280	302	302SD20-0208 30" END SECTION ES-1 OR 2	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	302	302SD20-0209 30" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0300	302	302SD20-0210 36" END SECTION ES-1 OR 2	3.000 EA	_____	_____	_____	_____
0310	302	302SD20-0211 36" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0320	302	302SD20-0237 DROP INLET DI-1	88.000 EA	_____	_____	_____	_____
0330	302	302SD20-0242 DROP INLET DI-2B,L=6'	4.000 EA	_____	_____	_____	_____
0340	302	302SD20-0249 DROP INLET DI-2B,L=20'	2.000 EA	_____	_____	_____	_____
0350	302	302SD20-0311 DROP INLET DI-3B,L=4'	4.000 EA	_____	_____	_____	_____
0360	302	302SD20-0312 DROP INLET DI-3B,L=6'	6.000 EA	_____	_____	_____	_____
0370	302	302SD20-0320 DROP INLET DI-3BB,L=4'	2.000 EA	_____	_____	_____	_____
0380	302	302SD20-0321 DROP INLET DI-3BB,L=6'	1.000 EA	_____	_____	_____	_____
0390	302	302SD20-0329 DROP INLET DI-3C,L=6'	4.000 EA	_____	_____	_____	_____
0400	302	302SD20-0446 DROP INLET DI-5	17.000 EA	_____	_____	_____	_____
0410	302	302SD20-0447 DROP INLET DI-7	4.000 EA	_____	_____	_____	_____
0420	302	302SD20-0448 DROP INLET DI-7A	1.000 EA	_____	_____	_____	_____
0430	302	302SD20-0449 DROP INLET DI-7B	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0440	302	302SD20-0649 DROP INLET DI-12C,L=4'	4.000 EA	_____	_____	_____	_____
0450	302	302SD20-0650 DROP INLET DI-12C,L=6'	1.000 EA	_____	_____	_____	_____
0460	302	302SD20-0653 DROP INLET DI-12C,L=12'	1.000 EA	_____	_____	_____	_____
0470	302	302SD20-0654 DROP INLET DI-12C,L=14'	1.000 EA	_____	_____	_____	_____
0480	302	302SD20-0661 MANHOLE MH-2	8.000 LF	_____	_____	_____	_____
0490	302	302SD20-0662 MANHOLE MH-1 OR 2	557.000 LF	_____	_____	_____	_____
0500	302	302SD20-0663 FRAME & COVER MH-1	35.000 EA	_____	_____	_____	_____
0510	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	85.000 LF	_____	_____	_____	_____
0520	ATTD	302SX20-0013 PIPE REHABILITATION	367.000 LF	_____	_____	_____	_____
0530	302	302SX20-0026 DROP INLET DI-15B TYPE 1 L= 10'	11.000 EA	_____	_____	_____	_____
0540	302	302SX20-0026 DROP INLET DI-15B TYPE 1 L= 12'	12.000 EA	_____	_____	_____	_____
0550	302	302SX20-0026 DROP INLET DI-15B TYPE 1 L= 6'	6.000 EA	_____	_____	_____	_____
0560	302	302SX20-0026 DROP INLET DI-15B TYPE 1 L= 8'	5.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0570	302	302SX20-0026 DROP INLET DI-16B L= 10'	4.000 EA	_____	_____	_____	_____
0580	302	302SX20-0026 DROP INLET DI-16B L= 12'	4.000 EA	_____	_____	_____	_____
0590	302	302SX20-0026 DROP INLET DI-16B L= 6'	5.000 EA	_____	_____	_____	_____
0600	302	302SX20-0026 DROP INLET DI-16B L= 8'	4.000 EA	_____	_____	_____	_____
0610	302	302SX20-0026 DROP INLET DI-16C L= 6'	1.000 EA	_____	_____	_____	_____
0620	302	302SX20-0026 DROP INLET DI-16C L= 8'	2.000 EA	_____	_____	_____	_____
0630	302	302SX20-0026 DROP INLET DI-17B L= 10'	1.000 EA	_____	_____	_____	_____
0640	302	302SX20-0026 DROP INLET DI-17B L= 12'	2.000 EA	_____	_____	_____	_____
0650	302	302SX20-0026 DROP INLET DI-17B L= 4'	2.000 EA	_____	_____	_____	_____
0660	302	302SX20-0026 DROP INLET DI-17B L= 6'	5.000 EA	_____	_____	_____	_____
0670	302	302SX20-0026 DROP INLET DI-17B L= 8'	1.000 EA	_____	_____	_____	_____
0680	302	302SX20-0026 DROP INLET DI-17C L= 6'	1.000 EA	_____	_____	_____	_____
0690	302	302SX20-0026 DROP INLET DI-17C L= 8'	1.000 EA	_____	_____	_____	_____
0700	302	302SX20-0026 DROP INLET DI-18B L= 10'	25.000 EA	_____	_____	_____	_____
0710	302	302SX20-0026 DROP INLET DI-18B L= 12'	41.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0720	302	302SX20-0026 DROP INLET DI-18B L= 6'	2.000 EA	_____	_____	_____	_____
0730	302	302SX20-0026 DROP INLET DI-18B L= 8'	10.000 EA	_____	_____	_____	_____
0740	302	302SX20-0026 DROP INLET DI-18C L= 6'	1.000 EA	_____	_____	_____	_____
0750	302	302SX20-0026 DROP INLET DI-18C L= 8'	1.000 EA	_____	_____	_____	_____
0760	303	303SD20-0001 REGULAR EXCAVATION	103,096.000 CY	_____	_____	_____	_____
0770	303	303SD20-0015 SETTLEMENT PLATE	1.000 EA	_____	_____	_____	_____
0780	303	303SD20-0018 SLOPE DRAIN	40.000 EA	_____	_____	_____	_____
0790	303	303SD20-0019 EROSION CONTROL MULCH	57.000 SY	_____	_____	_____	_____
0800	303	303SD20-0022 CHECK DAM ROCK TY. I	16.000 EA	_____	_____	_____	_____
0810	303	303SD20-0023 CHECK DAM ROCK TY. II	308.000 EA	_____	_____	_____	_____
0820	303	303SD20-0028 DEWATERING BASIN EC-8	6.000 EA	_____	_____	_____	_____
0830	303	303SD20-0029 SILTATION CONTROL EXCAVATION	12,159.000 CY	_____	_____	_____	_____
0840	303	303SD20-0030 INLET PROTECTION TYPE A	61.000 EA	_____	_____	_____	_____
0850	303	303SD20-0031 INLET PROTECTION TYPE B	258.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0860	303	303SD20-0032 GEOTEXTILE FABRIC	1,051.000 SY	_____	_____	_____	_____
0870	303	303SD20-0033 TEMP. SILT FENCE TYPE B	13,437.000 LF	_____	_____	_____	_____
0880	303	303SD20-0034 TEMP. SILT FENCE TYPE A	157,167.000 LF	_____	_____	_____	_____
0890	303	303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION	1,553.000 CY	_____	_____	_____	_____
0900	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	23,183.000 CY	_____	_____	_____	_____
0910	ATTD	303SX20-0017 REINFORCED SOIL SLOPE TY. A CASE 1, SLOPE RATIO 1/2" H TO 18" V	600.000 SF	_____	_____	_____	_____
0920	305	305SD20-0001 BORROW EXCAVATION (MIN CBR 5)	54,359.000 CY	_____	_____	_____	_____
0930	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	18,822.000 SY	_____	_____	_____	_____
0940	ATTD	305SX20-0006 SELECT MATERIAL NO. 10 SCREENINGS	79,454.000 TON	_____	_____	_____	_____
0950	ATTD	305SX20-0006 SELECT MATERIAL OGB	64,668.000 TON	_____	_____	_____	_____
0960	307	307SD20-0001 HYDRAULIC CEMENT	3,785.000 TON	_____	_____	_____	_____
0970	308	308SD20-0016 AGGR. MATERIAL NO.3	4.000 TON	_____	_____	_____	_____
0980	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	135.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0990	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	28,283.000 TON	_____	_____	_____	_____
1000	312	312SD20-0005 COVER MATL. AGGR. NO. 78	3,003.000 TON	_____	_____	_____	_____
1010	312	312SD20-0006 COVER MATL. AGGR. NO. 8 PEA GRAVEL	98.000 TON	_____	_____	_____	_____
1020	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	11,928.000 TON	_____	_____	_____	_____
1030	315	315SD20-0002 ASPHALT CONCRETE TY. SM- 12.5D CONST	9,416.000 TON	_____	_____	_____	_____
1040	315	315SD20-0004 ASPHALT CONCRETE TY. IM- 19.0A CONST	5,488.000 TON	_____	_____	_____	_____
1050	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	8,655.000 TON	_____	_____	_____	_____
1060	315	315SD20-0007 ASPHALT CONCRETE TY. SM- 9.5A CONST	81.000 TON	_____	_____	_____	_____
1070	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	93,858.000 TON	_____	_____	_____	_____
1080	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	112,913.000 LF	_____	_____	_____	_____
1090	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	20,934.000 SY	_____	_____	_____	_____
1100	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	24.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1110	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH (I-81)	75,706.000 LF	_____	_____	_____	_____
1120	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH (PLEASANT VALLEY & SIDE STREETS)	3,425.000 LF	_____	_____	_____	_____
1130	ATTD	315SX20-0013 FULL DEPTH RECLAMATION 10" DEPTH	130,165.000 SY	_____	_____	_____	_____
1140	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	526.000 CY	_____	_____	_____	_____
1150	316	316SD20-0036 REINF. STEEL BRIDGE APPR. SLAB CONST.	86,260.000 LB	_____	_____	_____	_____
1160	316	316SX20-0009 HYDRAULIC CEM. CONC. INTEGRALLY COLORED	378.000 SY	_____	_____	_____	_____
1170	317, 315	317SD20-0004 STONE MATRIX ASPH. SMA- 12.5 64E-22	20,649.000 TON	_____	_____	_____	_____
1180	317, 315	317SD20-0006 STONE MATRIX ASPH. SMA- 19.0 64E-22	44,911.000 TON	_____	_____	_____	_____
1190	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	27,760.000 CY	_____	_____	_____	_____
1200	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	20,772.000 TON	_____	_____	_____	_____
1210	401	401SD20-0003 POROUS BACKFILL	202.000 CY	_____	_____	_____	_____
1220	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	756.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1230	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	1,422.000 LF				
1240	401	401SD20-0007 COFFERDAM	5.000 EA				
1250	401	401SX20-0001 BRIDGE CONSTR ACCESS PLEASANT VALLEY	LUMP SUM	LUMP SUM			
1260	401	401SX20-0001 BRIDGE CONSTR ACCESS SOUTH BLACKS RUN	LUMP SUM	LUMP SUM			
1270	ATTD	401SX20-0001 BRIDGE PILE EXPLORATORY DRILLING	LUMP SUM	LUMP SUM			
1280	ATTD	401SX20-0002 TEMP. CAUSEWAY (2000)	LUMP SUM	LUMP SUM			
1290	ATTD	401SX20-0002 TEMP. CAUSEWAY (2001)	LUMP SUM	LUMP SUM			
1300	ATTD	401SX20-0002 TEMP. CAUSEWAY (2020)	LUMP SUM	LUMP SUM			
1310	ATTD	401SX20-0002 TEMP. CAUSEWAY (2021)	LUMP SUM	LUMP SUM			
1320	ATTD	401SX20-0002 TEMP. CAUSEWAY (2900)	LUMP SUM	LUMP SUM			
1330	ATTD	401SX20-0002 TEMP. CAUSEWAY (2901)	LUMP SUM	LUMP SUM			
1340	ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE COMPACTION GROUTING	246.300 CY				
1350	ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE CONCRETE CLASS A3 FOR LTP UNDER MSE WALL	223.000 CY				

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1360	ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE CONCRETE CLASS A3 UNREINFORCED	203.300 CY	_____	_____	_____	_____
1370	ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE MICROPILE GROUT	10.000 CY	_____	_____	_____	_____
1380	ATTD	401SX20-0005 BRIDGE SUBSTRUCTURE GROUT BORINGS	219.000 LF	_____	_____	_____	_____
1390	ATTD	401SX20-0005 BRIDGE SUBSTRUCTURE SAW CUTTING	516.000 LF	_____	_____	_____	_____
1400	ATTD	401SX20-0006 BRIDGE SUBSTRUCTURE FIBER WRAP	1,860.000 SF	_____	_____	_____	_____
1410	ATTD	401SX20-0011 BRIDGE SUBSTRUCTURE PILE EXPLORATORY DRILLING AND SUBSURFACE EXPLORATION	LUMP SUM	LUMP SUM	_____	_____	_____
1420	403	403SD20-0006 STEEL PILES 12"	13,096.000 LF	_____	_____	_____	_____
1430	403	403SD20-0034 PILE POINT FOR 12" STEEL PILE	127.000 EA	_____	_____	_____	_____
1440	ATTD	403SX20-0001 DYNAMIC PILE TEST END BEARING PILES	9.000 EA	_____	_____	_____	_____
1450	ATTD	403SX20-0016 PREBORING PILE 12" STEEL	9,203.000 LF	_____	_____	_____	_____
1460	ATTD	403SX20-0018 PILE MICROPILE 7"	2,151.000 LF	_____	_____	_____	_____
1470	ATTD	403SX20-0018 PILE MICROPILE CASING 7"	2,151.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1480	ATTD	403SX20-0018 PILE MICROPILE REDRILLING	100.000 LF	_____	_____	_____	_____
1490	ATTD	403SX20-0018 PILE VERIFICATION MICROPILE	31.000 LF	_____	_____	_____	_____
1500	ATTD	403SX20-0019 PILE MICROPILE LOAD TEST	8.000 EA	_____	_____	_____	_____
1510	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	883.300 CY	_____	_____	_____	_____
1520	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST. LOW SHRINK	70.900 CY	_____	_____	_____	_____
1530	404	404SD20-0007 CONC. CL. A4 MOD. LTWT LOW SHRINK., SPR. STRUCT. CONST.	2,290.500 CY	_____	_____	_____	_____
1540	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	11,673.000 SY	_____	_____	_____	_____
1550	404	404SD20-0010 COVER DEPTH SURVEY CONST.	11,167.000 SY	_____	_____	_____	_____
1560	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	4,413.800 CY	_____	_____	_____	_____
1570	404	404SD20-0015 CONCRETE CLASS T3, SUBSTRUCT. CONST.	1,022.500 CY	_____	_____	_____	_____
1580	ATTD	404SX20-0004 CONCRETE CL. A4 MOD. LTWT LOW SHRINK., SPR. STRUCT. CONST. (FRC)	123.100 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1590	406	406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST.	790,233.000 LB	_____	_____	_____	_____
1600	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	414,380.000 LB	_____	_____	_____	_____
1610	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	62,820.000 LB	_____	_____	_____	_____
1620	407	407SD20-0005 STR.STEEL PLATE GIRDER ASTM A709 GRADE36 --- (37,500 QTY)	LUMP SUM	LUMP SUM		_____	_____
1630	407	407SD20-0005 STR.STEEL PLATE GIRDER ASTM A709 GRADE36 -- (46,100 LBS)	LUMP SUM	LUMP SUM		_____	_____
1640	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W --- (1,014,300 QTY)	LUMP SUM	LUMP SUM		_____	_____
1650	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W --- (264,800 QTY)	LUMP SUM	LUMP SUM		_____	_____
1660	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W --- (337,500 QTY)	LUMP SUM	LUMP SUM		_____	_____
1670	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W --- (346,400 QTY)	LUMP SUM	LUMP SUM		_____	_____
1680	407	407SD20-0007 STR.ST.PLATE GIRDER ASTM A709 GR.50W --- (775,700 QTY)	LUMP SUM	LUMP SUM		_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1690	408	408SD20-0001 BEARING DEVICE, CONST.	34,650.000 LB				
1700	410	410SD20-0053 BRDG. MED. BARR. 42" SINGLE SLOPE	766.000 LF				
1710	410	410SD20-0060 CONCRETE PARAPET 42"	1,568.000 LF				
1720	ATTD	410SX20-0003 BRIDGE SUPERSTRUCTURE FIBER WRAP	1,957.000 SF				
1730	ATTD	410SX20-0011 PIER PROTECTION SYSTEM 54", CONST	2,719.000 LF				
1740	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING (B602)	LUMP SUM	LUMP SUM			
1750	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING (B603)	LUMP SUM	LUMP SUM			
1760	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING (B605)	LUMP SUM	LUMP SUM			
1770	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING (B607)	LUMP SUM	LUMP SUM			
1780	ATTD	410SX20-0014 BRIDGE INCIDENTALS TEMPORARY SHORING (B609)	LUMP SUM	LUMP SUM			
1790	410	410SX20-0021 RAILING 42" CPSR-1	515.000 LF				

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1800	412	412SD20-0024 REINF. STL. SPLICER #8 BAR	68.000 EA				
1810	412	412SD20-0044 SAW CUTTING	1,362.000 LF				
1820	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2000)	LUMP SUM	LUMP SUM			
1830	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2001)	LUMP SUM	LUMP SUM			
1840	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2002)	LUMP SUM	LUMP SUM			
1850	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2003)	LUMP SUM	LUMP SUM			
1860	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2020)	LUMP SUM	LUMP SUM			
1870	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2021)	LUMP SUM	LUMP SUM			
1880	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2900)	LUMP SUM	LUMP SUM			
1890	ATTD	413SX20-0002 DISM.& REM. EX. STR. (2901)	LUMP SUM	LUMP SUM			
1900	ATTD	413SX20-0002 DISM.& REM. EX. STR. (6514)	LUMP SUM	LUMP SUM			
1910	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2000)	LUMP SUM	LUMP SUM			
1920	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2001)	LUMP SUM	LUMP SUM			
1930	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2002)	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1940	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2003)	LUMP SUM	LUMP SUM		_____.	_____
1950	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2020)	LUMP SUM	LUMP SUM		_____.	_____
1960	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2021)	LUMP SUM	LUMP SUM		_____.	_____
1970	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2900)	LUMP SUM	LUMP SUM		_____.	_____
1980	ATTD	413SX20-0005 REM. PORT.OF EX.STR. (2901)	LUMP SUM	LUMP SUM		_____.	_____
1990	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	531.000 TON		_____.	_____.	_____
2000	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	420.000 TON		_____.	_____.	_____
2010	414	414SD20-0005 EROSION CTRL. STONE CL. II, EC-1	134.000 TON		_____.	_____.	_____
2020	414	414SD20-0008 DRY RIPRAP CL. AI	863.000 TON		_____.	_____.	_____
2030	414	414SD20-0010 DRY RIPRAP CL.I 18"	638.000 TON		_____.	_____.	_____
2040	414	414SD20-0012 DRY RIPRAP CL.I 26"	4,998.000 TON		_____.	_____.	_____
2050	414	414SD20-0056 DRY RIPRAP CL.II 38"	1,261.000 SY		_____.	_____.	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2060	415	415SD20-0004 CONC. SLAB SLOPE PROTECTION 4"	3,874.000 SY	_____	_____	_____	_____
2070	425	425SD20-0024 TYPE B HYDRO-DEMOLITION 4"	185.000 SY	_____	_____	_____	_____
2080	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B602)	3.000 DAY	_____	_____	_____	_____
2090	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B603)	3.000 DAY	_____	_____	_____	_____
2100	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B605)	3.000 DAY	_____	_____	_____	_____
2110	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B607)	4.000 DAY	_____	_____	_____	_____
2120	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (B609)	3.000 DAY	_____	_____	_____	_____
2130	ATTD	432SD20-0001 ELASTIC INCLUSION STANDARD EXPANDED POLYSTYRENE	138.000 CY	_____	_____	_____	_____
2140	501	501SD20-0001 UNDERDRAIN UD-1	41,004.000 LF	_____	_____	_____	_____
2150	501	501SD20-0004 UNDERDRAIN UD-4	1,999.000 LF	_____	_____	_____	_____
2160	501	501SD20-0006 CROSSDRAIN CD-1	252.000 LF	_____	_____	_____	_____
2170	501	501SD20-0007 CROSSDRAIN CD-2	1,279.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2180	501	501SD20-0009 OUTLET PIPE	1,191.000 LF				
2190	501	501SX20-0001 UNDERDRAIN 6" PERFORATED	937.000 LF				
2200	502	502SD20-0003 PAVED DITCH PG-2A	251.000 SY				
2210	502	502SD20-0011 CURB, STD. CG-2	610.000 LF				
2220	502	502SD20-0012 CURB, RADIAL CG-2	216.000 LF				
2230	502	502SD20-0014 CURB, STD. CG-3	737.000 LF				
2240	502	502SD20-0020 CURB, ASPHALT MC-3B	561.000 LF				
2250	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	1,919.000 LF				
2260	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	1,229.000 LF				
2270	502	502SD20-0029 ENTRANCE GUTTER CG-9D	2.000 SY				
2280	502	502SD20-0031 ENTRANCE GUTTER CG-13	61.000 SY				
2290	502	502SD20-0053 MEDIAN STRIP MS-1	136.000 SY				
2300	502	502SX20-0004 CURB CG-3 MOD.	283.000 LF				
2310	ATTD	502SX20-0011 MEDIAN BARRIER CSB-1	160.000 LF				

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2320	ATTD	502SX20-0011 MEDIAN BARRIER CSB-2	9,695.000 LF	_____	_____	_____	_____
2330	ATTD	502SX20-0011 MEDIAN BARRIER CSB-3 TY. I	21,018.000 LF	_____	_____	_____	_____
2340	ATTD	502SX20-0011 MEDIAN BARRIER CSB-3 TY. II	7,285.000 LF	_____	_____	_____	_____
2350	ATTD	502SX20-0011 MEDIAN BARRIER CSB-3 TY. III	129.000 LF	_____	_____	_____	_____
2360	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	326.000 CY	_____	_____	_____	_____
2370	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	62.000 SY	_____	_____	_____	_____
2380	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	1,210.000 SY	_____	_____	_____	_____
2390	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	17.000 EA	_____	_____	_____	_____
2400	505	505SD20-0011 GUARDRAIL GR-MGS1	13,661.000 LF	_____	_____	_____	_____
2410	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	1,792.000 LF	_____	_____	_____	_____
2420	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	31.000 LF	_____	_____	_____	_____
2430	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	18.000 EA	_____	_____	_____	_____
2440	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	16.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2450	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	19.000 EA	_____	_____	_____	_____
2460	505	505SD20-0027 GUARDRAIL TERMINAL GR-6 NCHRP 350	200.000 LF	_____	_____	_____	_____
2470	505	505SD20-0030 GUARDRAIL GR-2	4,689.000 LF	_____	_____	_____	_____
2480	505	505SD20-0040 GUARDRAIL GR-10	175.000 LF	_____	_____	_____	_____
2490	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	31.000 EA	_____	_____	_____	_____
2500	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	67,257.000 LF	_____	_____	_____	_____
2510	ATTD	505SX20-0058 GUARDRAIL CABLE END TERMINAL	4.000 EA	_____	_____	_____	_____
2520	506	506SD20-0002 RETAINING WALL RW-3	537.000 CY	_____	_____	_____	_____
2530	506	506SD20-0007 RETAINING WALL EXCAVATION	1,146.000 CY	_____	_____	_____	_____
2540	ATTD	506SX20-0003 WALL SPECIAL DESIGN RETAINING WALL	LUMP SUM	LUMP SUM		_____	_____
2550	ATTD	506SX20-0007 RETAINING STRUCTURE MSE WALL	7,080.000 SF	_____	_____	_____	_____
2560	507	507SD20-0005 FENCE FE-CL	8,249.000 LF	_____	_____	_____	_____
2570	507	507SD20-0007 LINE BRACE UNIT FE-CL	90.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2580	507	507SD20-0009 CORNER BRACE UNIT FE-CL	49.000 EA	_____	_____	_____	_____
2590	507	507SD20-0022 GATE FE-G 14'	4.000 EA	_____	_____	_____	_____
2600	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	9,400.000 LF	_____	_____	_____	_____
2610	507	507SD20-0033 PEDESTRIAN FENCE 10'	445.000 LF	_____	_____	_____	_____
2620	507	507SX20-0016 PEDESTRIAN FENCE 9'	334.700 LF	_____	_____	_____	_____
2630	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	44,144.000 SY	_____	_____	_____	_____
2640	509	509SD20-0001 FLOWABLE BACKFILL	165.700 CY	_____	_____	_____	_____
2650	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	4.000 EA	_____	_____	_____	_____
2660	510	510SD20-0046 ADJUST EXIST. WATER METER & BOX	2.000 EA	_____	_____	_____	_____
2670	510	510SD20-0050 ADJUST EXIST FRAME & COVER	3.000 EA	_____	_____	_____	_____
2680	510	510SX20-0016 REMOVE EXIST. FENCE .	3,563.000 LF	_____	_____	_____	_____
2690	510	510SX20-0017 RESET EXIST. GUARDRAIL .	1,880.000 LF	_____	_____	_____	_____
2700	510	510SX20-0031 MODIFY EXIST. INLET	5.000 EA	_____	_____	_____	_____
2710	511	511SD20-0001 ALLAYING DUST	9,688.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2720	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	73,683.000 LF	_____	_____	_____	_____
2730	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	43.000 EA	_____	_____	_____	_____
2740	512	512SD20-0008 IMPACT ATTEN.SER. TY. I TL- 2, <40 MPH	3.000 EA	_____	_____	_____	_____
2750	512	512SD20-0012 TYPE 3 BARRICADE 4'	14.000 EA	_____	_____	_____	_____
2760	512	512SD20-0013 TYPE 3 BARRICADE 8'	20.000 EA	_____	_____	_____	_____
2770	512	512SD20-0014 TEMPORARY SIGN	5,269.000 SF	_____	_____	_____	_____
2780	512	512SD20-0015 AGGREGATE MATERIAL NO. 25 OR 26	350.000 TON	_____	_____	_____	_____
2790	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	16,710.000 HR	_____	_____	_____	_____
2800	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	2,236,780.000 DAY	_____	_____	_____	_____
2810	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,500.000 HR	_____	_____	_____	_____
2820	512	512SD20-0026 ELECTRONIC ARROW BOARD	17,010.000 HR	_____	_____	_____	_____
2830	512	512SD20-0027 FLAGGER SERVICE	3,000.000 HR	_____	_____	_____	_____
2840	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	65,762.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2850	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,279,312.000 LF	_____	_____	_____	_____
2860	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	500.000 EA	_____	_____	_____	_____
2870	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	5,475.000 LF	_____	_____	_____	_____
2880	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	14,878.000 LF	_____	_____	_____	_____
2890	512	512SD20-0065 TEMP. PVMT MRKG TY. D, CL. III, 24"	40.000 LF	_____	_____	_____	_____
2900	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	188.000 DAY	_____	_____	_____	_____
2910	ATTD	512SX20-0019 TRAFFIC CONTROL PORT. CHANGEABLE MESS. SIGN	4.000 EA	_____	_____	_____	_____
2920	ATTD	512SX20-0019 TRAFFIC CONTROL TRUCKS ENTERING HIGHWAY SYSTEM	9.000 EA	_____	_____	_____	_____
2930	ATTD	512SX20-0019 TRAFFIC CONTROL WORK ZONE DIGITAL SPEED LIMIT SIGN TRAILER (TYPE C)	2.000 EA	_____	_____	_____	_____
2940	512	512SX20-0020 MODIFY SIGNAL PLEASANT VALLEY & EARLY	LUMP SUM	LUMP SUM	_____	_____	_____
2950	ATTD	512SX20-0040 POLICE PATROL UNIFORMED FLAGGERS	1,500.000 HR	_____	_____	_____	_____
2960	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2970	ATTD	514SX20-0001 FIELD OFFICE MODIFIED TYPE I	78.000 MO	_____	_____	_____	_____
2980	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	199,341.000 SY	_____	_____	_____	_____
2990	515	515SD20-0005 FLEXIBLE PAVE. PLANING ABOVE 2"-4"	7,274.000 SY	_____	_____	_____	_____
3000	515	515SD20-0006 FLEX PAVEMENT PLANING ABOVE 4"	17,076.000 SY	_____	_____	_____	_____
3010	515	515SX20-0004 FLEXIBLE PAVEMENT PLANING SLOPE CORRECT	97,930.000 SY	_____	_____	_____	_____
3020	515	515SX20-0004 FLEXIBLE PAVEMENT PLANING UP TO 9.5 IN SHLDR STRENGTHENING	47,524.000 SY	_____	_____	_____	_____
3030	516	516SX20-0008 DEMO. OF BLDG. D-1 SHED	LUMP SUM	LUMP SUM	_____	_____	_____
3040	516	516SX20-0009 CLEARING PARCEL NO. 001 D-701 SIGN	LUMP SUM	LUMP SUM	_____	_____	_____
3050	516	516SX20-0009 CLEARING PARCEL NO. 001 D-901 LIGHT POLE	LUMP SUM	LUMP SUM	_____	_____	_____
3060	516	516SX20-0009 CLEARING PARCEL NO. 002 D-702 SIGN	LUMP SUM	LUMP SUM	_____	_____	_____
3070	516	516SX20-0009 CLEARING PARCEL NO. 005 D-700 SIGN	LUMP SUM	LUMP SUM	_____	_____	_____
3080	516	516SX20-0009 CLEARING PARCEL NO. 012 D-902 LIGHT POLE	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3090	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
3100	519	519SX20-0001 SOUND BARRIER WALL ABSORPTIVE	363,147.000 SF				
3110	519	519SX20-0001 SOUND BARRIER WALL COLOR COATING	739,539.000 SF				
3120	519	519SX20-0001 SOUND BARRIER WALL STR. MOUNTED REFLECTIVE	6,622.000 SF				
3130	520	520SD20-0003 1" WATER SERVICE LINE	185.000 LF				
3140	520	520SD20-0014 6" DI WATER MAIN	8.000 LF				
3150	520	520SD20-0020 12" DI WATER MAIN	985.000 LF				
3160	520	520SD20-0167 5/8" WATER METER BOX & YOKE	1.000 EA				
3170	520	520SD20-0179 4" SANITARY SERVICE LATERAL CONNECTION	37.000 LF				
3180	520	520SD20-0186 8" DI SANITARY SEWER PIPE	334.000 LF				
3190	520	520SD20-0200 16" DI SANITARY SEWER PIPE	292.000 LF				
3200	520	520SD20-0206 20" DI SANITARY SEWER PIPE	376.000 LF				
3210	520	520SD20-0272 SANITARY SEWER MANHOLE	131.300 LF				

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3220	520	520SD20-0274 MANHOLE FRAME & COVER F & C-1	11.000 EA	_____	_____	_____	_____
3230	520	520SD20-0287 6" STEEL ENCASE. PIPE	40.000 LF	_____	_____	_____	_____
3240	520	520SD20-0299 24" STEEL JACKED ENCASEMENT PIPE	439.000 LF	_____	_____	_____	_____
3250	520	520SD20-0301 30" STEEL ENCASE. PIPE	75.000 LF	_____	_____	_____	_____
3260	520	520SD20-0304 36" STEEL JACKED ENCASEMENT PIPE	168.000 LF	_____	_____	_____	_____
3270	ATTD	520SX20-0002 WATER FACILITIES PIPE LINE CROSSING MARKER	2.000 EA	_____	_____	_____	_____
3280	520	520SX20-0005 4" SEWER CLEANOUT	1.000 EA	_____	_____	_____	_____
3290	520	520SX20-0007 SEWER UTILITY 30" STEEL JACKED ENCASEMENT PIPE	140.000 LF	_____	_____	_____	_____
3300	ATTD	520SX20-0282 CONCRETE ENCASEMENT .	56.600 CY	_____	_____	_____	_____
3310	ATTD	522SX20-0004 ASBESTOS REMOVAL (2000)	LUMP SUM	LUMP SUM	_____	_____	_____
3320	ATTD	522SX20-0004 ASBESTOS REMOVAL (2001)	LUMP SUM	LUMP SUM	_____	_____	_____
3330	ATTD	522SX20-0004 ASBESTOS REMOVAL (2002)	LUMP SUM	LUMP SUM	_____	_____	_____
3340	ATTD	522SX20-0004 ASBESTOS REMOVAL (2003)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3350	ATTD	522SX20-0004 ASBESTOS REMOVAL (2020)	LUMP SUM	LUMP SUM			
3360	ATTD	522SX20-0004 ASBESTOS REMOVAL (2021)	LUMP SUM	LUMP SUM			
3370	ATTD	522SX20-0004 ASBESTOS REMOVAL (6514)	LUMP SUM	LUMP SUM			
3380	ATTD	523SP20-0002 STORM WATER MANAGEMENT LOW PERM. LINER	11,164.000 SY				
3390	ATTD	523SX20-0002 SOIL BIORETENTION SOIL MEDIA	607.000 CY				
3400	602	602SD20-0004 TOPSOIL CLASS B	3,902.000 CY				
3410	602	602SX20-0006 TOPSOIL CLASS B, 3"	10,325.000 CY				
3420	603	603SD20-0002 TEMPORARY SEED	4,150.000 LB				
3430	603	603SD20-0003 REGULAR SEED	8,344.000 LB				
3440	603	603SD20-0004 OVERSEEDING	5,632.000 LB				
3450	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	104,665.000 SY				
3460	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	200,860.000 SY				
3470	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	50,215.000 SY				

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3480	603	603SD20-0014 FERTILIZER NITROGEN - N	2,878.000 LB	_____	_____	_____	_____
3490	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	2,110.000 LB	_____	_____	_____	_____
3500	603	603SD20-0016 FERTILIZER POTASSIUM - K	2,110.000 LB	_____	_____	_____	_____
3510	603	603SD20-0017 LIME	173.000 TON	_____	_____	_____	_____
3520	605	605SX20-0019 TREE SWM & SCREENING LANDSCAPE	43.000 EA	_____	_____	_____	_____
3530	605	605SX20-0020 SHRUB SWM LANDSCAPE	92.000 EA	_____	_____	_____	_____
3540	605	605SX20-0021 HERB PERENNIAL/ GRASS SWM LANDSCAPE	2,318.000 EA	_____	_____	_____	_____
3550	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	3,610.000 SY	_____	_____	_____	_____
3560	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	350.000 SY	_____	_____	_____	_____
3570	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	24,509.000 SY	_____	_____	_____	_____
3580	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	220.000 EA	_____	_____	_____	_____
3590	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	41.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3600	700	700SD20-0005 REMOVE EXISTING 3 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
3610	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	2.000 EA	_____	_____	_____	_____
3620	700	700SD20-0013 RELOCATE EX. 2 POST GRND MOUNT SGN PANEL	10.000 EA	_____	_____	_____	_____
3630	700	700SD20-0018 VA SIGN POST W4 X 13	300.000 LF	_____	_____	_____	_____
3640	700	700SD20-0019 VA SIGN POST W6 X 12	210.000 LF	_____	_____	_____	_____
3650	700	700SD20-0021 VIA SIGN POST W12 X 14	68.000 LF	_____	_____	_____	_____
3660	700	700SD20-0022 VIA SIGN POST W12 X 16	280.000 LF	_____	_____	_____	_____
3670	700	700SD20-0023 VIA SIGN POST W12 X 19	324.000 LF	_____	_____	_____	_____
3680	700	700SD20-0024 VIA SIGN POST W14 X 22	38.000 LF	_____	_____	_____	_____
3690	700	700SD20-0025 VIA SIGN POST W14 X 26	129.000 LF	_____	_____	_____	_____
3700	700	700SD20-0027 VIA SIGN POST W16 X 31	165.000 LF	_____	_____	_____	_____
3710	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	730.000 LF	_____	_____	_____	_____
3720	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	36.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3730	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	232.000 LF	_____	_____	_____	_____
3740	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	210.000 LF	_____	_____	_____	_____
3750	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	53.000 EA	_____	_____	_____	_____
3760	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	10.000 EA	_____	_____	_____	_____
3770	700	700SD20-0045 CONC. FOUND. SSP-VA, 2'6" DIA. X 7' DEEP	10.000 EA	_____	_____	_____	_____
3780	700	700SD20-0046 CONC. FOUND. SSP-VA, 1'9" DIA. X 4'6" DEEP	20.000 EA	_____	_____	_____	_____
3790	700	700SD20-0047 CONC. FOUND. SSP-VA, 2'6" DIA. X 6' DEEP	4.000 EA	_____	_____	_____	_____
3800	700	700SD20-0048 CONC. FOUND. SSP-VIA, 2'3" DIA. X 4'6" DEEP	1.000 EA	_____	_____	_____	_____
3810	700	700SD20-0049 CONC. FOUND. SSP-VIA, 3' DIA. X 7' DEEP	48.000 EA	_____	_____	_____	_____
3820	700	700SD20-0053 CONC. FOUND. SSP-VIA, 4' DIA. X 9'6" DEEP	4.000 EA	_____	_____	_____	_____
3830	700	700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE	400.000 CY	_____	_____	_____	_____
3840	700	700SD20-0066 PEDESTAL POLE PF-2, 10'	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3850	700	700SD20-0069 CONC. FOUND. PF-2	1.000 EA	_____	_____	_____	_____
3860	700	700SD20-0143 6 CONDUCTOR CABLE	1,380.000 LF	_____	_____	_____	_____
3870	700	700SD20-0146 12 CONDUCTOR CABLE	2,360.000 LF	_____	_____	_____	_____
3880	700	700SD20-0148 8 CONDUCTOR CABLE EGC	585.000 LF	_____	_____	_____	_____
3890	700	700SD20-0178 JUNCTION BOX JB-S2	14.000 EA	_____	_____	_____	_____
3900	700	700SD20-0179 JUNCTION BOX JB-S3	2.000 EA	_____	_____	_____	_____
3910	700	700SD20-0192 BORED CONDUIT 3"	610.000 LF	_____	_____	_____	_____
3920	700	700SD20-0194 CONDUIT PVC 2"	1,161.000 LF	_____	_____	_____	_____
3930	700	700SD20-0196 CONDUIT PVC 4"	454.000 LF	_____	_____	_____	_____
3940	700	700SD20-0197 TRENCH EXCAVATION ECI-1	740.000 LF	_____	_____	_____	_____
3950	700	700SD20-0199 TEST BORE	20.000 EA	_____	_____	_____	_____
3960	700	700SX20-0002 SIGN STRUCTURE, OVERHEAD SPAN (75'-85')	2.000 EA	_____	_____	_____	_____
3970	700	700SX20-0003 SIGN STRUCTURE, OVERHEAD CANT. (30'-50')	16.000 EA	_____	_____	_____	_____
3980	ATTD	700SX20-0007 CONDUCTOR CABLE AND GROUND WIRE	145.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3990	700	700SX20-0007 CONDUCTOR CABLE NUMBER 6 EGC	450.000 LF	_____	_____	_____	_____
4000	700	700SX20-0017 REMOVE EXIST. OVERHEAD SIGN STRUCTURE .	6.000 EA	_____	_____	_____	_____
4010	700	700SX20-0019 TRAFFIC SIGN U-TYPE ROLLED RAIL STEEL POST; 2.00 LBS/FT	886.000 LF	_____	_____	_____	_____
4020	700	700SX20-0021 TRAFFIC SIGN BARRIER MOUNTED SIGN SUPPORT	16.000 EA	_____	_____	_____	_____
4030	701	701SD20-0001 SIGN PANEL	7,961.000 SF	_____	_____	_____	_____
4040	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	6,405.000 LF	_____	_____	_____	_____
4050	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	315.000 LF	_____	_____	_____	_____
4060	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	178,840.000 LF	_____	_____	_____	_____
4070	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	7,375.000 LF	_____	_____	_____	_____
4080	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	660.000 LF	_____	_____	_____	_____
4090	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	4,670.000 LF	_____	_____	_____	_____
4100	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	1,998.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
4110	ATTD	704SD20-0033 INLAID PAVEMENT MARKER CONCRETE	44.000 EA	_____	_____	_____	_____
4120	704	704SD20-0039 PVTM MSG. MARK. "SCHOOL" TY B, CL II, 6'	1.000 EA	_____	_____	_____	_____
4130	704	704SD20-0048 PVTM SYMB MRKG SGL TURN ARR. TY B CL II	2.000 EA	_____	_____	_____	_____
4140	704	704SD20-0060 SYMB MRKG LANE REDUCTION ARR TY B CL II	4.000 EA	_____	_____	_____	_____
4150	704	704SD20-0087 PVTM SYMB MRKG YIELD 2' X 3' TY B, CL II	18.000 EA	_____	_____	_____	_____
4160	704	704SD20-0096 SYMB MRKG BICYCLE THRU ARROW TY B CL II	5.000 EA	_____	_____	_____	_____
4170	704	704SD20-0102 SYMB MRKG HELMETED BICYCLIST TY B CL II	5.000 EA	_____	_____	_____	_____
4180	704	704SD20-0105 PVTM SYMB MRKG SHARED LANE TY B CL II	4.000 EA	_____	_____	_____	_____
4190	704	704SD20-0113 TYPE A CLASS I PVTM LINE MRKG 6"	2,524,847.000 LF	_____	_____	_____	_____
4200	704	704SD20-0114 TYPE A CLASS I PVTM LINE MRKG 8"	621,187.000 LF	_____	_____	_____	_____
4210	704	704SD20-0115 TYPE A CLASS I PVTM LINE MRKG 12"	100,483.000 LF	_____	_____	_____	_____
4220	510	704SP20-0001 REMOVAL OF SRPM	14,709.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000116280C01

Oversight/State Project No.: 0081-115-270, C501

Order No.: N24

Federal Project No.: NHPP-0813(222)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
4230	704	704SX20-0001 PAVEMENT MARKING TYPE D CLASS III CONTRAST PVMT MRKG 8" CONTRAST TAPE	14,878.000 LF	_____	_____	_____	_____
4240	ATTD	704SX20-0002 PAVEMENT MARKING TEMP. INLAID PVMT MARKER ASPHALT	13,891.000 EA	_____	_____	_____	_____
4250	ATTD	801SX20-0002 COMMUNICATION EQUIP. TIME-LAPSE MONITORING SYSTEM	LUMP SUM	LUMP SUM		_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____