

Schedule of Items

Proposal ID: CM526PMA127812 Oversight/State Project No.: PM5A-145-F26, P401

Order No.: 560

Federal Project No.: PM05(554)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY. I OR II NO. 21A OR 21B	50.000 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	41,591.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	11,675.000 LF	_____	_____	_____	_____
0040	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	168,674.000 LF	_____	_____	_____	_____
0050	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	36,378.190 TON	_____	_____	_____	_____
0060	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0A	550.000 TON	_____	_____	_____	_____
0070	512	512SD20-0027 FLAGGER SERVICE	2,208.000 HR	_____	_____	_____	_____
0080	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	686,774.000 LF	_____	_____	_____	_____
0090	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	1,594.000 LF	_____	_____	_____	_____
0100	512	512SP20-0002 MAINTENANCE OF TRAFFIC MOT	LUMP SUM	LUMP SUM		_____	_____
0110	515	515SD20-0013 FLEXIBLE PAVE. PLANING 0"- 2"	395,124.190 SY	_____	_____	_____	_____
0120	700	700SD20-0118 14/1 CONDUCTOR CABLE ENCLOSED	8,070.000 LF	_____	_____	_____	_____
0130	700	700SD20-0182 CONDUIT PVC 1"	375.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM526PMA127812 Oversight/State Project No.: PM5A-145-F26, P401

Order No.: 560

Federal Project No.: PM05(554)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	703	703SD20-0042 LOOP SAW CUT 3/8"	2,328.000 LF	_____	_____	_____	_____
0150	703	703SD20-0043 LOOP SAW CUT 5/8"	500.000 LF	_____	_____	_____	_____
0160	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	232,650.000 LF	_____	_____	_____	_____
0170	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	113,792.000 LF	_____	_____	_____	_____
0180	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	80.000 LF	_____	_____	_____	_____
0190	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	1,557.000 LF	_____	_____	_____	_____
0200	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	1,861.000 EA	_____	_____	_____	_____
0210	704	704SD20-0038 PVMT MSG. MARK. "SCHOOL" TY B, CL I, 6'	2.000 EA	_____	_____	_____	_____
0220	704	704SD20-0041 PVMT MSG. MARK. R/R CROSSING TY. B, CL. I	2.000 EA	_____	_____	_____	_____
0230	704	704SD20-0044 PVMT SYMB MRKG THRU ARROW TY B, CL I	2.000 EA	_____	_____	_____	_____
0240	704	704SD20-0047 PVMT SYMB MRKG SGL TURN ARR. TY B CL I	122.000 EA	_____	_____	_____	_____
0250	704	704SX20-0001 PAVEMENT MARKING TRANSVERSE WHITE RAISED RUMBLE STRIPS	384.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 4

Proposal ID: CM526PMA127812 Oversight/State Project No.: PM5A-145-F26, P401

Order No.: 560

Federal Project No.: PM05(554)

Contractor: _____

Section: 0001

Total: _____

SECTION: 0002

ALTERNATE ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIALS	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____