

Schedule of Items

Proposal ID: CM426PM5127962

Oversight/State Project No.: PM45-964-F26, P401

Order No.: 484

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. 21A OR 21B	618.000 TON	_____	_____	_____	_____
0020	303	303SD20-0006 EXTRA EXCAVATION	312.000 CY	_____	_____	_____	_____
0030	ATTD	305SP20-0003 AGR. BASE MAT. TY.I OR II NO. 21A OR 21B	5,853.540 TON	_____	_____	_____	_____
0040	ATTD	305SP20-0005 MACHINING SHOULDERS	21,615.000 LF	_____	_____	_____	_____
0050	310	310SD20-0001 TACK COAT	26,999.000 GAL	_____	_____	_____	_____
0060	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	54,384.000 LF	_____	_____	_____	_____
0070	315	315SD20-0036 ASPH. CONC. TY. SM-12.5E MAINT	9,445.750 TON	_____	_____	_____	_____
0080	315	315SD20-0043 ASPH. CONC. TY. IM-19.0D MAINT	6,545.630 TON	_____	_____	_____	_____
0090	315	315SD20-0044 ASPH. CONC. TY. IM-19.0E MAINT	9,970.400 TON	_____	_____	_____	_____
0100	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	3,730.030 TON	_____	_____	_____	_____
0110	ATTD	315SX20-0002 PAVEMENT ASPHALT REPAIR MASTIC	6,700.000 LB	_____	_____	_____	_____
0120	ATTD	316SP20-0004 PATCH HCC PAVEMENT TYPE IV-A	1,407.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM426PM5127962

Oversight/State Project No.: PM45-964-F26, P401

Order No.: 484

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	ATTD	323SD20-0010 PARTIAL DEPTH PCC PATCHING (ASPHALT PATCH MIX TYPE AND DEPTH) IM- 19.0E UP TO 4" DEEP	6,903.000 SY	_____	_____	_____	_____
0140	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	43.000 EA	_____	_____	_____	_____
0150	505	505SD20-0010 RUB RAIL	30.000 LF	_____	_____	_____	_____
0160	505	505SD20-0011 GUARDRAIL GR-MGS1	19,776.000 LF	_____	_____	_____	_____
0170	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	287.000 LF	_____	_____	_____	_____
0180	505	505SD20-0015 RADIAL GUARDRAIL GR- MGS1A	50.000 LF	_____	_____	_____	_____
0190	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	18.000 EA	_____	_____	_____	_____
0200	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	18.000 EA	_____	_____	_____	_____
0210	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	10.000 EA	_____	_____	_____	_____
0220	505	505SD20-0047 FIXED OBJECT ATTACH. GR- FOA-3 TY. I	2.000 EA	_____	_____	_____	_____
0230	505	505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II	1.000 EA	_____	_____	_____	_____
0240	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	19,279.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM426PM5127962

Oversight/State Project No.: PM45-964-F26, P401

Order No.: 484

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	ATTD	505SX20-0001 HAND DIG GUARDRAIL POST HAND DIG GUARDRAIL POST	900.000 EA	_____	_____	_____	_____
0260	505	505SX20-0058 GUARDRAIL NS GR MGS2 END TERMINAL SITE PREPARATION, MODERATE	18.000 EA	_____	_____	_____	_____
0270	505	505SX20-0058 GUARDRAIL NS GR TERMINAL SITE PREPARATION, MINOR	1.000 EA	_____	_____	_____	_____
0280	505	505SX20-0058 GUARDRAIL SP. DES. GR. BR. ATTACH BR-GR (BR-GR-20B)	2.000 EA	_____	_____	_____	_____
0290	505	505SX20-0058 GUARDRAIL SP. DES. GR. BR. ATTACH BR-GR (BR-GR-20C)	1.000 EA	_____	_____	_____	_____
0300	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	61,378.000 LF	_____	_____	_____	_____
0310	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	34,214.000 LF	_____	_____	_____	_____
0320	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	88,541.000 LF	_____	_____	_____	_____
0330	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	3,502.000 LF	_____	_____	_____	_____
0340	512	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	_____
0350	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	5,290.000 SY	_____	_____	_____	_____
0360	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	37,757.860 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM426PM5127962

Oversight/State Project No.: PM45-964-F26, P401

Order No.: 484

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0370	515	515SD20-0017 RIGID PAV.TIE-IN PLANING 0"-2"	3,731.000 SY	_____	_____	_____	_____
0380	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	63,334.000 LF	_____	_____	_____	_____
0390	704	704SD20-0028 TYPE B CLASS VI PVMT LINE MRKG 8"	50.000 LF	_____	_____	_____	_____
0400	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	2,251.000 LF	_____	_____	_____	_____
0410	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	1,235.000 LF	_____	_____	_____	_____
0420	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	421.000 EA	_____	_____	_____	_____

Section: 0001

Total:

SECTION: 0002

ALTERNATE BID ITEM

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0430	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____

Section: 0002

Total:

Total Bid: