

Schedule of Items

Proposal ID: CM426PM1127956

Oversight/State Project No.: PM41-964-F26, P401

Order No.: 480

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. 21A OR 21B	320.000 TON	_____	_____	_____	_____
0020	303	303SD20-0006 EXTRA EXCAVATION	160.000 CY	_____	_____	_____	_____
0030	310	310SD20-0001 TACK COAT	22,723.000 GAL	_____	_____	_____	_____
0040	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	19,642.000 LF	_____	_____	_____	_____
0050	315	315SD20-0036 ASPH. CONC. TY. SM-12.5E MAINT	10,539.180 TON	_____	_____	_____	_____
0060	315	315SD20-0044 ASPH. CONC. TY. IM-19.0E MAINT	7,287.100 TON	_____	_____	_____	_____
0070	315	315SD20-0100 ASPHALT CONCRETE BASE COURSE BM-25.0	2,625.210 TON	_____	_____	_____	_____
0080	315	315SP20-0049 ASPH. CONC. BMD P+VO SM- 9.5D	2,957.730 TON	_____	_____	_____	_____
0090	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	4,255.970 TON	_____	_____	_____	_____
0100	ATTD	316SP20-0004 PATCH HCC PAVEMENT TYPE IV-A	726.000 SY	_____	_____	_____	_____
0110	ATTD	323SD20-0010 PARTIAL DEPTH PCC PATCHING (ASPHALT PATCH MIX TYPE AND DEPTH) IM- 19.0E UP TO 4" DEEP	720.000 SY	_____	_____	_____	_____
0120	323	323SD20-0030 TRAVEL LANE PATCHING (PATCH MIX TYPE) IM-19.0D	116.160 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM426PM1127956

Oversight/State Project No.: PM41-964-F26, P401

Order No.: 480

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	9,107.000 LF	_____	_____	_____	_____
0140	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	44,448.000 LF	_____	_____	_____	_____
0150	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	2,115.000 LF	_____	_____	_____	_____
0160	512	512SP20-0002 MAINTENANCE OF TRAFFIC MAINTENANCE OF TRAFFIC	LUMP SUM	LUMP SUM		_____	_____
0170	515	515SD20-0013 FLEXIBLE PAVE. PLANING 0"- 2"	110,371.220 SY	_____	_____	_____	_____
0180	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	41,184.000 SY	_____	_____	_____	_____
0190	ATTD	515SX20-0002 FLEXIBLE PAVE. PLANING 6" DEEP	12,531.200 SY	_____	_____	_____	_____
0200	ATTD	515SX20-0002 FLEXIBLE PAVE. PLANING 8" DEEP MILLING	7,955.200 SY	_____	_____	_____	_____
0210	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	180.000 LF	_____	_____	_____	_____
0220	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	30.000 LF	_____	_____	_____	_____
0230	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	82,243.000 LF	_____	_____	_____	_____
0240	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	7,724.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM426PM1127956

Oversight/State Project No.: PM41-964-F26, P401

Order No.: 480

Federal Project No.: PM04545

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0250	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	7,627.000 LF	_____	_____	_____	_____
0260	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	807.000 EA	_____	_____	_____	_____
0270	704	704SD20-0059 SYMB MRKG LANE REDUCTION ARR TY B CL I	2.000 EA	_____	_____	_____	_____
0280	704	704SD20-0062 SYMB MRKG WRONG-WAY ARROW TY B CL I	2.000 EA	_____	_____	_____	_____
0290	704	704SX20-0001 PAVEMENT MARKING TYPE B CLASS VI CONTRAST PVMT MRKG 12"	1,772.000 LF	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____