

Schedule of Items

Proposal ID: C0000117418B28

Oversight/State Project No.: 0264-965-411, B628

Order No.: N87

Federal Project No.: NHPP-BR05(321)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	407SX20-0003 STRUCT. STEEL STRUCT. STEEL ASTM A709 GRADE 36 - SPAN C BEAM 20 WEB CRACK AND FLANGE REPAIR	LUMP SUM	LUMP SUM			
0020	ATTD	407SX20-0006 STRUCT. STEEL STRUC. STEEL ASTM A709 GRADE 36 - SPAN C BAY 19 DIAPHRAGM CONNEC. PLATE REPLACE.	LUMP SUM	LUMP SUM			
0030	ATTD	407SX20-0006 STRUCT. STEEL STRUCT. STEEL ASTM A709 GRADE 36 - SPAN C BAY 9 DIAPHRAGM CONNEC. PLATE REPLACE	LUMP SUM	LUMP SUM			
0040	411	411SX20-0001 PRE. & SPOT COAT EX. STR. FAILING COATING AND IMPACT DAMAGED COATING, SCRAPES AND GOUGES ON SPAN C BAY 19	761.000 SF				
0050	411	411SX20-0001 PRE. & SPOT COAT EX. STR. SPAN C BEAM 10 BOTTOM FLANGE AND SPAN C BAY 9 DIAPHRAGM CONNECTION PLATE REPAIRS	24.000 SF				
0060	411	411SX20-0001 PRE. & SPOT COAT EX. STR. SPAN C BEAM 20 WEB CRACK REPAIR AND FLANGE REPAIR	93.000 SF				
0070	411	411SX20-0002 ZONE COAT. EX. STR. COAT BEAM ENDS PER PLAN INCLUDING BEAMS STIFFENERS AND DIAPHRAGMS	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000117418B28

Oversight/State Project No.: 0264-965-411, B628

Order No.: N87

Federal Project No.: NHPP-BR05(321)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0080	411	411SX20-0006 DISPOSAL OF MATERIAL (STR. NO. 22232)	LUMP SUM	LUMP SUM			
0090	412	412SD20-0010 ANCHOR BOLT REPLACEMENT	2.000 EA				
0100	412	412SD20-0013 CRACK REPAIR TYPE B	147.000 LF				
0110	412	412SD20-0017 EMBEDDED GALVANIC ANODES	637.000 EA				
0120	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR	44.000 SY				
0130	ATTD	412SX20-0009 SUPERSTR. WID./REPAIR GRINDING MINOR DEFECT ON SPAN C BEAM 10 BOTTOM FLANGE	1.000 EA				
0140	ATTD	412SX20-0009 SUPERSTR. WID./REPAIR GRINDING MINOR DEFECT OVER RIGHT TRAVEL LANE	2.000 EA				
0150	ATTD	412SX20-0009 SUPERSTR. WID./REPAIR JACKING AND BLOCKING BEAM - FOR TYPE B1 BEARING REPAIR AND ANCHOR BOLT REPLACE	12.000 EA				
0160	ATTD	412SX20-0009 SUPERSTR. WID./REPAIR JACKING AND BLOCKING BEAM - SPAN C BEAM 20 AT PIER 3	1.000 EA				

Schedule of Items

Proposal ID: C0000117418B28

Oversight/State Project No.: 0264-965-411, B628

Order No.: N87

Federal Project No.: NHPP-BR05(321)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0170	ATTD	412SX20-0012 SUPERSTR. WID./REPAIR REINSTALL EXISTING DIAPHRAGM - SPAN C BAY 19 FIRST INTERMEDIATE DIAPHRAGM	300.000 LB				
0180	ATTD	412SX20-0012 SUPERSTR. WID./REPAIR REINSTALL EXISTING DIAPHRAGMS - SPAN C BAY 19 SECOND INTERMEDIATE DIAPHRAGM	300.000 LB				
0190	ATTD	412SX20-0012 SUPERSTR. WID./REPAIR REINSTALL EXISTING DIAPHRAGMS - SPAN C BAY 9 FIRST INTERMEDIATE DIAPHRAGM	200.000 LB				
0200	ATTD	412SX20-0013 BR.SUPERSTR. WID./REPAIR STRUCTURAL STEEL HEAT- STRAIGHTENING - SPAN C BEAM 20	LUMP SUM	LUMP SUM			
0210	ATTD	412SX20-0013 BR.SUPERSTR. WID./REPAIR STRUCTURAL STEEL HEAT- STRAIGHTENING - SPAN C BEAM 20 OVER LEFT TURN LANE	LUMP SUM	LUMP SUM			
0220	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. NO. 22232)	LUMP SUM	LUMP SUM			
0230	413	413SX20-0005 REM. PORT.OF EX.STR. MATERIAL REMOVAL FOR SPAN BEAM 20 WEB CRACK REPAIR AND FLANGE REPAIR	LUMP SUM	LUMP SUM			

Schedule of Items

Proposal ID: C0000117418B28

Oversight/State Project No.: 0264-965-411, B628

Order No.: N87

Federal Project No.: NHPP-BR05(321)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0240	413	413SX20-0005 REM. PORT.OF EX.STR. MATERIAL REMOVAL FOR SPAN C BAY 9 DIAPHRAGM CONNECTION PLATE REPLACEMENT	LUMP SUM	LUMP SUM			
0250	413	413SX20-0005 REM. PORT.OF EX.STR. STRUCTURAL STEEL REMOVAL FOR OTHER REPAIRS	LUMP SUM	LUMP SUM			
0260	426	426SD20-0001 REPLACE BEARING	1.000 EA				
0270	426	426SD20-0002 RESET EXIST. ROCKER EXPN. BEARING	12.000 EA				
0280	426	426SD20-0005 GRINDING MINOR DEFECT	10.000 EA				
0290	426	426SD20-0009 PARTIAL BEAM/GIRDER REPLACEMENT BEAM 20 WEB WINDOW REPAIR	30.000 LB				
0300	426	426SX20-0004 FIELD WELDING-FULL PENETRATION GROOVE BEAM 20 WEB REPAIR WELD	3.000 LF				
0310	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (STR. NO. 22232)	4.000 DAY				
0320	512	512SD20-0014 TEMPORARY SIGN	1,400.000 SF				
0330	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,400.000 HR				

Schedule of Items

Proposal ID: C0000117418B28

Oversight/State Project No.: 0264-965-411, B628

Order No.: N87

Federal Project No.: NHPP-BR05(321)

Contractor: _____

SECTION: 0001

ALL BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0340	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	37,000.000 DAY	_____	_____	_____	_____
0350	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,400.000 HR	_____	_____	_____	_____
0360	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,400.000 HR	_____	_____	_____	_____
0370	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0380	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0390	ATTD	522SX20-0004 ASBESTOS REMOVAL ASBESTOS REMOVAL STR. NO. 22232	LUMP SUM	LUMP SUM		_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____