

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0013 ENDWALL EW-12	2.000 EA	_____	_____	_____	_____
0020	302	302SD20-0023 15" PIPE	93.000 LF	_____	_____	_____	_____
0030	302	302SD20-0028 18" PIPE	250.000 LF	_____	_____	_____	_____
0040	302	302SD20-0199 15" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0050	302	302SD20-0200 18" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0060	302	302SD20-0259 DROP INLET DI-2C,L=6'	1.000 EA	_____	_____	_____	_____
0070	302	302SD20-0313 DROP INLET DI-3B,L=8'	1.000 EA	_____	_____	_____	_____
0080	302	302SD20-0314 DROP INLET DI-3B,L=10'	2.000 EA	_____	_____	_____	_____
0090	302	302SD20-0446 DROP INLET DI-5	3.000 EA	_____	_____	_____	_____
0100	302	302SD20-0662 MANHOLE MH-1 OR 2	2.210 LF	_____	_____	_____	_____
0110	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0120	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. 57	20.000 TON	_____	_____	_____	_____
0130	302	302SX20-0005 PRECAST BOX CULVERT SINGLE BARREL 10' x 5'	15.000 LF	_____	_____	_____	_____
0140	303	303SD20-0001 REGULAR EXCAVATION	4,410.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0007 BORROW EXCAVATION MIN. CBR 5	4,065.000 CY	_____	_____	_____	_____
0160	303	303SD20-0013 GEOTEXTILE EMBANKMENT STAB.	750.000 SY	_____	_____	_____	_____
0170	303	303SD20-0017 MINOR STR. EXCAV. BOX CULVERT	64.000 CY	_____	_____	_____	_____
0180	303	303SD20-0021 TEMPORARY DIVERSION DIKE	2,529.000 LF	_____	_____	_____	_____
0190	303	303SD20-0022 CHECK DAM ROCK TY. I	23.000 EA	_____	_____	_____	_____
0200	303	303SD20-0023 CHECK DAM ROCK TY. II	6.000 EA	_____	_____	_____	_____
0210	303	303SD20-0028 DEWATERING BASIN EC-8	3.000 EA	_____	_____	_____	_____
0220	303	303SD20-0029 SILTATION CONTROL EXCAVATION	574.000 CY	_____	_____	_____	_____
0230	303	303SD20-0030 INLET PROTECTION TYPE A	4.000 EA	_____	_____	_____	_____
0240	303	303SD20-0031 INLET PROTECTION TYPE B	5.000 EA	_____	_____	_____	_____
0250	303	303SD20-0034 TEMP. SILT FENCE TYPE A	2,184.000 LF	_____	_____	_____	_____
0260	ATTD	303SX20-0007 EMBANKMENT ROCKFILL	750.000 CY	_____	_____	_____	_____
0270	305	305SD20-0012 AGGR.BASE MAT.TY. I NO.21A OR 21B	273.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	315	315SD20-0008 ASPHALT CONCRETE TY. SM- 9.5D CONST	14.000 TON	_____	_____	_____	_____
0290	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	67.000 TON	_____	_____	_____	_____
0300	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH SAW CUT	1,577.000 LF	_____	_____	_____	_____
0310	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	9.000 SY	_____	_____	_____	_____
0320	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0330	ATTD	401SX20-0004 BRIDGE SUBSTRUCTURE CONCRETE CLASS A3 UNREINFORCED	6.000 CY	_____	_____	_____	_____
0340	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	17.000 CY	_____	_____	_____	_____
0350	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	1,026.000 LB	_____	_____	_____	_____
0360	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	7.000 TON	_____	_____	_____	_____
0370	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	11.000 TON	_____	_____	_____	_____
0380	414	414SD20-0057 DRY RIPRAP CL.II 38"	16.000 TON	_____	_____	_____	_____
0390	501	501SD20-0003 UNDERDRAIN UD-3	2,066.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	501	501SD20-0004 UNDERDRAIN UD-4	490.000 LF	_____	_____	_____	_____
0410	501	501SD20-0009 OUTLET PIPE 6" DIA. OUTLET PIPE	27.000 LF	_____	_____	_____	_____
0420	502	502SD20-0004 PAVED DITCH PG-5	13.000 SY	_____	_____	_____	_____
0430	502	502SD20-0011 CURB, STD. CG-2	200.000 LF	_____	_____	_____	_____
0440	502	502SD20-0012 CURB, RADIAL CG-2	100.000 LF	_____	_____	_____	_____
0450	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	60.000 LF	_____	_____	_____	_____
0460	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	1,050.000 LF	_____	_____	_____	_____
0470	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	500.000 LF	_____	_____	_____	_____
0480	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	0.521 CY	_____	_____	_____	_____
0490	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	33.000 SY	_____	_____	_____	_____
0500	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	2,900.000 SY	_____	_____	_____	_____
0510	504	504SD20-0014 HANDRAIL HR-1 TYPE II	499.000 LF	_____	_____	_____	_____
0520	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	347.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	ATTD	510SX20-0002 REMOVE COMB. CURB AND GUTTER	60.000 LF	_____	_____	_____	_____
0540	510	510SX20-0026 REMOVE EXIST. DROP INLET .	2.000 EA	_____	_____	_____	_____
0550	510	510SX20-0033 ADJUST EXIST. DROP INLET MODIFY EXISTING DI REPLACE TOP	1.000 EA	_____	_____	_____	_____
0560	510	510SX20-0039 REMOVE EXIST. 15" PIPE	5.000 LF	_____	_____	_____	_____
0570	510	510SX20-0042 RELOCATE REMOVE AND RELOCATE EXISTING SIGN PANEL.	10.000 EA	_____	_____	_____	_____
0580	511	511SD20-0001 ALLAYING DUST	60.000 HR	_____	_____	_____	_____
0590	512	512SD20-0001 PILOT VEHICLE	80.000 HR	_____	_____	_____	_____
0600	512	512SD20-0014 TEMPORARY SIGN TEMPORARY CONSTRUCTION SIGN	300.000 SF	_____	_____	_____	_____
0610	512	512SD20-0022 GROUP 2 LONGITUDINAL CHANNELIZING DEVICE	50.000 LF	_____	_____	_____	_____
0620	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,200.000 HR	_____	_____	_____	_____
0630	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	14,000.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,500.000 HR	_____	_____	_____	_____
0650	512	512SD20-0027 FLAGGER SERVICE	5,500.000 HR	_____	_____	_____	_____
0660	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	1,500.000 LF	_____	_____	_____	_____
0670	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	60.000 DAY	_____	_____	_____	_____
0680	ATTD	512SX20-0040 POLICE PATROL UNIFORMED FLAGGING	40.000 HR	_____	_____	_____	_____
0690	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0700	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0710	602	602SX20-0005 TOPSOIL 3" CLASS B TOPSOIL	2.390 ACRE	_____	_____	_____	_____
0720	603	603SD20-0002 TEMPORARY SEED	239.000 LB	_____	_____	_____	_____
0730	603	603SD20-0003 REGULAR SEED	956.000 LB	_____	_____	_____	_____
0740	603	603SD20-0004 OVERSEEDING	765.000 LB	_____	_____	_____	_____
0750	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	11,616.000 SY	_____	_____	_____	_____
0760	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	14,411.000 SY	_____	_____	_____	_____

Schedule of Items

Page: 8

Proposal ID: C0000115132M01

Oversight/State Project No.: 0011-082-892,M501, B627

Order No.: N91

Federal Project No.: STP-5115(325)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	603	603SD20-0014 FERTILIZER NITROGEN - N	239.000 LB	_____	_____	_____	_____
0780	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	167.000 LB	_____	_____	_____	_____
0790	603	603SD20-0016 FERTILIZER POTASSIUM - K	167.000 LB	_____	_____	_____	_____
0800	603	603SD20-0017 LIME	13.150 TON	_____	_____	_____	_____
0810	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	6,843.000 SY	_____	_____	_____	_____
0820	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	10.000 EA	_____	_____	_____	_____
0830	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	1,550.000 LF	_____	_____	_____	_____
0840	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	400.000 LF	_____	_____	_____	_____

Section: 0001

Total: _____

Total Bid: _____