

Schedule of Items

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0027 15" STORM SEWER PIPE	24.000 LF	_____	_____	_____	_____
0020	302	302SD20-0032 18" STORM SEWER PIPE	266.000 LF	_____	_____	_____	_____
0030	302	302SD20-0237 DROP INLET DI-1	2.000 EA	_____	_____	_____	_____
0040	302	302SD20-0242 DROP INLET DI-2B,L=6'	2.000 EA	_____	_____	_____	_____
0050	302	302SD20-0243 DROP INLET DI-2B,L=8'	1.000 EA	_____	_____	_____	_____
0060	302	302SD20-0244 DROP INLET DI-2B,L=10'	1.000 EA	_____	_____	_____	_____
0070	302	302SD20-0260 DROP INLET DI-2C,L=8'	1.000 EA	_____	_____	_____	_____
0080	303	303SD20-0001 REGULAR EXCAVATION	630.000 CY	_____	_____	_____	_____
0090	303	303SD20-0029 SILTATION CONTROL EXCAVATION	227.000 CY	_____	_____	_____	_____
0100	303	303SD20-0030 INLET PROTECTION TYPE A	4.000 EA	_____	_____	_____	_____
0110	303	303SD20-0031 INLET PROTECTION TYPE B	10.000 EA	_____	_____	_____	_____
0120	303	303SD20-0034 TEMP. SILT FENCE TYPE A	921.000 LF	_____	_____	_____	_____
0130	308	308SD20-0007 AGGR. MATL. NO. 21B	481.000 TON	_____	_____	_____	_____
0140	315	315SD20-0003 ASPHALT CONCRETE TY. SM- 12.5E CONST	435.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	350.000 TON	_____	_____	_____	_____
0160	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	840.000 LF	_____	_____	_____	_____
0170	501	501SD20-0004 UNDERDRAIN UD-4	350.000 LF	_____	_____	_____	_____
0180	501	501SD20-0009 OUTLET PIPE	204.000 LF	_____	_____	_____	_____
0190	502	502SD20-0011 CURB, STD. CG-2	50.000 LF	_____	_____	_____	_____
0200	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	240.000 LF	_____	_____	_____	_____
0210	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	335.000 LF	_____	_____	_____	_____
0220	502	502SD20-0029 ENTRANCE GUTTER CG-9D	115.000 SY	_____	_____	_____	_____
0230	502	502SD20-0056 MEDIAN STRIP MS-1A	125.000 SY	_____	_____	_____	_____
0240	ATTD	502SX20-0010 SAW CUT H.C.C. ITEMS FULL DEPTH	21.000 LF	_____	_____	_____	_____
0250	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	3.000 SY	_____	_____	_____	_____
0260	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	140.000 SY	_____	_____	_____	_____
0270	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,000.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	509	509SD20-0001 FLOWABLE BACKFILL	6.700 CY	_____	_____	_____	_____
0290	ATTD	510SX20-0009 CONNECT TO EXIST. A/C PIPE	2.000 EA	_____	_____	_____	_____
0300	ATTD	510SX20-0010 REMOVE EXIST. A/C PIPE	120.000 LF	_____	_____	_____	_____
0310	510	510SX20-0031 MODIFY EXIST. MODIFY EXISTING DROP INLET	1.000 EA	_____	_____	_____	_____
0320	510	510SX20-0039 REMOVE EXIST. REMOVE EXISTING 15" CONC. PIPE	10.000 LF	_____	_____	_____	_____
0330	510	510SX20-0040 REMOVE EXIST. REMOVE EXISTING DROP INLET	3.000 EA	_____	_____	_____	_____
0340	512	512SD20-0012 TYPE 3 BARRICADE 4'	4.000 EA	_____	_____	_____	_____
0350	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0360	512	512SD20-0014 TEMPORARY SIGN	700.000 SF	_____	_____	_____	_____
0370	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	900.000 HR	_____	_____	_____	_____
0380	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	2,520.000 DAY	_____	_____	_____	_____
0390	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	336.000 HR	_____	_____	_____	_____
0400	512	512SD20-0026 ELECTRONIC ARROW BOARD	900.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	512	512SD20-0027 FLAGGER SERVICE	40.000 HR	_____	_____	_____	_____
0420	512	512SD20-0029 WARNING LIGHT TY. B	1,080.000 DAY	_____	_____	_____	_____
0430	ATTD	512SX20-0045 SAFETY UNIFORMED FLAGGER	160.000 HR	_____	_____	_____	_____
0440	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0450	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	2,700.000 SY	_____	_____	_____	_____
0460	516	516SX20-0008 DEMO. OF BLDG. D1 - BRICK BUILDING	LUMP SUM	LUMP SUM	_____	_____	_____
0470	516	516SX20-0008 DEMO. OF BLDG. D2 - FRAME STORAGE BUILDING	LUMP SUM	LUMP SUM	_____	_____	_____
0480	516	516SX20-0008 DEMO. OF BLDG. D3 - SIGN	LUMP SUM	LUMP SUM	_____	_____	_____
0490	516	516SX20-0008 DEMO. OF BLDG. D900 - CONCRETE SIDEWALK	LUMP SUM	LUMP SUM	_____	_____	_____
0500	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0510	520	520SD20-0003 1" WATER SERVICE LINE	165.000 LF	_____	_____	_____	_____
0520	520	520SD20-0167 5/8" WATER METER BOX & YOKE	1.000 EA	_____	_____	_____	_____
0530	520	520SD20-0183 6" SANITARY SERVICE LATERAL CONNECTION	25.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 6

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	520	520SD20-0185 8" SANITARY SEWER PIPE	74.000 LF	_____	_____	_____	_____
0550	520	520SD20-0272 SANITARY SEWER MANHOLE	9.000 LF	_____	_____	_____	_____
0560	520	520SD20-0274 MANHOLE FRAME & COVER F & C-1	3.000 EA	_____	_____	_____	_____
0570	520	520SD20-0275 RECONSTRUCT EXISTING SANITARY MANHOLE	7.000 LF	_____	_____	_____	_____
0580	520	520SX20-0006 6" SEWER CLEANOUT	1.000 EA	_____	_____	_____	_____
0590	ATTD	522SP20-0005 CAT II NF ACM	450.000 SF	_____	_____	_____	_____
0600	602	602SD20-0004 TOPSOIL CLASS B	214.000 CY	_____	_____	_____	_____
0610	603	603SD20-0002 TEMPORARY SEED	100.000 LB	_____	_____	_____	_____
0620	603	603SD20-0003 REGULAR SEED	80.000 LB	_____	_____	_____	_____
0630	603	603SD20-0004 OVERSEEDING	64.000 LB	_____	_____	_____	_____
0640	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	3,207.000 SY	_____	_____	_____	_____
0650	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	4,840.000 SY	_____	_____	_____	_____
0660	603	603SD20-0014 FERTILIZER NITROGEN - N	62.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119431C01B Oversight/State Project No.: 0011-139-261, C501

Order No.: N52

Federal Project No.: STP-5139(134)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	47.000 LB	_____	_____	_____	_____
0680	603	603SD20-0016 FERTILIZER POTASSIUM - K	47.000 LB	_____	_____	_____	_____
0690	603	603SD20-0017 LIME	3.860 TON	_____	_____	_____	_____
0700	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
0710	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	21.000 LF	_____	_____	_____	_____
0720	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	2.000 EA	_____	_____	_____	_____
0730	701	701SD20-0001 SIGN PANEL	12.000 SF	_____	_____	_____	_____
0740	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	2,550.000 LF	_____	_____	_____	_____
0750	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	175.000 LF	_____	_____	_____	_____
0760	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	6.000 EA	_____	_____	_____	_____
0770	704	704SD20-0051 DBL TURN ARR. THRU/LT OR RT TY B, CL II	5.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____