

Schedule of Items

Proposal ID: C0000115716M01      Oversight/State Project No.: 0629-085-851, M501  
 Order No.: A22      Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION CONSTRUCTION RECORD DOCUMENTS	LUMP SUM	LUMP SUM			
0020	302	302SD20-0013 ENDWALL EW-12	1.000 EA				
0030	302	302SD20-0023 15" PIPE	94.000 LF				
0040	302	302SD20-0037 24" PIPE	139.000 LF				
0050	302	302SD20-0039 24" CONC. PIPE	24.000 LF				
0060	302	302SD20-0135 30" X 19" ELLIPTICAL CONC. PIPE	46.000 LF				
0070	302	302SD20-0198 15" END SECTION ES-1 OR 2	2.000 EA				
0080	302	302SD20-0204 24" END SECTION ES-1 OR 2	1.000 EA				
0090	302	302SD20-0447 DROP INLET DI-7	1.000 EA				
0100	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	6.000 LF				
0110	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM			
0120	303	303SD20-0007 BORROW EXCAVATION MIN CBR 5	600.000 CY				
0130	303	303SD20-0022 CHECK DAM ROCK TY. I	26.000 EA				

Schedule of Items

Proposal ID: C0000115716M01      Oversight/State Project No.: 0629-085-851, M501  
 Order No.: A22      Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	303	303SD20-0023 CHECK DAM ROCK TY. II	10.000 EA	_____	_____	_____	_____
0150	303	303SD20-0029 SILTATION CONTROL EXCAVATION	142.000 CY	_____	_____	_____	_____
0160	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0170	303	303SD20-0031 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0180	ATTD	303SX20-0008 GEOTEXTILE SUBGRADE SEPARATION	5,022.000 SY	_____	_____	_____	_____
0190	306	306SD20-0001 LIME	3.800 TON	_____	_____	_____	_____
0200	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	1,689.000 TON	_____	_____	_____	_____
0210	ATTD	309SP20-0001 SELECT MATERIAL TYPE OGB	1,689.000 TON	_____	_____	_____	_____
0220	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	605.000 TON	_____	_____	_____	_____
0230	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	25.000 TON	_____	_____	_____	_____
0240	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	200.000 LF	_____	_____	_____	_____
0250	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	73.000 TON	_____	_____	_____	_____
0260	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	25.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115716M01 Oversight/State Project No.: 0629-085-851, M501

Order No.: A22

Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	ATTD	419SX20-0009 BRG. LIGHTING SYSTEM REMOVE EXIST. PARKING LOT LIGHTING SYS.	LUMP SUM	LUMP SUM			
0280	501	501SD20-0007 CROSSDRAIN CD-2	65.000 LF				
0290	501	501SD20-0009 OUTLET PIPE	10.000 LF				
0300	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	10.570 CY				
0310	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	7.000 SY				
0320	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	90.000 SY				
0330	ATTD	504SX20-0007 CONCRETE CONC PARKING LOT WHEEL STOP	83.000 EA				
0340	507	507SD20-0005 FENCE FE-CL	275.000 LF				
0350	507	507SD20-0007 LINE BRACE UNIT FE-CL	2.000 EA				
0360	507	507SD20-0009 CORNER BRACE UNIT FE-CL	2.000 EA				
0370	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,395.000 SY				
0380	510	510SX20-0039 REMOVE EXIST. STORM PIPE	49.000 LF				
0390	ATTD	510SX20-0040 REMOVE EXIST. CONTROL CENTER	1.000 EA				

Schedule of Items

Proposal ID: C0000115716M01      Oversight/State Project No.: 0629-085-851, M501  
 Order No.: A22      Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	ATTD	510SX20-0040 REMOVE EXIST. JUNCTION BOX	2.000 EA	_____	_____	_____	_____
0410	511	511SD20-0001 ALLAYING DUST	60.000 HR	_____	_____	_____	_____
0420	512	512SD20-0013 TYPE 3 BARRICADE 8'	7.000 EA	_____	_____	_____	_____
0430	512	512SD20-0014 TEMPORARY SIGN	250.000 SF	_____	_____	_____	_____
0440	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	250.000 HR	_____	_____	_____	_____
0450	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	1,800.000 DAY	_____	_____	_____	_____
0460	512	512SD20-0026 ELECTRONIC ARROW BOARD	250.000 HR	_____	_____	_____	_____
0470	512	512SD20-0027 FLAGGER SERVICE	960.000 HR	_____	_____	_____	_____
0480	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	40.000 DAY	_____	_____	_____	_____
0490	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0500	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	480.000 SY	_____	_____	_____	_____
0510	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0520	ATTD	523SP20-0002 STORM WATER MANAGEMENT LOW PERMEABILITY LINER	417.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115716M01 Oversight/State Project No.: 0629-085-851, M501

Order No.: A22

Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	602	602SD20-0004 TOPSOIL CLASS B 12" SWM	139.000 CY	_____	_____	_____	_____
0540	602	602SD20-0004 TOPSOIL CLASS B 3"	278.000 CY	_____	_____	_____	_____
0550	603	603SD20-0002 TEMPORARY SEED	69.000 LB	_____	_____	_____	_____
0560	603	603SD20-0003 REGULAR SEED	276.000 LB	_____	_____	_____	_____
0570	603	603SD20-0004 OVERSEEDING	221.000 LB	_____	_____	_____	_____
0580	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	4,175.000 SY	_____	_____	_____	_____
0590	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,340.000 SY	_____	_____	_____	_____
0600	603	603SD20-0014 FERTILIZER NITROGEN - N	69.000 LB	_____	_____	_____	_____
0610	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	48.000 LB	_____	_____	_____	_____
0620	603	603SD20-0016 FERTILIZER POTASSIUM - K	48.000 LB	_____	_____	_____	_____
0630	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	649.000 SY	_____	_____	_____	_____
0640	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	214.000 SY	_____	_____	_____	_____
0650	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL RELOCATE SIGN POST	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115716M01      Oversight/State Project No.: 0629-085-851, M501  
 Order No.: A22      Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	270.000 LF	_____	_____	_____	_____
0670	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	20.000 EA	_____	_____	_____	_____
0680	700	700SD20-0144 8 CONDUCTOR CABLE	4,400.000 LF	_____	_____	_____	_____
0690	700	700SD20-0148 8 CONDUCTOR CABLE EGC	1,900.000 LF	_____	_____	_____	_____
0700	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	13.000 EA	_____	_____	_____	_____
0710	700	700SD20-0156 LIGHTING POLE LP-2 TYPE D	13.000 EA	_____	_____	_____	_____
0720	700	700SD20-0170 ELECTRICAL SERVICE SE-8, TY. A	1.000 EA	_____	_____	_____	_____
0730	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
0740	700	700SD20-0177 JUNCTION BOX JB-S1	3.000 EA	_____	_____	_____	_____
0750	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
0760	700	700SD20-0191 BORED CONDUIT 2"	325.000 LF	_____	_____	_____	_____
0770	700	700SD20-0194 CONDUIT PVC 2"	1,810.000 LF	_____	_____	_____	_____
0780	700	700SD20-0197 TRENCH EXCAVATION ECI-1	1,450.000 LF	_____	_____	_____	_____
0790	701	701SD20-0001 SIGN PANEL	89.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115716M01      Oversight/State Project No.: 0629-085-851, M501  
 Order No.: A22      Federal Project No.: STP-085-8(090)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	800.000 LF	_____	_____	_____	_____
0810	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	3,432.000 LF	_____	_____	_____	_____
0820	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	110.000 LF	_____	_____	_____	_____
0830	704	704SD20-0093 MRKG INT'L ACCESSIBILITY SYMB TY B CL II HANDICAP PARKING SYMBOL	5.000 EA	_____	_____	_____	_____
0840	705	705SD20-0003 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
0850	ATTD	705SX20-0001 LUMINAIRE LUMINAIRE LED 160 W (4000K)	13.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	