

Schedule of Items

Proposal ID: C0000125595N01 Oversight/State Project No.: 9999-962-887, N501
 Order No.: A08 Federal Project No.: HSIP-962-2(154)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0002 CLEARING AND GRUBBING	3.100 ACRE	_____	_____	_____	_____
0020	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,920.000 HR	_____	_____	_____	_____
0030	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	297.000 DAY	_____	_____	_____	_____
0040	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,920.000 HR	_____	_____	_____	_____
0050	512	512SD20-0027 FLAGGER SERVICE	4,762.000 HR	_____	_____	_____	_____
0060	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	384.000 DAY	_____	_____	_____	_____
0070	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0080	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	93.000 EA	_____	_____	_____	_____
0090	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	22.000 EA	_____	_____	_____	_____
0100	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	6.000 EA	_____	_____	_____	_____
0110	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	5,999.000 LF	_____	_____	_____	_____
0120	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	108.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000125595N01

Oversight/State Project No.: 9999-962-887, N501

Order No.: A08

Federal Project No.: HSIP-962-2(154)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0130	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	261.000 LF	_____	_____	_____	_____
0140	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	28.000 LF	_____	_____	_____	_____
0150	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	694.000 EA	_____	_____	_____	_____
0160	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	10.000 EA	_____	_____	_____	_____
0170	701	701SD20-0001 SIGN PANEL	8,658.000 SF	_____	_____	_____	_____
0180	702	702SD20-0012 FLEXIBLE POST DELINEATOR, GROUND MOUNT	59.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	