

Schedule of Items

Proposal ID: C0000117024B05 Oversight/State Project No.: 0778-007-024, B605, M501
 Order No.: A16 Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0013 ENDWALL EW-12 (6" PIPE 2:1 SLOPE)	2.000 EA	_____	_____	_____	_____
0020	302	302SD20-0013 ENDWALL EW-12 (6" PIPE 4:1 SLOPE)	1.000 EA	_____	_____	_____	_____
0030	302	302SD20-0037 24" PIPE	64.000 LF	_____	_____	_____	_____
0040	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM		_____	_____
0050	303	303SD20-0007 BORROW EXCAVATION MIN. CBR-5	115.000 CY	_____	_____	_____	_____
0060	303	303SD20-0023 CHECK DAM ROCK TY. II	3.000 EA	_____	_____	_____	_____
0070	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0080	303	303SD20-0029 SILTATION CONTROL EXCAVATION	224.000 CY	_____	_____	_____	_____
0090	303	303SD20-0033 TEMP. SILT FENCE TYPE B	1,270.000 LF	_____	_____	_____	_____
0100	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	322.000 SY	_____	_____	_____	_____
0110	306	306SD20-0001 LIME	6.260 TON	_____	_____	_____	_____
0120	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	90.000 TON	_____	_____	_____	_____
0130	ATTD	314SP20-0014 MODIFIED DOUBLE SEAL	616.300 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117024B05 Oversight/State Project No.: 0778-007-024, B605, M501
 Order No.: A16 Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	315	315SX20-0007 ASPHALT CONCRETE SM-9.5AL	38.000 TON	_____	_____	_____	_____
0150	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	38.000 LF	_____	_____	_____	_____
0160	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	304.000 CY	_____	_____	_____	_____
0170	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	323.000 TON	_____	_____	_____	_____
0180	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	16.000 SY	_____	_____	_____	_____
0190	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	166.000 LF	_____	_____	_____	_____
0200	401	401SD20-0007 COFFERDAM	3.000 EA	_____	_____	_____	_____
0210	ATTD	401SX20-0002 TEMP. CAUSEWAY TEMP. CAUSEWAY	LUMP SUM	LUMP SUM	_____	_____	_____
0220	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	45.600 CY	_____	_____	_____	_____
0230	404	404SD20-0012 CONCRETE CLASS A4, SUBSTRUCT. CONST.	128.000 CY	_____	_____	_____	_____
0240	ATTD	404SX20-0001 CONCRETE CLASS A3 (UNREINFORCED)	9.800 CY	_____	_____	_____	_____
0250	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	11,220.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117024B05

Oversight/State Project No.: 0778-007-024, B605, M501

Order No.: A16

Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD	407SX20-0003 STRUCT. STEEL PREFABRICATED STEEL TRUSS SUPERSTRUCTURE	LUMP SUM	LUMP SUM			
0270	ATTD	412SX20-0013 BR.SUPERSTR. WID./REPAIR TEMPORARY PIER SUPPORTS	LUMP SUM	LUMP SUM			
0280	413	413SX20-0003 ENV.& WORKER PROTECT. STRUCTURE 6149	LUMP SUM	LUMP SUM			
0290	413	413SX20-0004 MATERIAL DISPOSAL STRUCTURE 6149	LUMP SUM	LUMP SUM			
0300	ATTD	413SX20-0005 REM. PORT.OF EX.STR. NO. 6149	LUMP SUM	LUMP SUM			
0310	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	10.000 TON				
0320	418	418SD20-0001 LUMBER TREATED, SPR. STRUCT. CONST.	12.400 MFBM				
0330	429	429SD20-0004 WATERPROOFING MEMBRANE TYPE III	315.000 SY				
0340	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE VIRGINIA STR. 6149	2.000 DAY				
0350	501	501SD20-0007 CROSSDRAIN CD-2	36.000 LF				
0360	501	501SD20-0009 OUTLET PIPE	18.000 LF				
0370	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	1.398 CY				

Schedule of Items

Proposal ID: C0000117024B05 Oversight/State Project No.: 0778-007-024, B605, M501
 Order No.: A16 Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0380	505	505SD20-0011 GUARDRAIL GR-MGS1	87.500 LF	_____	_____	_____	_____
0390	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	150.000 LF	_____	_____	_____	_____
0400	505	505SD20-0016 RADIAL GUARDRAIL GR- MGS1, 9' POST	25.000 LF	_____	_____	_____	_____
0410	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	3.000 EA	_____	_____	_____	_____
0420	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0430	505	505SD20-0027 GUARDRAIL TERMINAL GR-6 NCHRP 350	12.500 LF	_____	_____	_____	_____
0440	505	505SD20-0030 GUARDRAIL GR-2	12.500 LF	_____	_____	_____	_____
0450	505	505SD20-0039 GUARDRAIL TER.SITE PREPARATION	3.000 EA	_____	_____	_____	_____
0460	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	435.000 LF	_____	_____	_____	_____
0470	505	505SD20-0074 GUARDRAIL, THRIE BEAM	350.000 LF	_____	_____	_____	_____
0480	ATTD	505SX20-0004 GUARDRAIL TOP MOUNTED POST	12.000 EA	_____	_____	_____	_____
0490	ATTD	505SX20-0058 GUARDRAIL W-BEAM TO THRIE BEAM TRANSITION SECTION	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117024B05

Oversight/State Project No.: 0778-007-024, B605, M501

Order No.: A16

Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0500	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	85.000 LF	_____	_____	_____	_____
0510	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	322.000 SY	_____	_____	_____	_____
0520	509	509SD20-0001 FLOWABLE BACKFILL	5.000 CY	_____	_____	_____	_____
0530	ATTD	510SX20-0040 REMOVE EXIST. REMOVE AND SALVAGE EXISTING DETOUR SIGN	12.000 EA	_____	_____	_____	_____
0540	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	48.000 LF	_____	_____	_____	_____
0550	512	512SD20-0012 TYPE 3 BARRICADE 4'	5.000 EA	_____	_____	_____	_____
0560	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
0570	512	512SD20-0014 TEMPORARY SIGN	360.000 SF	_____	_____	_____	_____
0580	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0590	514	514SD20-0001 FIELD OFFICE TY.I	12.000 MO	_____	_____	_____	_____
0600	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	21.500 SY	_____	_____	_____	_____
0610	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0620	521	521SD20-0001 MAILBOX POST, SINGLE	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117024B05

Oversight/State Project No.: 0778-007-024, B605, M501

Order No.: A16

Federal Project No.: BROS-007-8(187)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0630	602	602SD20-0004 TOPSOIL CLASS B	536.000 CY	_____	_____	_____	_____
0640	603	603SD20-0002 TEMPORARY SEED	80.000 LB	_____	_____	_____	_____
0650	603	603SD20-0003 REGULAR SEED	532.000 LB	_____	_____	_____	_____
0660	603	603SD20-0004 OVERSEEDING	426.000 LB	_____	_____	_____	_____
0670	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	5,990.000 SY	_____	_____	_____	_____
0680	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,872.000 SY	_____	_____	_____	_____
0690	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	2,057.000 SY	_____	_____	_____	_____
0700	603	603SD20-0014 FERTILIZER NITROGEN - N	122.000 LB	_____	_____	_____	_____
0710	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	83.000 LB	_____	_____	_____	_____
0720	603	603SD20-0016 FERTILIZER POTASSIUM - K	83.000 LB	_____	_____	_____	_____
0730	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	382.000 SY	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	