

Schedule of Items

Proposal ID: C0000101435C01 Oversight/State Project No.: 0661-034-801, C501
 Order No.: A06 Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 PERMANENT SWM FACILITY AS-BUILT DOCUMENTATION SWM FACILITY AS-BUILT	LUMP SUM	LUMP SUM			
0020	302	302SD20-0013 ENDWALL EW-12	10.000 EA				
0030	302	302SD20-0023 15" PIPE	194.000 LF				
0040	302	302SD20-0028 18" PIPE	164.000 LF				
0050	302	302SD20-0039 24" CONC. PIPE	50.000 LF				
0060	302	302SD20-0133 23" X 14" ELLIPTICAL CONC. PIPE	130.000 LF				
0070	302	302SD20-0134 30" X 19" ELLIPTICAL PIPE	174.000 LF				
0080	302	302SD20-0135 30" X 19" ELLIPTICAL CONC. PIPE	94.000 LF				
0090	302	302SD20-0198 15" END SECTION ES-1 OR 2	2.000 EA				
0100	302	302SD20-0200 18" END SECTION ES-1 OR 2	2.000 EA				
0110	302	302SD20-0221 23" X 14" END SECTION ES-1A	4.000 EA				
0120	302	302SD20-0222 30" X 19" END SECTION ES-1A	2.000 EA				
0130	302	302SD20-0670 TEMP. DIVE. CHANNEL LINING CL. A	1,333.000 SY				

Schedule of Items

Proposal ID: C0000101435C01 Oversight/State Project No.: 0661-034-801, C501

Order No.: A06

Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	302SD20-0672 TEMP. DIVE. CHANNEL EXCAVATION	525.000 CY	_____	_____	_____	_____
0150	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	7.000 LF	_____	_____	_____	_____
0160	303	303SD20-0001 REGULAR EXCAVATION	11,779.000 CY	_____	_____	_____	_____
0170	303	303SD20-0013 GEOTEXTILE EMBANKMENT STAB. STABILIZED CONSTRUCTION ENTRANCE (STD EC-11)	200.000 SY	_____	_____	_____	_____
0180	303	303SD20-0021 TEMPORARY DIVERSION DIKE STD EC-9	873.000 LF	_____	_____	_____	_____
0190	303	303SD20-0023 CHECK DAM ROCK TY. II	31.000 EA	_____	_____	_____	_____
0200	303	303SD20-0029 SILTATION CONTROL EXCAVATION	1,465.000 CY	_____	_____	_____	_____
0210	303	303SD20-0034 TEMP. SILT FENCE TYPE A	8,376.000 LF	_____	_____	_____	_____
0220	303	303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION	740.000 CY	_____	_____	_____	_____
0230	305	305SD20-0001 BORROW EXCAVATION	4,649.000 CY	_____	_____	_____	_____
0240	305	305SD20-0007 SELECT MATL. TY. II MIN. CBR-30	1,883.000 CY	_____	_____	_____	_____
0250	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	3,050.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101435C01 Oversight/State Project No.: 0661-034-801, C501
 Order No.: A06 Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	3,944.000 TON	_____	_____	_____	_____
0270	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	165.000 TON	_____	_____	_____	_____
0280	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	978.000 TON	_____	_____	_____	_____
0290	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	1,388.000 TON	_____	_____	_____	_____
0300	315	315SD20-0027 ASPH. CONC. TY. SM-9.5A MAINT	889.000 TON	_____	_____	_____	_____
0310	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	1,145.000 LF	_____	_____	_____	_____
0320	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	60.000 TON	_____	_____	_____	_____
0330	501	501SD20-0004 UNDERDRAIN UD-4	2,669.000 LF	_____	_____	_____	_____
0340	501	501SD20-0009 OUTLET PIPE	121.000 LF	_____	_____	_____	_____
0350	503	503SD20-0002 R/W MONUMENT RM-2	38.000 EA	_____	_____	_____	_____
0360	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	25.000 CY	_____	_____	_____	_____
0370	505	505SD20-0066 CABLE BARRICADE CR-1	1.000 EA	_____	_____	_____	_____
0380	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	110.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101435C01 Oversight/State Project No.: 0661-034-801, C501
 Order No.: A06 Federal Project No.: NONE

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	508	508SD20-0001 OBSCURING ROADWAY	40.000 UNIT	_____	_____	_____	_____
0400	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	2,854.000 SY	_____	_____	_____	_____
0410	509	509SD20-0001 FLOWABLE BACKFILL	2.000 CY	_____	_____	_____	_____
0420	510	510SX20-0039 REMOVE EXIST. PIPE	60.000 LF	_____	_____	_____	_____
0430	512	512SD20-0012 TYPE 3 BARRICADE 4'	2.000 EA	_____	_____	_____	_____
0440	512	512SD20-0013 TYPE 3 BARRICADE 8'	6.000 EA	_____	_____	_____	_____
0450	512	512SD20-0014 TEMPORARY SIGN	959.000 SF	_____	_____	_____	_____
0460	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	280.000 HR	_____	_____	_____	_____
0470	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	591.000 DAY	_____	_____	_____	_____
0480	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,680.000 HR	_____	_____	_____	_____
0490	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,120.000 HR	_____	_____	_____	_____
0500	512	512SD20-0027 FLAGGER SERVICE	1,120.000 HR	_____	_____	_____	_____
0510	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,350.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101435C01

Oversight/State Project No.: 0661-034-801, C501

Order No.: A06

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	512	512SD20-0066 TRAFFIC BARRIER SERVICE CONC.	20.000 LF	_____	_____	_____	_____
0530	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0540	514	514SD20-0003 FIELD OFFICE TY.III	16.000 MO	_____	_____	_____	_____
0550	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	1,383.000 SY	_____	_____	_____	_____
0560	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0570	602	602SX20-0005 TOPSOIL CLASS B 3"	4.900 ACRE	_____	_____	_____	_____
0580	603	603SD20-0002 TEMPORARY SEED	490.000 LB	_____	_____	_____	_____
0590	603	603SD20-0003 REGULAR SEED	1,960.000 LB	_____	_____	_____	_____
0600	603	603SD20-0004 OVERSEEDING	1,568.000 LB	_____	_____	_____	_____
0610	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	29,645.000 SY	_____	_____	_____	_____
0620	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	23,716.000 SY	_____	_____	_____	_____
0630	603	603SD20-0014 FERTILIZER NITROGEN - N	490.000 LB	_____	_____	_____	_____
0640	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	343.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101435C01

Oversight/State Project No.: 0661-034-801, C501

Order No.: A06

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0650	603	603SD20-0016 FERTILIZER POTASSIUM - K	343.000 LB	_____	_____	_____	_____
0660	603	603SD20-0017 LIME	27.000 TON	_____	_____	_____	_____
0670	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	5,728.000 SY	_____	_____	_____	_____
0680	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	43.000 SY	_____	_____	_____	_____
0690	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	7.000 EA	_____	_____	_____	_____
0700	700	700SD20-0010 REMOVE EXIST OVERHEAD SIGNAL SIGN PANEL	3.000 EA	_____	_____	_____	_____
0710	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	2.000 EA	_____	_____	_____	_____
0720	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	81.000 LF	_____	_____	_____	_____
0730	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	11.000 LF	_____	_____	_____	_____
0740	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	12.000 EA	_____	_____	_____	_____
0750	701	701SD20-0001 SIGN PANEL	74.000 SF	_____	_____	_____	_____
0760	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000101435C01

Oversight/State Project No.: 0661-034-801, C501

Order No.: A06

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	1.000 EA	_____	_____	_____	_____
0780	703	703SD20-0046 REMOVE EXISTING SIGNAL HEAD	4.000 EA	_____	_____	_____	_____
0790	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	11,400.000 LF	_____	_____	_____	_____
0800	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	370.000 LF	_____	_____	_____	_____
0810	ATTD	801SX20-0001 COMMUNICATION EQUIP. NS MODIFY EXISTING CONTROLLER CABINET	1.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	