

Schedule of Items

Proposal ID: C0000123889C01B Oversight/State Project No.: 0017-036-652, C501
 Order No.: N71 Federal Project No.: STP-5111(502)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	302	302SD20-0027 15" STORM SEWER PIPE	324.000 LF				
0030	302	302SD20-0032 18" STORM SEWER PIPE	53.000 LF				
0040	302	302SD20-0041 24" STORM SEWER PIPE	12.000 LF				
0050	302	302SD20-0133 23" X 14" ELLIPTICAL CONC. PIPE	573.000 LF				
0060	302	302SD20-0199 15" END SECTION ES-1	4.000 EA				
0070	302	302SD20-0221 23" X 14" END SECTION ES-1A	1.000 EA				
0080	302	302SD20-0329 DROP INLET DI-3C,L=6'	2.000 EA				
0090	302	302SD20-0662 MANHOLE MH-1 OR 2	9.100 LF				
0100	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA				
0110	ATTD	302SX20-0015 SPEC. DESIGN ROCK CHECK DAM TYPE 1 MOD.	1.000 EA				
0120	ATTD	302SX20-0015 SPEC. DESIGN SWM DI-1	1.000 EA				
0130	303	303SD20-0001 REGULAR EXCAVATION	971.000 CY				
0140	303	303SD20-0019 EROSION CONTROL MULCH	2,554.000 SY				

Schedule of Items

Proposal ID: C0000123889C01B Oversight/State Project No.: 0017-036-652, C501
 Order No.: N71 Federal Project No.: STP-5111(502)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0022 CHECK DAM ROCK TY. I	10.000 EA	_____	_____	_____	_____
0160	303	303SD20-0029 SILTATION CONTROL EXCAVATION	56.000 CY	_____	_____	_____	_____
0170	303	303SD20-0030 INLET PROTECTION TYPE A	2.000 EA	_____	_____	_____	_____
0180	303	303SD20-0031 INLET PROTECTION TYPE B	2.000 EA	_____	_____	_____	_____
0190	303	303SD20-0034 TEMP. SILT FENCE TYPE A	355.000 LF	_____	_____	_____	_____
0200	305	305SD20-0001 BORROW EXCAVATION	205.000 CY	_____	_____	_____	_____
0210	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	1,227.000 TON	_____	_____	_____	_____
0220	315	315SD20-0002 ASPHALT CONCRETE TY. SM-12.5D CONST	805.000 TON	_____	_____	_____	_____
0230	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	427.000 TON	_____	_____	_____	_____
0240	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	1,364.000 TON	_____	_____	_____	_____
0250	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	875.000 LF	_____	_____	_____	_____
0260	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	3,073.000 LF	_____	_____	_____	_____
0270	502	502SD20-0011 CURB, STD. CG-2	303.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123889C01B Oversight/State Project No.: 0017-036-652, C501
 Order No.: N71 Federal Project No.: STP-5111(502)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	502	502SD20-0012 CURB, RADIAL CG-2	109.000 LF	_____	_____	_____	_____
0290	502	502SD20-0056 MEDIAN STRIP MS-1A	213.000 SY	_____	_____	_____	_____
0300	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	2,361.000 SY	_____	_____	_____	_____
0310	511	511SD20-0001 ALLAYING DUST	24.000 HR	_____	_____	_____	_____
0320	512	512SD20-0014 TEMPORARY SIGN	701.000 SF	_____	_____	_____	_____
0330	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	6,700.000 HR	_____	_____	_____	_____
0340	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	72,790.000 DAY	_____	_____	_____	_____
0350	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	9,000.000 HR	_____	_____	_____	_____
0360	512	512SD20-0026 ELECTRONIC ARROW BOARD	21,120.000 HR	_____	_____	_____	_____
0370	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0380	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	4,216.000 SY	_____	_____	_____	_____
0390	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0400	602	602SD20-0003 TOPSOIL CLASS B 2"	1.510 ACRE	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123889C01B Oversight/State Project No.: 0017-036-652, C501

Order No.: N71

Federal Project No.: STP-5111(502)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	603	603SD20-0002 TEMPORARY SEED	151.000 LB	_____	_____	_____	_____
0420	603	603SD20-0003 REGULAR SEED	425.000 LB	_____	_____	_____	_____
0430	603	603SD20-0004 OVERSEEDING	340.000 LB	_____	_____	_____	_____
0440	603	603SD20-0007 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	9,136.000 SY	_____	_____	_____	_____
0450	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	7,308.000 SY	_____	_____	_____	_____
0460	603	603SD20-0014 FERTILIZER NITROGEN - N	230.000 LB	_____	_____	_____	_____
0470	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	106.000 LB	_____	_____	_____	_____
0480	603	603SD20-0016 FERTILIZER POTASSIUM - K	106.000 LB	_____	_____	_____	_____
0490	603	603SD20-0017 LIME	8.310 TON	_____	_____	_____	_____
0500	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	9,136.000 SY	_____	_____	_____	_____
0510	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	7,308.000 SY	_____	_____	_____	_____
0520	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	67.780 SY	_____	_____	_____	_____
0530	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123889C01B Oversight/State Project No.: 0017-036-652, C501
 Order No.: N71 Federal Project No.: STP-5111(502)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	1.000 EA	_____	_____	_____	_____
0550	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
0560	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	179.000 LF	_____	_____	_____	_____
0570	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	211.000 LF	_____	_____	_____	_____
0580	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	28.000 EA	_____	_____	_____	_____
0590	701	701SD20-0001 SIGN PANEL	327.000 SF	_____	_____	_____	_____
0600	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	5,195.000 LF	_____	_____	_____	_____
0610	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	54.000 LF	_____	_____	_____	_____
0620	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	33.000 EA	_____	_____	_____	_____
0630	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	5.000 EA	_____	_____	_____	_____
0640	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	37.000 EA	_____	_____	_____	_____

Section: 0001 Total: _____

Total Bid: _____