

Schedule of Items

Proposal ID: C0000107309M01 Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0014 6" PIPE	39.000 LF	_____	_____	_____	_____
0020	302	302SD20-0016 8" PIPE	42.000 LF	_____	_____	_____	_____
0030	302	302SD20-0039 24" CONC. PIPE	49.000 LF	_____	_____	_____	_____
0040	302	302SD20-0205 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0050	303	303SD20-0001 REGULAR EXCAVATION	313.000 CY	_____	_____	_____	_____
0060	303	303SD20-0023 CHECK DAM ROCK TY. II	17.000 EA	_____	_____	_____	_____
0070	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0080	303	303SD20-0029 SILTATION CONTROL EXCAVATION	216.000 CY	_____	_____	_____	_____
0090	303	303SD20-0032 GEOTEXTILE FABRIC	66.000 SY	_____	_____	_____	_____
0100	303	303SD20-0033 TEMP. SILT FENCE TYPE B	819.000 LF	_____	_____	_____	_____
0110	303	303SD20-0034 TEMP. SILT FENCE TYPE A	421.000 LF	_____	_____	_____	_____
0120	ATTD	303SX20-0010 ACCESS ROAD (TEMPORARY CONSTRUCTION ACCESS)	LUMP SUM	LUMP SUM	_____	_____	_____
0130	305	305SD20-0012 AGGR.BASE MAT.TY. I NO.21A OR 21B	307.000 TON	_____	_____	_____	_____
0140	306	306SD20-0001 LIME	2.640 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107309M01 Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	165.000 TON	_____	_____	_____	_____
0160	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	136.000 TON	_____	_____	_____	_____
0170	315	315SD20-0008 ASPHALT CONCRETE TY. SM-9.5D CONST	71.000 TON	_____	_____	_____	_____
0180	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE (FULL DEPTH)	400.000 LF	_____	_____	_____	_____
0190	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0200	ATTD	401SX20-0008 BRIDGE SUBSTRUCTURE (GROUTED ANCHORS)	12.000 EA	_____	_____	_____	_____
0210	ATTD	403SX20-0018 PILE (MICROPILES)	324.000 LF	_____	_____	_____	_____
0220	404	404SD20-0012 CONCRETE CLASS A4, SUBSTRUCT. CONST.	67.000 CY	_____	_____	_____	_____
0230	ATTD	410SX20-0008 BRIDGE SUPERSTRUCTURE (PRECAST MOMENT SLABS)	150.000 LF	_____	_____	_____	_____
0240	ATTD	410SX20-0020 PARAPET SSCP-1	150.000 LF	_____	_____	_____	_____
0250	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	7.000 TON	_____	_____	_____	_____
0260	414	414SD20-0012 DRY RIPRAP CL.I 26"	32.000 TON	_____	_____	_____	_____
0270	414	414SD20-0057 DRY RIPRAP CL.II 38"	141.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107309M01 Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	502	502SD20-0011 CURB, STD. CG-2	73.000 LF	_____	_____	_____	_____
0290	502	502SD20-0012 CURB, RADIAL CG-2	19.000 LF	_____	_____	_____	_____
0300	502	502SD20-0014 CURB, STD. CG-3	27.000 LF	_____	_____	_____	_____
0310	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	2.000 CY	_____	_____	_____	_____
0320	505	505SD20-0011 GUARDRAIL GR-MGS1	25.000 LF	_____	_____	_____	_____
0330	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0340	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	1.000 EA	_____	_____	_____	_____
0350	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	37.000 LF	_____	_____	_____	_____
0360	ATTD	506SX20-0002 WALL (PRECAST MODULAR RETAINING WALL)	213.000 SF	_____	_____	_____	_____
0370	507	507SD20-0001 FENCE FE-W1	191.000 LF	_____	_____	_____	_____
0380	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	6.000 EA	_____	_____	_____	_____
0390	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	300.000 SY	_____	_____	_____	_____
0400	510	510SX20-0016 REMOVE EXIST. FENCE .	209.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107309M01 Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	512	512SD20-0013 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0420	512	512SD20-0014 TEMPORARY SIGN	250.000 SF	_____	_____	_____	_____
0430	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	4,872.000 DAY	_____	_____	_____	_____
0440	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	6,048.000 HR	_____	_____	_____	_____
0450	512	512SD20-0027 FLAGGER SERVICE	1,272.000 HR	_____	_____	_____	_____
0460	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	1,420.000 LF	_____	_____	_____	_____
0470	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0480	514	514SD20-0001 FIELD OFFICE TY.I	14.000 MO	_____	_____	_____	_____
0490	515	515SD20-0003 FLEX. PAVE.TIE-IN PLANING ABOVE 2"-4"	374.000 SY	_____	_____	_____	_____
0500	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN	LUMP SUM	LUMP SUM	_____	_____	_____
0510	602	602SD20-0004 TOPSOIL CLASS B	194.000 CY	_____	_____	_____	_____
0520	603	603SD20-0002 TEMPORARY SEED	106.000 LB	_____	_____	_____	_____
0530	603	603SD20-0003 REGULAR SEED	132.000 LB	_____	_____	_____	_____
0540	603	603SD20-0004 OVERSEEDING	106.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107309M01 Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	2,239.000 SY	_____	_____	_____	_____
0560	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	2,323.000 SY	_____	_____	_____	_____
0570	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	666.000 SY	_____	_____	_____	_____
0580	603	603SD20-0014 FERTILIZER NITROGEN - N	48.000 LB	_____	_____	_____	_____
0590	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	34.000 LB	_____	_____	_____	_____
0600	603	603SD20-0016 FERTILIZER POTASSIUM - K	34.000 LB	_____	_____	_____	_____
0610	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	20.000 SY	_____	_____	_____	_____
0620	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	6.000 EA	_____	_____	_____	_____
0630	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	105.000 LF	_____	_____	_____	_____
0640	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	7.000 EA	_____	_____	_____	_____
0650	701	701SD20-0001 SIGN PANEL	36.000 SF	_____	_____	_____	_____
0660	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	1,290.000 LF	_____	_____	_____	_____
0670	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	22.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000107309M01

Oversight/State Project No.: 0649-080-R77, M501

Order No.: A39

Federal Project No.: NONE

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_