

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	ATTD	302SD20-0001 BEDDING MATL.AGGR.NO. 25 OR 26	567.000 TON				
0030	302	302SD20-0013 ENDWALL EW-12	2.000 EA				
0040	302	302SD20-0025 15" CONC. PIPE	945.000 LF				
0050	302	302SD20-0143 45" X 29" ELLIPTICAL CONC. PIPE	65.000 LF				
0060	302	302SD20-0198 15" END SECTION ES-1 OR 2	2.000 EA				
0070	302	302SD20-0225 45" X 29" END SECTION ES-1A	2.000 EA				
0080	302	302SD20-0241 DROP INLET DI-2B,L=4'	1.000 EA				
0090	302	302SD20-0242 DROP INLET DI-2B,L=6'	1.000 EA				
0100	302	302SD20-0309 DROP INLET DI-3A	1.000 EA				
0110	302	302SD20-0311 DROP INLET DI-3B,L=4'	7.000 EA				
0120	302	302SD20-0312 DROP INLET DI-3B,L=6'	1.000 EA				
0130	302	302SD20-0320 DROP INLET DI-3BB,L=4'	2.000 EA				
0140	302	302SD20-0329 DROP INLET DI-3C,L=6'	3.000 EA				

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0448 DROP INLET DI-7A	1.000 EA	_____	_____	_____	_____
0160	303	302SX20-0013 PIPE 15" TEMP CONC PIPE	32.000 LF	_____	_____	_____	_____
0170	303	302SX20-0022 DRAINAGE 15" INLET CAP	17.000 EA	_____	_____	_____	_____
0180	303	302SX20-0022 DRAINAGE 15" PIPE TEMP. PLUG	3.000 EA	_____	_____	_____	_____
0190	303	302SX20-0022 DRAINAGE 45"X29" TEMP PLUG	1.000 EA	_____	_____	_____	_____
0200	303	303SD20-0001 REGULAR EXCAVATION	1,962.000 CY	_____	_____	_____	_____
0210	303	303SD20-0007 BORROW EXCAVATION	5,919.000 CY	_____	_____	_____	_____
0220	303	303SD20-0023 CHECK DAM ROCK TY. II	7.000 EA	_____	_____	_____	_____
0230	303	303SD20-0024 CHECK DAM SEDIMENT RETENTION ROLL 18"	20.000 EA	_____	_____	_____	_____
0240	303	303SD20-0029 SILTATION CONTROL EXCAVATION	513.100 CY	_____	_____	_____	_____
0250	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0260	303	303SD20-0031 INLET PROTECTION TYPE B	15.000 EA	_____	_____	_____	_____
0270	303	303SD20-0034 TEMP. SILT FENCE TYPE A	2,191.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	305	305SD20-0005 SELECT MATL. TY. I MIN. CBR-30	565.000 TON	_____	_____	_____	_____
0290	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	811.000 SY	_____	_____	_____	_____
0300	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	2,076.000 TON	_____	_____	_____	_____
0310	315	315SD20-0002 ASPHALT CONCRETE TY. SM-12.5D CONST	207.000 TON	_____	_____	_____	_____
0320	315	315SD20-0003 ASPHALT CONCRETE TY. SM-12.5E CONST	434.000 TON	_____	_____	_____	_____
0330	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	511.000 TON	_____	_____	_____	_____
0340	315	315SD20-0006 ASPHALT CONCRETE TY. IM-19.0E CONST	547.000 TON	_____	_____	_____	_____
0350	315	315SD20-0011 ASPHALT CONCRETE TY. BM-25.0D CONST	1,293.000 TON	_____	_____	_____	_____
0360	ATTD	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	1,584.000 LF	_____	_____	_____	_____
0370	316	316SX20-0009 HYDRAULIC CEM. CONC. 10" JOINTED REINFORCED	546.000 SY	_____	_____	_____	_____
0380	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	19.360 TON	_____	_____	_____	_____
0390	414	414SD20-0005 EROSION CTRL. STONE CL. II, EC-1	131.800 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	414	414SD20-0055 DRY RIPRAP CL. A1 20"	20.110 TON	_____	_____	_____	_____
0410	501	501SD20-0002 UNDERDRAIN UD-2	264.000 LF	_____	_____	_____	_____
0420	501	501SD20-0004 UNDERDRAIN UD-4	1,851.000 LF	_____	_____	_____	_____
0430	501	501SD20-0007 CROSSDRAIN CD-2	94.000 LF	_____	_____	_____	_____
0440	501	501SD20-0009 OUTLET PIPE	190.000 LF	_____	_____	_____	_____
0450	502	502SD20-0012 CURB, RADIAL CG-2	271.000 LF	_____	_____	_____	_____
0460	502	502SD20-0015 CURB, RADIAL CG-3 MOD.	371.000 LF	_____	_____	_____	_____
0470	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	1,039.000 LF	_____	_____	_____	_____
0480	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	1,042.000 LF	_____	_____	_____	_____
0490	502	502SD20-0053 MEDIAN STRIP MS-1	283.000 SY	_____	_____	_____	_____
0500	508	508SD20-0001 OBSCURING ROADWAY	3.000 UNIT	_____	_____	_____	_____
0510	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	1,995.000 SY	_____	_____	_____	_____
0520	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	2,627.000 SY	_____	_____	_____	_____
0530	509	509SD20-0001 FLOWABLE BACKFILL	4.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	2.000 EA	_____	_____	_____	_____
0550	510	510SD20-0043 ADJ.EXIST.WATER MANHOLE FRAME & COVE	1.000 EA	_____	_____	_____	_____
0560	510	510SX20-0040 REMOVE EXIST. REMOVE EXISTING FLASHER	1.000 EA	_____	_____	_____	_____
0570	511	511SD20-0001 ALLAYING DUST	200.000 HR	_____	_____	_____	_____
0580	512	512SD20-0014 TEMPORARY SIGN	607.000 SF	_____	_____	_____	_____
0590	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	3,360.000 HR	_____	_____	_____	_____
0600	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	21,956.000 DAY	_____	_____	_____	_____
0610	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	672.000 HR	_____	_____	_____	_____
0620	512	512SD20-0027 FLAGGER SERVICE	5,280.000 HR	_____	_____	_____	_____
0630	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	10,212.000 LF	_____	_____	_____	_____
0640	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	227.000 SF	_____	_____	_____	_____
0650	512	512SD20-0051 TEMP. PVMT. SYMB. MRKG THRU ARROW TY. A	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	2.000 EA	_____	_____	_____	_____
0670	512	512SD20-0053 TEMP. PVMT. SYMB. MRKG R/R CROSSING TY. A	2.000 EA	_____	_____	_____	_____
0680	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4" WHITE	2,768.000 LF	_____	_____	_____	_____
0690	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4" YELLOW	3,374.000 LF	_____	_____	_____	_____
0700	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8" WHITE	2,006.000 LF	_____	_____	_____	_____
0710	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	960.000 DAY	_____	_____	_____	_____
0720	512	512SX20-0006 TEMP. PVMT MRKG TY. D CL. III WHITE YIELD (1'X1.5')	32.000 EA	_____	_____	_____	_____
0730	512	512SX20-0006 TEMP. PVMT MRKG TY. D CL. III WHITE YIELD (2'X3')	24.000 EA	_____	_____	_____	_____
0740	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0750	514	514SD20-0001 FIELD OFFICE TY.I	16.000 MO	_____	_____	_____	_____
0760	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	603.000 SY	_____	_____	_____	_____
0770	515	515SD20-0014 FLEXIBLE PAVEMENT PLANING ABOVE 2"-4"	147.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	515	515SD20-0015 FLEXIBLE PAVEMENT PLANING ABOVE 4"	482.000 SY	_____	_____	_____	_____
0790	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0800	520	520SD20-0014 6" DI WATER MAIN	14.000 LF	_____	_____	_____	_____
0810	520	520SD20-0017 10" WATER MAIN	381.000 LF	_____	_____	_____	_____
0820	520	520SD20-0020 12" DI WATER MAIN	135.000 LF	_____	_____	_____	_____
0830	520	520SD20-0089 6" GATE VALVE & BOX	2.000 EA	_____	_____	_____	_____
0840	520	520SD20-0091 10" GATE VALVE & BOX	2.000 EA	_____	_____	_____	_____
0850	520	520SD20-0092 12" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
0860	520	520SD20-0162 FIRE HYDRANT	2.000 EA	_____	_____	_____	_____
0870	520	520SD20-0299 24" STEEL JACKED ENCASEMENT PIPE	59.000 LF	_____	_____	_____	_____
0880	ATTD	522SX20-0006 ENVIR. PROTECTION TRANSPORTATION & DISPOSAL OF CONTAMINATED GROUNDWATER	5,000.000 GAL	_____	_____	_____	_____
0890	ATTD	522SX20-0007 ENVIR. PROTECTION MGT CONTAMINATED GROUNDWATER (ONSITE)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0900	ATTD	522SX20-0007 ENVIR. PROTECTION MGT OF CONTAMINATED SOIL (ONSITE)	LUMP SUM	LUMP SUM			
0910	ATTD	522SX20-0008 ENVIR. PROTECTION TRANSPORTATION & DISPOSAL OF CONTAMINATED SOIL	560.000 TON				
0920	602	602SD20-0003 TOPSOIL CLASS B 2"	1.220 ACRE				
0930	603	603SD20-0002 TEMPORARY SEED	122.000 LB				
0940	603	603SD20-0003 REGULAR SEED	328.000 LB				
0950	603	603SD20-0004 OVERSEEDING	262.000 LB				
0960	603	603SD20-0005 LEGUME SEED	15.000 LB				
0970	603	603SD20-0006 LEGUME OVERSEEDING	12.000 LB				
0980	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	7,381.000 SY				
0990	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	5,905.000 SY				
1000	603	603SD20-0014 FERTILIZER NITROGEN - N	122.000 LB				
1010	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	85.000 LB				

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1020	603	603SD20-0016 FERTILIZER POTASSIUM - K	85.000 LB	_____	_____	_____	_____
1030	603	603SD20-0017 LIME	6.710 TON	_____	_____	_____	_____
1040	ATTD	605SX20-0014 LANDSCAPE ORGANIC BACKFILL HARDWOOD BARK MULCH	32.000 CY	_____	_____	_____	_____
1050	ATTD	605SX20-0014 LANDSCAPE RIVER JACKS STONE (3-5" DIAMETER)	50.000 CY	_____	_____	_____	_____
1060	605	605SX20-0019 TREE 'NELLIE R. STEVENS' HOLLY	7.000 EA	_____	_____	_____	_____
1070	605	605SX20-0020 SHRUB 'OYYO LUYKEN' CHERRYLAUREL	58.000 EA	_____	_____	_____	_____
1080	605	605SX20-0021 HERB 'HAPPY RETURNS' DAYLILY	280.000 EA	_____	_____	_____	_____
1090	605	605SX20-0021 HERB 'PARDON ME' DAYLILY	280.000 EA	_____	_____	_____	_____
1100	605	605SX20-0021 HERB 'PETITE DELIGHT' BEE BALM	140.000 EA	_____	_____	_____	_____
1110	605	605SX20-0021 HERB 'POW WOW WHITE' CONEFLOWER	140.000 EA	_____	_____	_____	_____
1120	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	277.100 SY	_____	_____	_____	_____
1130	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	169.500 SY	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1140	608	608SD20-0001 MOWING	40.000 HR	_____	_____	_____	_____
1150	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	20.000 EA	_____	_____	_____	_____
1160	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	1.000 EA	_____	_____	_____	_____
1170	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	2.000 EA	_____	_____	_____	_____
1180	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	298.000 LF	_____	_____	_____	_____
1190	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	58.000 LF	_____	_____	_____	_____
1200	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	213.000 LF	_____	_____	_____	_____
1210	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	85.000 LF	_____	_____	_____	_____
1220	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	29.000 EA	_____	_____	_____	_____
1230	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	14.000 EA	_____	_____	_____	_____
1240	700	700SD20-0144 8 CONDUCTOR CABLE	2,420.000 LF	_____	_____	_____	_____
1250	700	700SD20-0148 8 CONDUCTOR CABLE EGC	920.000 LF	_____	_____	_____	_____
1260	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	8.000 EA	_____	_____	_____	_____

## Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1270	700	700SD20-0156 LIGHTING POLE LP-2 TYPE D	8.000 EA	_____	_____	_____	_____
1280	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
1290	700	700SD20-0178 JUNCTION BOX JB-S2	6.000 EA	_____	_____	_____	_____
1300	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
1310	700	700SD20-0192 BORED CONDUIT 3"	215.000 LF	_____	_____	_____	_____
1320	700	700SD20-0194 CONDUIT PVC 2"	705.000 LF	_____	_____	_____	_____
1330	700	700SD20-0197 TRENCH EXCAVATION ECI-1	705.000 LF	_____	_____	_____	_____
1340	ATTD	700SX20-0014 LIGHTING ELECTRICAL SERVICE SE-5 (RDTO)	LUMP SUM	LUMP SUM	_____	_____	_____
1350	ATTD	700SX20-0021 TRAFFIC SIGN HISTORICAL MARKER POST & FOUNDATION	1.000 EA	_____	_____	_____	_____
1360	701	701SD20-0001 SIGN PANEL	402.000 SF	_____	_____	_____	_____
1370	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	3,075.000 LF	_____	_____	_____	_____
1380	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	45.000 LF	_____	_____	_____	_____
1390	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	105.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115403C01B    Oversight/State Project No.: 0040-067-738, C501  
 Order No.: N67    Federal Project No.: STP-067-4(037)

Contractor: \_\_\_\_\_

SECTION: 0001    REGULAR BID ITEMS

Cat Alt Set ID:    Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1400	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	20.000 EA	_____	_____	_____	_____
1410	704	704SD20-0090 PVMT SYMB MRKG R/R CROSSING TY B CL II	1.000 EA	_____	_____	_____	_____
1420	705	705SD20-0003 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
1430	ATTD	705SX20-0001 LUMINAIRE 49W LED POLE- MOUNT	8.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	_____
				<b>Total Bid:</b>		_____	_____