

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 CONST REC DOCS SWM FACILITY SWM FACILITY	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	35.000 EA				
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	302, 406	302SD20-0005 REINF. STEEL	201.000 LB				
0060	302	302SD20-0012 ENDWALL GRATE & FRAME EW-11A	1.000 EA				
0070	302	302SD20-0013 ENDWALL EW-12	3.000 EA				
0080	302	302SD20-0027 15" STORM SEWER PIPE	2,540.000 LF				
0090	302	302SD20-0030 18" CONC. PIPE	97.000 LF				
0100	302	302SD20-0032 18" STORM SEWER PIPE	890.000 LF				
0110	302	302SD20-0038 24" JACKED & BORED PIPE	51.000 LF				
0120	302	302SD20-0039 24" CONC. PIPE	246.000 LF				
0130	302	302SD20-0041 24" STORM SEWER PIPE	1,324.000 LF				
0140	302	302SD20-0051 30" STORM SEWER PIPE	1,056.000 LF				

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0061 36" STORM SEWER PIPE	410.000 LF	_____	_____	_____	_____
0160	302	302SD20-0064 42" CONC. PIPE	12.000 LF	_____	_____	_____	_____
0170	302	302SD20-0066 42" STORM SEWER PIPE	60.000 LF	_____	_____	_____	_____
0180	302	302SD20-0198 15" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0190	302	302SD20-0200 18" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0200	302	302SD20-0237 DROP INLET DI-1	6.000 EA	_____	_____	_____	_____
0210	302	302SD20-0241 DROP INLET DI-2B,L=4'	3.000 EA	_____	_____	_____	_____
0220	302	302SD20-0312 DROP INLET DI-3B,L=6'	1.000 EA	_____	_____	_____	_____
0230	302	302SD20-0313 DROP INLET DI-3B,L=8'	7.000 EA	_____	_____	_____	_____
0240	302	302SD20-0314 DROP INLET DI-3B,L=10'	4.000 EA	_____	_____	_____	_____
0250	302	302SD20-0329 DROP INLET DI-3C,L=6'	2.000 EA	_____	_____	_____	_____
0260	302	302SD20-0330 DROP INLET DI-3C,L=8'	1.000 EA	_____	_____	_____	_____
0270	302	302SD20-0446 DROP INLET DI-5	26.000 EA	_____	_____	_____	_____
0280	302	302SD20-0447 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0290	302	302SD20-0501 DROP INLET DI-10K TY. II,L=8'	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0300	302	302SD20-0511 DROP INLET DI-10K TY. III,L=10'	1.000 EA	_____	_____	_____	_____
0310	302	302SD20-0661 MANHOLE MH-2	9.000 LF	_____	_____	_____	_____
0320	302	302SD20-0662 MANHOLE MH-1 OR 2	127.600 LF	_____	_____	_____	_____
0330	302	302SD20-0663 FRAME & COVER MH-1	18.000 EA	_____	_____	_____	_____
0340	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	24.200 LF	_____	_____	_____	_____
0350	ATTD	302SX20-0013 PIPE REHABILITATION (18" METHOD B, CATEGORY A OR B)	74.000 LF	_____	_____	_____	_____
0360	303	303SD20-0001 REGULAR EXCAVATION	61,526.000 CY	_____	_____	_____	_____
0370	303	303SD20-0021 TEMPORARY DIVERSION DIKE	256.000 LF	_____	_____	_____	_____
0380	303	303SD20-0023 CHECK DAM ROCK TY. II	265.000 EA	_____	_____	_____	_____
0390	303	303SD20-0029 SILTATION CONTROL EXCAVATION	3,406.000 CY	_____	_____	_____	_____
0400	303	303SD20-0030 INLET PROTECTION TYPE A	48.000 EA	_____	_____	_____	_____
0410	303	303SD20-0031 INLET PROTECTION TYPE B	42.000 EA	_____	_____	_____	_____
0420	303	303SD20-0034 TEMP. SILT FENCE TYPE A	6,023.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0430	303	303SD20-0035 TEMP. SEDIMENT BASIN EXCAVATION	12,431.000 CY	_____	_____	_____	_____
0440	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	2,214.000 CY	_____	_____	_____	_____
0450	ATTD	303SX20-0012 UTILITY TEST PIT UNPAVED	22.000 EA	_____	_____	_____	_____
0460	ATTD	303SX20-0013 UTILITY TEST PIT ASPHALT CONCRETE	7.000 EA	_____	_____	_____	_____
0470	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	28,627.000 TON	_____	_____	_____	_____
0480	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	539.000 TON	_____	_____	_____	_____
0490	ATTD	308SX20-0005 COARSE AGGREGATE NO.8	167.000 TON	_____	_____	_____	_____
0500	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	6,934.000 TON	_____	_____	_____	_____
0510	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	121.000 TON	_____	_____	_____	_____
0520	315	315SD20-0009 ASPHALT CONCRETE TY. SM-9.5E CONST	4,675.000 TON	_____	_____	_____	_____
0530	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	9,766.000 TON	_____	_____	_____	_____
0540	ATTD	315SX20-0004 PAVEMENT LIQUID ASPHALT COATING (PAVEMENT MARKER GROOVE)	136.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	ATTD	315SX20-0011 SAW-CUT ASPH CONC 12" DEPTH	10,402.000 LF	_____	_____	_____	_____
0560	316	316SD20-0030 CONCRETE ENTRANCE PAVE. 7"	222.000 SY	_____	_____	_____	_____
0570	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	308.800 CY	_____	_____	_____	_____
0580	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	2,670.000 TON	_____	_____	_____	_____
0590	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	84.000 SY	_____	_____	_____	_____
0600	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	332.000 LF	_____	_____	_____	_____
0610	402	402SD20-0004 TEMPORARY SHEET PILING	14,092.000 SF	_____	_____	_____	_____
0620	ATTD	402SX20-0001 TEMP. SUPPORT OF EXCAVATION (VIRGINIA STR. NO. 1800)	5,100.000 SF	_____	_____	_____	_____
0630	403	403SD20-0006 STEEL PILES 12"	1,868.000 LF	_____	_____	_____	_____
0640	403	403SD20-0034 PILE POINT FOR 12" STEEL PILE	42.000 EA	_____	_____	_____	_____
0650	403	403SD20-0036 DRIVING TEST FOR 12" STEEL PILE	372.000 LF	_____	_____	_____	_____
0660	ATTD	403SX20-0001 DYNAMIC PILE TEST END BEARING PILES	6.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	588.500 CY	_____	_____	_____	_____
0680	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	2,056.000 SY	_____	_____	_____	_____
0690	404	404SD20-0010 COVER DEPTH SURVEY CONST.	1,518.000 SY	_____	_____	_____	_____
0700	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	69.800 CY	_____	_____	_____	_____
0710	406	406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST.	89,000.000 LB	_____	_____	_____	_____
0720	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	9,940.000 LB	_____	_____	_____	_____
0730	407	407SD20-0015 STR. STEEL PLATE GIRDER ASTM A709 GR.50W	LUMP SUM	LUMP SUM	_____	_____	_____
0740	ATTD	410SX20-0001 ARCHITECTURAL TREATMENT SUBSTRUCTURE	564.000 SY	_____	_____	_____	_____
0750	ATTD	410SX20-0001 ARCHITECTURAL TREATMENT SUPERSTRUCTURE	178.000 SY	_____	_____	_____	_____
0760	ATTD	410SX20-0004 BRIDGE SUPERSTRUCTURE CRR STEEL, CLASS I BRIDGE APPROACH SLAB	52,380.000 LB	_____	_____	_____	_____
0770	ATTD	410SX20-0011 PIER PROTECTION SYSTEM 54", CONST	352.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	ATTD	410SX20-0020 PARAPET RAILING, CPSR 2 RAILS	337.000 LF	_____	_____	_____	_____
0790	ATTD	412SX20-0002 CONC. SURFACE COLOR COATING (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0800	ATTD	413SX20-0002 DISM.& REM. EX. STR. (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0810	413	413SX20-0003 ENV.& WORKER PROTECT. (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0820	413	413SX20-0004 MATERIAL DISPOSAL (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0830	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	14.500 TON	_____	_____	_____	_____
0840	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	9.300 TON	_____	_____	_____	_____
0850	414	414SD20-0005 EROSION CTRL. STONE CL. II, EC-1	19.000 TON	_____	_____	_____	_____
0860	ATTD	419SX20-0005 WATER LINE (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0870	ATTD	419SX20-0008 BRG. CONDUIT SYSTEM (VIRGINIA STR. NO. 1800)	LUMP SUM	LUMP SUM	_____	_____	_____
0880	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (VIRGINIA STR. NO. 1800)	4.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0890	ATTD	432SD20-0001 ELASTIC INCLUSION - STANDARD EPS	78.000 CY	_____	_____	_____	_____
0900	501	501SD20-0001 UNDERDRAIN UD-1	8,954.000 LF	_____	_____	_____	_____
0910	501	501SD20-0002 UNDERDRAIN UD-2	557.000 LF	_____	_____	_____	_____
0920	501	501SD20-0003 UNDERDRAIN UD-3	1,683.000 LF	_____	_____	_____	_____
0930	501	501SD20-0009 OUTLET PIPE	492.000 LF	_____	_____	_____	_____
0940	502	502SD20-0003 PAVED DITCH PG-2A	730.000 SY	_____	_____	_____	_____
0950	502	502SD20-0011 CURB, STD. CG-2	858.000 LF	_____	_____	_____	_____
0960	502	502SD20-0012 CURB, RADIAL CG-2	77.000 LF	_____	_____	_____	_____
0970	502	502SD20-0014 CURB, STD. CG-3	109.000 LF	_____	_____	_____	_____
0980	502	502SD20-0015 CURB, RADIAL CG-3	212.000 LF	_____	_____	_____	_____
0990	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	2,245.000 LF	_____	_____	_____	_____
1000	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	1,069.000 LF	_____	_____	_____	_____
1010	502	502SD20-0031 ENTRANCE GUTTER CG-13	111.000 SY	_____	_____	_____	_____
1020	502	502SD20-0038 MEDIAN BARRIER MB-7F	603.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1030	502	502SD20-0039 MEDIAN BARRIER MB-9A	48.000 LF	_____	_____	_____	_____
1040	502	502SD20-0044 MEDIAN BARRIER MB-8A TYPE I	396.000 LF	_____	_____	_____	_____
1050	502	502SD20-0053 MEDIAN STRIP MS-1	1,118.000 SY	_____	_____	_____	_____
1060	502	502SD20-0056 MEDIAN STRIP MS-1A	100.000 SY	_____	_____	_____	_____
1070	ATTD	502SX20-0002 MEDIAN BARRIER MODIFIED MB-7F TYPE A	255.000 LF	_____	_____	_____	_____
1080	ATTD	502SX20-0002 MEDIAN BARRIER MODIFIED MB-7F TYPE B	220.000 LF	_____	_____	_____	_____
1090	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	56.900 CY	_____	_____	_____	_____
1100	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	51.000 SY	_____	_____	_____	_____
1110	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	501.000 SY	_____	_____	_____	_____
1120	ATTD	504SX20-0003 HANDRAIL HR-1 TYPE II	164.000 LF	_____	_____	_____	_____
1130	505	505SD20-0011 GUARDRAIL GR-MGS1	150.000 LF	_____	_____	_____	_____
1140	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	6.000 EA	_____	_____	_____	_____
1150	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1160	505	505SD20-0053 FIXED OBJECT ATTACH. GR-FOA-2 TY. I	2.000 EA	_____	_____	_____	_____
1170	505	505SD20-0055 FIXED OBJECT ATTACH. GR-FOA-5	4.000 EA	_____	_____	_____	_____
1180	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	2,837.000 LF	_____	_____	_____	_____
1190	506	506SD20-0002 RETAINING WALL RW-3	395.000 CY	_____	_____	_____	_____
1200	506	506SD20-0007 RETAINING WALL EXCAVATION	1,207.000 CY	_____	_____	_____	_____
1210	ATTD	506SX20-0006 RETAINING WALL TEMPORARY SUPPORT OF FILL	5,170.000 SF	_____	_____	_____	_____
1220	ATTD	506SX20-0007 RETAINING STRUCTURE MSE WALL	7,910.000 SF	_____	_____	_____	_____
1230	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	2,384.000 LF	_____	_____	_____	_____
1240	507	507SD20-0032 PEDESTRIAN FENCE 8'	127.000 LF	_____	_____	_____	_____
1250	ATTD	507SX20-0013 FENCE (FE-CL)	1,067.000 LF	_____	_____	_____	_____
1260	508	508SD20-0001 OBSCURING ROADWAY	39.000 UNIT	_____	_____	_____	_____
1270	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	18,869.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1280	509	509SD20-0001 FLOWABLE BACKFILL	235.400 CY	_____	_____	_____	_____
1290	ATTD	510SX20-0002 REMOVE COMB. CURB AND GUTTER	2,200.000 LF	_____	_____	_____	_____
1300	ATTD	510SX20-0040 REMOVE EXIST. COMM ANTENNA	1.000 EA	_____	_____	_____	_____
1310	510	510SX20-0040 REMOVE EXIST. CONC. PAD WITH MASONRY	1.000 EA	_____	_____	_____	_____
1320	510	510SX20-0040 REMOVE EXIST. CONC. PAD WITH MASONRY AND PICNIC TABLE	1.000 EA	_____	_____	_____	_____
1330	ATTD	510SX20-0040 REMOVE EXIST. ELECTRICAL SERVICE	1.000 EA	_____	_____	_____	_____
1340	ATTD	510SX20-0040 REMOVE EXIST. EMERGENCY PREEMPTION DETECTOR	6.000 EA	_____	_____	_____	_____
1350	510	510SX20-0040 REMOVE EXIST. LIGHT POLE	3.000 EA	_____	_____	_____	_____
1360	510	510SX20-0040 REMOVE EXIST. SIGN	8.000 EA	_____	_____	_____	_____
1370	ATTD	510SX20-0040 REMOVE EXIST. VIDEO DETECTION CAMERA	2.000 EA	_____	_____	_____	_____
1380	511	511SD20-0001 ALLAYING DUST	223.000 HR	_____	_____	_____	_____
1390	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	1,700.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1400	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH	14.000 EA	_____	_____	_____	_____
1410	512	512SD20-0009 IMPACT ATTEN.SER. TY. III TL-2, <=45 MPH	41.000 EA	_____	_____	_____	_____
1420	512	512SD20-0013 TYPE 3 BARRICADE 8'	43.000 EA	_____	_____	_____	_____
1430	512	512SD20-0014 TEMPORARY SIGN	4,548.000 SF	_____	_____	_____	_____
1440	512	512SD20-0022 GROUP 2 LONGITUDINAL CHANNELIZING DEVICE	4.000 LF	_____	_____	_____	_____
1450	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	540.000 HR	_____	_____	_____	_____
1460	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	720,360.000 DAY	_____	_____	_____	_____
1470	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	54,976.000 HR	_____	_____	_____	_____
1480	512	512SD20-0026 ELECTRONIC ARROW BOARD	540.000 HR	_____	_____	_____	_____
1490	512	512SD20-0027 FLAGGER SERVICE	500.000 HR	_____	_____	_____	_____
1500	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	108,281.000 LF	_____	_____	_____	_____
1510	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	2,704.000 SF	_____	_____	_____	_____
1520	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	1,464.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1530	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	36,490.000 LF	_____	_____	_____	_____
1540	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	40,802.000 LF	_____	_____	_____	_____
1550	512	512SD20-0048 TEMP. PVMT MRKG TY. A, 8"	12,923.000 LF	_____	_____	_____	_____
1560	512	512SD20-0050 TEMP. PVMT MRKG TY. A, 24"	1,145.000 LF	_____	_____	_____	_____
1570	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	63.000 EA	_____	_____	_____	_____
1580	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	3,198.000 LF	_____	_____	_____	_____
1590	512	512SD20-0066 TRAFFIC BARRIER SERVICE CONC.	27,700.000 LF	_____	_____	_____	_____
1600	512	512SX20-0020 MODIFY SIGNAL CANDLERS MOUNTAIN ROAD AND WOODALL ROAD	LUMP SUM	LUMP SUM	_____	_____	_____
1610	512	512SX20-0050 TEMP. TRAFFIC CONTROL SIGNAL CANDLERS MOUNTAIN ROAD AND ROUTE 29 BUSINESS RAMP D	LUMP SUM	LUMP SUM	_____	_____	_____
1620	512	512SX20-0050 TEMP. TRAFFIC CONTROL SIGNAL CANDLERS MOUNTAIN ROAD AND ROUTE 29 BUSINESS RAMP F	LUMP SUM	LUMP SUM	_____	_____	_____
1630	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
1640	514	514SD20-0002 FIELD OFFICE TY.II	36.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1650	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	24,728.000 SY	_____	_____	_____	_____
1660	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
1670	520	520SD20-0006 2" WATER SERVICE LINE	23.000 LF	_____	_____	_____	_____
1680	520	520SD20-0014 6" DI WATER MAIN	146.000 LF	_____	_____	_____	_____
1690	520	520SD20-0016 8" DI WATER MAIN	1,471.000 LF	_____	_____	_____	_____
1700	520	520SD20-0020 12" DI WATER MAIN	5.000 LF	_____	_____	_____	_____
1710	520	520SD20-0089 6" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1720	520	520SD20-0090 8" GATE VALVE & BOX	5.000 EA	_____	_____	_____	_____
1730	520	520SD20-0162 FIRE HYDRANT	2.000 EA	_____	_____	_____	_____
1740	520	520SD20-0165 2" AIR RELEASE VALVE & BOX	2.000 EA	_____	_____	_____	_____
1750	520	520SD20-0175 2" WATER METER & BOX	1.000 EA	_____	_____	_____	_____
1760	520	520SD20-0183 6" SANITARY SERVICE LATERAL CONNECTION	14.000 LF	_____	_____	_____	_____
1770	520	520SD20-0185 8" SANITARY SEWER PIPE	738.000 LF	_____	_____	_____	_____
1780	520	520SD20-0266 8" SANITARY DROP CONNECTION	9.200 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1790	520	520SD20-0272 SANITARY SEWER MANHOLE	59.300 LF	_____	_____	_____	_____
1800	520	520SD20-0274 MANHOLE FRAME & COVER F & C-1	5.000 EA	_____	_____	_____	_____
1810	520	520SX20-0006 6" SEWER CLEANOUT	1.000 EA	_____	_____	_____	_____
1820	602	602SX20-0005 TOPSOIL CLASS B 3"	5.810 ACRE	_____	_____	_____	_____
1830	603	603SD20-0001 PERMANENT SEED	2,542.000 LB	_____	_____	_____	_____
1840	603	603SD20-0002 TEMPORARY SEED	2,034.000 LB	_____	_____	_____	_____
1850	603	603SD20-0004 OVERSEEDING	2,034.000 LB	_____	_____	_____	_____
1860	603	603SD20-0005 LEGUME SEED	69.000 LB	_____	_____	_____	_____
1870	603	603SD20-0006 LEGUME OVERSEEDING	55.000 LB	_____	_____	_____	_____
1880	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	28,120.000 SY	_____	_____	_____	_____
1890	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	1,089.000 LF	_____	_____	_____	_____
1900	603	603SD20-0014 FERTILIZER NITROGEN - N	581.000 LB	_____	_____	_____	_____
1910	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	407.000 LB	_____	_____	_____	_____
1920	603	603SD20-0016 FERTILIZER POTASSIUM - K	407.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1930	603	603SD20-0017 LIME	31.960 TON	_____	_____	_____	_____
1940	ATTD	605SX20-0011 LANDSCAPE MEADOW SEED MIX	19,949.000 SY	_____	_____	_____	_____
1950	605	605SX20-0019 TREE AMERICAN HOPHORNBEAM	8.000 EA	_____	_____	_____	_____
1960	605	605SX20-0019 TREE AUTUMN BRILLIANCE APPLE SERVICEBERRY	26.000 EA	_____	_____	_____	_____
1970	605	605SX20-0019 TREE BRACKEN'S BEAUTY SOUTHERN MAGNOLIA	39.000 EA	_____	_____	_____	_____
1980	605	605SX20-0019 TREE EASTERN REDBUD	29.000 EA	_____	_____	_____	_____
1990	605	605SX20-0019 TREE EASTERN REDCEDAR	22.000 EA	_____	_____	_____	_____
2000	605	605SX20-0019 TREE MUSKOGEE CRAPE MYRTLE (MULTI-TRUNK)	64.000 EA	_____	_____	_____	_____
2010	605	605SX20-0019 TREE OCTOBER GLORY RED MAPLE	7.000 EA	_____	_____	_____	_____
2020	605	605SX20-0019 TREE SATYR HILL AMERICAN HOLLY	23.000 EA	_____	_____	_____	_____
2030	605	605SX20-0019 TREE SCARLET OAK	11.000 EA	_____	_____	_____	_____
2040	605	605SX20-0019 TREE SWAMP WHITE OAK	7.000 EA	_____	_____	_____	_____
2050	605	605SX20-0019 TREE TUPELO	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2060	605	605SX20-0019 TREE WHITE FRINGETREE	32.000 EA	_____	_____	_____	_____
2070	605	605SX20-0019 TREE WINTER KING HAWTHORN	18.000 EA	_____	_____	_____	_____
2080	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	8,172.000 SY	_____	_____	_____	_____
2090	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	53.000 EA	_____	_____	_____	_____
2100	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	13.000 EA	_____	_____	_____	_____
2110	700	700SD20-0005 REMOVE EXISTING 3 POST SIGN STRUCTURE	2.000 EA	_____	_____	_____	_____
2120	700	700SD20-0014 RELOCATE EX. 3 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
2130	700	700SD20-0018 VA SIGN POST W4 X 13	75.000 LF	_____	_____	_____	_____
2140	700	700SD20-0020 VIA SIGN POST W10 X 12	33.000 LF	_____	_____	_____	_____
2150	700	700SD20-0021 VIA SIGN POST W12 X 14	29.000 LF	_____	_____	_____	_____
2160	700	700SD20-0022 VIA SIGN POST W12 X 16	37.000 LF	_____	_____	_____	_____
2170	700	700SD20-0023 VIA SIGN POST W12 X 19	80.000 LF	_____	_____	_____	_____
2180	700	700SD20-0025 VIA SIGN POST W14 X 26	100.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2190	700	700SD20-0029 VIA SIGN POST W18 X 40	50.000 LF	_____	_____	_____	_____
2200	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	680.000 LF	_____	_____	_____	_____
2210	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	36.000 LF	_____	_____	_____	_____
2220	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	316.000 LF	_____	_____	_____	_____
2230	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	136.000 LF	_____	_____	_____	_____
2240	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	48.000 EA	_____	_____	_____	_____
2250	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	19.000 EA	_____	_____	_____	_____
2260	700	700SD20-0046 CONC. FOUND. SSP-VA, 1'9" DIA. X 4'6" DEEP	3.000 EA	_____	_____	_____	_____
2270	700	700SD20-0048 CONC. FOUND. SSP-VIA, 2'3" DIA. X 4'6" DEEP	2.000 EA	_____	_____	_____	_____
2280	700	700SD20-0049 CONC. FOUND. SSP-VIA, 3' DIA. X 7' DEEP	12.000 EA	_____	_____	_____	_____
2290	700	700SD20-0053 CONC. FOUND. SSP-VIA, 4' DIA. X 9'6" DEEP	4.000 EA	_____	_____	_____	_____
2300	700	700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE	55.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2310	700	700SD20-0060 ELECTRICAL SERVICE SE-5	4.000 EA	_____	_____	_____	_____
2320	700	700SD20-0067 PEDESTAL POLE PF-2, 12'	1.000 EA	_____	_____	_____	_____
2330	700	700SD20-0068 CONC. FOUND. PF-8	86.000 CY	_____	_____	_____	_____
2340	700	700SD20-0069 CONC. FOUND. PF-2	1.000 EA	_____	_____	_____	_____
2350	700	700SD20-0094 SIGNAL MAST ARM POLE MP-3, TY. D	3.000 EA	_____	_____	_____	_____
2360	700	700SD20-0095 SIGNAL MAST ARM POLE MP-3, TY. E1	4.000 EA	_____	_____	_____	_____
2370	700	700SD20-0097 SIGNAL MAST ARM POLE MP-3, TY. F	1.000 EA	_____	_____	_____	_____
2380	700	700SD20-0098 MAST ARM 30'	1.000 EA	_____	_____	_____	_____
2390	700	700SD20-0099 MAST ARM 40'	1.000 EA	_____	_____	_____	_____
2400	700	700SD20-0100 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
2410	700	700SD20-0101 MAST ARM 60'	2.000 EA	_____	_____	_____	_____
2420	700	700SD20-0103 MAST ARM 70'	3.000 EA	_____	_____	_____	_____
2430	700	700SD20-0110 14/2 CONDUCTOR CABLE	1,195.000 LF	_____	_____	_____	_____
2440	700	700SD20-0112 14/4 CONDUCTOR CABLE	3,725.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2450	700	700SD20-0114 14/7 CONDUCTOR CABLE	1,005.000 LF	_____	_____	_____	_____
2460	700	700SD20-0120 14/2 CONDUCTOR CABLE SHIELDED	2,285.000 LF	_____	_____	_____	_____
2470	700	700SD20-0144 8 CONDUCTOR CABLE	345.000 LF	_____	_____	_____	_____
2480	700	700SD20-0148 8 CONDUCTOR CABLE EGC	3,800.000 LF	_____	_____	_____	_____
2490	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	57.000 EA	_____	_____	_____	_____
2500	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	4.000 EA	_____	_____	_____	_____
2510	700	700SD20-0177 JUNCTION BOX JB-S1	72.000 EA	_____	_____	_____	_____
2520	700	700SD20-0178 JUNCTION BOX JB-S2	29.000 EA	_____	_____	_____	_____
2530	700	700SD20-0179 JUNCTION BOX JB-S3	9.000 EA	_____	_____	_____	_____
2540	700	700SD20-0180 JUNCTION BOX JB-S4	2.000 EA	_____	_____	_____	_____
2550	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	20.000 EA	_____	_____	_____	_____
2560	700	700SD20-0191 BORED CONDUIT 2"	1,365.000 LF	_____	_____	_____	_____
2570	700	700SD20-0192 BORED CONDUIT 3"	2,895.000 LF	_____	_____	_____	_____
2580	700	700SD20-0193 BORED CONDUIT 4"	120.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2590	700	700SD20-0194 CONDUIT PVC 2"	12,330.000 LF	_____	_____	_____	_____
2600	700	700SD20-0195 CONDUIT PVC 3"	460.000 LF	_____	_____	_____	_____
2610	700	700SD20-0197 TRENCH EXCAVATION ECI-1	13,020.000 LF	_____	_____	_____	_____
2620	700	700SD20-0199 TEST BORE	11.000 EA	_____	_____	_____	_____
2630	700	700SD20-0222 LUMINAIRE ARM 12'	3.000 EA	_____	_____	_____	_____
2640	700	700SD20-0224 LUMINAIRE ARM 16'	1.000 EA	_____	_____	_____	_____
2650	700	700SD20-0225 LUMINAIRE ARM 18'	2.000 EA	_____	_____	_____	_____
2660	ATTD 700	700SX20-0003 SIGN STRUCTURE, OVERHEAD CANT. 46 FT	1.000 EA	_____	_____	_____	_____
2670	ATTD	700SX20-0007 CONDUCTOR CABLE 10/3C	1,595.000 LF	_____	_____	_____	_____
2680	ATTD	700SX20-0007 CONDUCTOR CABLE CAT 5e GEL FILLED SHIELDED DIRECT BURIAL CABLE	3,030.000 LF	_____	_____	_____	_____
2690	ATTD	700SX20-0007 CONDUCTOR CABLE CAT6 WATER BLOCKING, SHIELDED, DIRECT BURIED CABLE	50.000 LF	_____	_____	_____	_____
2700	ATTD	700SX20-0007 CONDUCTOR CABLE EVP DETECTOR CABLE (INFRARED)	2,285.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2710	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION APS MOUNTING EXTENDER	1.000 EA	_____	_____	_____	_____
2720	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION APS PEDESTRIAN ACTUATION (PA-2)	3.000 EA	_____	_____	_____	_____
2730	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION APS PEDESTRIAN ACTUATION (PA-3)	3.000 EA	_____	_____	_____	_____
2740	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION ATC CABINET - TYPE II (32 OUTPUTS)	3.000 EA	_____	_____	_____	_____
2750	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION AUXILIARY COMMUNICATIONS CABINET	3.000 EA	_____	_____	_____	_____
2760	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION EVP DETECTION SYSTEM INFRARED (2-WAY)	1.000 EA	_____	_____	_____	_____
2770	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION EVP DETECTION SYSTEM INFRARED (3-WAY)	2.000 EA	_____	_____	_____	_____
2780	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION LOCAL CONTROLLER (ATC)	3.000 EA	_____	_____	_____	_____
2790	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION RECTANGULAR RAPID FLASHING BEACON ASSEMBLY	4.000 EA	_____	_____	_____	_____
2800	700	700SX20-0017 REMOVE EXIST. OVERHEAD SIGN STRUCTURE .	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2810	700	700SX20-0022 CONC FOUNDATION CF-5	3.000 EA	_____	_____	_____	_____
2820	700	700SX20-0030 LUMINAIRE ARM 15'	1.000 EA	_____	_____	_____	_____
2830	701	701SD20-0001 SIGN PANEL	1,998.000 SF	_____	_____	_____	_____
2840	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	65.000 EA	_____	_____	_____	_____
2850	703	703SD20-0039 HANGER ASSEMBLY SMB-3, ONE WAY	4.000 EA	_____	_____	_____	_____
2860	703	703SD20-0044 REMOVE EXISTING POLE	6.000 EA	_____	_____	_____	_____
2870	703	703SD20-0045 REMOVE EXISTING FOUNDATION	108.000 EA	_____	_____	_____	_____
2880	703	703SD20-0046 REMOVE EXISTING SIGNAL HEAD	22.000 EA	_____	_____	_____	_____
2890	703	703SD20-0047 REMOVE EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
2900	703	703SD20-0048 REMOVE EXISTING MANHOLE/JUNCTION BOX	20.000 EA	_____	_____	_____	_____
2910	703	703SD20-0053 UNINTERRUPT. PWR SUPPLY TYPE 2	3.000 EA	_____	_____	_____	_____
2920	703	703SD20-0054 UNINTERRUPT. PWR SUPPLY BATTERY PAC	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2930	703	703SD20-0055 UNINTERRUPT. PWR SUPPLY CABINET ATT	3.000 EA	_____	_____	_____	_____
2940	703	703SD20-0060 PEDESTRIAN SIGNAL HEAD SP-8	4.000 EA	_____	_____	_____	_____
2950	ATTD	703SX20-0003 DETECTOR VIDEO DETECTION CAMERA (360 DEG., FISHEYE)	6.000 EA	_____	_____	_____	_____
2960	ATTD	703SX20-0003 DETECTOR VIDEO DETECTION CAMERA (TRADITIONAL ADVANCED TYPE III)	5.000 EA	_____	_____	_____	_____
2970	ATTD	703SX20-0003 DETECTOR VIDEO DETECTION SYSTEM TY. III	3.000 EA	_____	_____	_____	_____
2980	ATTD	703SX20-0004 HANGER ASSEMBLY MAST ARM HANGER ASSEMBLY, SM-3 (INLINE)	22.000 EA	_____	_____	_____	_____
2990	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	12,605.000 LF	_____	_____	_____	_____
3000	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	220.000 LF	_____	_____	_____	_____
3010	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	1,625.000 LF	_____	_____	_____	_____
3020	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	775.000 LF	_____	_____	_____	_____
3030	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	14,335.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501

Order No.: N83

Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3040	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	1,150.000 LF	_____	_____	_____	_____
3050	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	430.000 LF	_____	_____	_____	_____
3060	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	25.000 LF	_____	_____	_____	_____
3070	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	396.000 EA	_____	_____	_____	_____
3080	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	16.000 EA	_____	_____	_____	_____
3090	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	7.000 EA	_____	_____	_____	_____
3100	704	704SD20-0108 PVMT MSG. MARK. "ONLY" TY B, CL II, 8'	1.000 EA	_____	_____	_____	_____
3110	ATTD	705SX20-0001 LUMINAIRE (90 W, LED)	7.000 EA	_____	_____	_____	_____
3120	801	801SD20-0002 ITS CONTROLLER CABINET POLE MOUNTED	1.000 EA	_____	_____	_____	_____
3130	ATTD	801SX20-0001 COMMUNICATION EQUIP. 5.8 GHZ WIRELESS BROADBAND RADIO DUAL	2.000 EA	_____	_____	_____	_____
3140	ATTD	801SX20-0001 COMMUNICATION EQUIP. INSTALL FIELD ROUTER	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119384C01B Oversight/State Project No.: U000-118-311, C501
 Order No.: N83 Federal Project No.: NHPP-5118(346)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
3150	ATTD	801SX20-0001 COMMUNICATION EQUIP. PRE-TERMINATED FIBER PATCH PANEL (COMPACT)	4.000 EA	_____	_____	_____	_____
3160	ATTD	801SX20-0002 COMMUNICATION EQUIP. REMOVE EXISTING CCTV LOCATION	LUMP SUM	LUMP SUM	_____	_____	_____
3170	802	802SD20-0001 UNINTERRUPTIBLE POWER SUPPLY ITS-CC	1.000 EA	_____	_____	_____	_____
3180	803	803SD20-0001 CCTV CAMERA DIGITAL	1.000 EA	_____	_____	_____	_____
3190	803	803SD20-0009 CCTV CAMERA POLE 45'	1.000 EA	_____	_____	_____	_____
3200	808	808SD20-0004 FIBER OPTIC DROP CABLE 12 STRAND	2,065.000 LF	_____	_____	_____	_____
3210	812	812SD20-0002 BORED ITS CONDUIT HDPE 2"	470.000 LF	_____	_____	_____	_____
3220	812	812SD20-0007 ITS CONDUIT HDPE 2"	1,290.000 LF	_____	_____	_____	_____
3230	ATTD	812SX20-0008 ITS CONDUIT HDPE 3"	175.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____