

Schedule of Items

Proposal ID: C0000117111B62      Oversight/State Project No.: 0643-098-855, B662  
 Order No.: A52      Federal Project No.: STP-098-1(057)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0001 REGULAR EXCAVATION	165.000 CY				
0030	303	303SD20-0019 EROSION CONTROL MULCH	472.000 SY				
0040	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA				
0050	303	303SD20-0029 SILTATION CONTROL EXCAVATION	12.700 CY				
0060	303	303SD20-0033 TEMP. SILT FENCE TYPE B	381.000 LF				
0070	ATTD	303SX20-0005 ROCK EXCAVATION	50.000 CY				
0080	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	270.000 TON				
0090	309	309SD20-0001 AGGR. MATL. NO. 1	52.000 TON				
0100	315	315SD20-0001 ASPHALT CONCRETE TY. SM-12.5A CONST	57.000 TON				
0110	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	50.000 LF				
0120	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	570.000 CY				
0130	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	570.000 TON				

Schedule of Items

Proposal ID: C0000117111B62      Oversight/State Project No.: 0643-098-855, B662  
 Order No.: A52      Federal Project No.: STP-098-1(057)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	60.000 SY	_____	_____	_____	_____
0150	401	401SD20-0005 PIPE UNDERDRAIN 6" CONST.	50.000 LF	_____	_____	_____	_____
0160	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0170	ATTD	402SX20-0002 TEMP SUPPORT OF EXCAVATION TEMPORARY SUPPORT OF EXCAVATION	LUMP SUM	LUMP SUM	_____	_____	_____
0180	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	161.000 CY	_____	_____	_____	_____
0190	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	11,540.000 LB	_____	_____	_____	_____
0200	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	7,690.000 LB	_____	_____	_____	_____
0210	ATTD	410SX20-0007 BRIDGE SUPERSTRUCTURE PRECAST CONCRETE SLABS 3.375' X 21" X 31'	LUMP SUM	LUMP SUM	_____	_____	_____
0220	ATTD	410SX20-0014 BRIDGE INCIDENTALS CONSTRUCTION ACCESS	LUMP SUM	LUMP SUM	_____	_____	_____
0230	ATTD	413SX20-0002 DISM.& REM. EX. STR. VA. STR. NO. 6275	LUMP SUM	LUMP SUM	_____	_____	_____
0240	414	414SD20-0012 DRY RIPRAP CL.I 26"	63.000 TON	_____	_____	_____	_____
0250	414	414SD20-0014 DRY RIPRAP CL.II 24"	380.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117111B62      Oversight/State Project No.: 0643-098-855, B662  
 Order No.: A52      Federal Project No.: STP-098-1(057)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T	70.000 SY	_____	_____	_____	_____
0270	429	429SD20-0004 WATERPROOFING MEMBRANE TYPE III	26.000 SY	_____	_____	_____	_____
0280	505	505SD20-0074 GUARDRAIL, THRIE BEAM	231.000 LF	_____	_____	_____	_____
0290	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	365.000 LF	_____	_____	_____	_____
0300	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	31.000 SY	_____	_____	_____	_____
0310	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC (STRUCTURE NO. 6275)	LUMP SUM	LUMP SUM	_____	_____	_____
0320	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0330	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
0340	602	602SD20-0002 TOPSOIL CLASS A	4.000 CY	_____	_____	_____	_____
0350	602	602SD20-0004 TOPSOIL CLASS B	4.000 CY	_____	_____	_____	_____
0360	603	603SD20-0002 TEMPORARY SEED	150.000 LB	_____	_____	_____	_____
0370	603	603SD20-0003 REGULAR SEED	21.000 LB	_____	_____	_____	_____
0380	603	603SD20-0004 OVERSEEDING	17.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117111B62      Oversight/State Project No.: 0643-098-855, B662  
 Order No.: A52      Federal Project No.: STP-098-1(057)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	603	603SD20-0005 LEGUME SEED	1.000 LB	_____	_____	_____	_____
0400	603	603SD20-0006 LEGUME OVERSEEDING	1.000 LB	_____	_____	_____	_____
0410	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	424.000 SY	_____	_____	_____	_____
0420	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	5,022.000 SY	_____	_____	_____	_____
0430	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	108.000 LF	_____	_____	_____	_____
0440	603	603SD20-0014 FERTILIZER NITROGEN - N	28.000 LB	_____	_____	_____	_____
0450	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	25.000 LB	_____	_____	_____	_____
0460	603	603SD20-0016 FERTILIZER POTASSIUM - K	25.000 LB	_____	_____	_____	_____
0470	603	603SD20-0017 LIME	2.350 TON	_____	_____	_____	_____
0480	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	235.000 SY	_____	_____	_____	_____
0490	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	197.000 LF	_____	_____	_____	_____
0500	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	15.000 EA	_____	_____	_____	_____
0510	701	701SD20-0001 SIGN PANEL	105.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000117111B62

Oversight/State Project No.: 0643-098-855, B662

Order No.: A52

Federal Project No.: STP-098-1(057)

Contractor: \_\_\_\_\_

Section: 0001

Total: \_\_\_\_\_

Total Bid: \_\_\_\_\_