

Schedule of Items

Proposal ID: C0000118431B20      Oversight/State Project No.: 0749-056-752, B620  
 Order No.: A67      Federal Project No.: BROS-056-7(031)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0020	303	303SD20-0001 REGULAR EXCAVATION	71.000 CY				
0030	303	303SD20-0007 BORROW EXCAVATION	468.000 CY				
0040	303	303SD20-0023 CHECK DAM ROCK TY. II	11.000 EA				
0050	303	303SD20-0028 DEWATERING BASIN EC-8	4.000 EA				
0060	303	303SD20-0029 SILTATION CONTROL EXCAVATION	110.000 CY				
0070	303	303SD20-0034 TEMP. SILT FENCE TYPE A	424.000 LF				
0080	ATTD	303SX20-0022 EROSION CONTROL TURBIDITY CURTAIN (IMPERVIOUS)	107.000 LF				
0090	308	308SD20-0011 AGGR. BASE MATL. TY. I NO. 21A	398.000 TON				
0100	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	21.000 TON				
0110	315	315SD20-0008 ASPHALT CONCRETE TY. SM-9.5D CONST	34.000 TON				
0120	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	49.000 TON				
0130	ATTD	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	120.000 LF				

Schedule of Items

Proposal ID: C0000118431B20      Oversight/State Project No.: 0749-056-752, B620  
 Order No.: A67      Federal Project No.: BROS-056-7(031)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	792.000 CY	_____	_____	_____	_____
0150	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	635.000 TON	_____	_____	_____	_____
0160	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	37.000 SY	_____	_____	_____	_____
0170	401	401SD20-0007 COFFERDAM	2.000 EA	_____	_____	_____	_____
0180	ATTD	401SX20-0011 BRIDGE SUBSTRUCTURE TEMPORARY SHORING	LUMP SUM	LUMP SUM	_____	_____	_____
0190	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	206.000 CY	_____	_____	_____	_____
0200	ATTD	404SP20-0002 SHEAR KEYS	37.000 CF	_____	_____	_____	_____
0210	405	405SD20-0154 PREST.CONC.BOX BEAM 3' X 2'3"X(+65'-70')	3.000 EA	_____	_____	_____	_____
0220	405	405SD20-0188 PREST.CONC.BOX BEAM 4' X 2'3"X(+65'-70')	2.000 EA	_____	_____	_____	_____
0230	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	8,130.000 LB	_____	_____	_____	_____
0240	406	406SD20-0008 CR REINF. STEEL CL. I SUBSTRUCT. CONST.	4,700.000 LB	_____	_____	_____	_____
0250	ATTD	410SX20-0007 BRIDGE SUPERSTRUCTURE TEMPORARY DETOUR BRIDGE	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000118431B20      Oversight/State Project No.: 0749-056-752, B620  
 Order No.: A67      Federal Project No.: BROS-056-7(031)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	413	413SX20-0002 DISM.& REM. EX. STR. STR. NO. 6120	LUMP SUM	LUMP SUM			
0270	413	413SX20-0003 ENV.& WORKER PROTECT. STR. NO. 6120	LUMP SUM	LUMP SUM			
0280	413	413SX20-0004 MATERIAL DISPOSAL STR. NO. 6120 TYPE B	LUMP SUM	LUMP SUM			
0290	414	414SD20-0057 DRY RIPRAP CL.II 38"	494.000 TON				
0300	505	505SD20-0074 GUARDRAIL, THRIE BEAM	150.000 LF				
0310	507	507SD20-0001 FENCE FE-W1	90.000 LF				
0320	507	507SD20-0015 FENCE FE-B	10.000 LF				
0330	507	507SX20-0013 FENCE WOODEN (MATCH IN KIND)	90.000 LF				
0340	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	240.000 SY				
0350	ATTD	510SX20-0016 REMOVE EXIST. FENCE EXISTING FENCE	100.000 LF				
0360	511	511SD20-0001 ALLAYING DUST	150.000 HR				
0370	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA				
0380	512	512SD20-0014 TEMPORARY SIGN	295.000 SF				

Schedule of Items

Proposal ID: C0000118431B20      Oversight/State Project No.: 0749-056-752, B620  
 Order No.: A67      Federal Project No.: BROS-056-7(031)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	1,080.000 DAY	_____	_____	_____	_____
0400	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	672.000 HR	_____	_____	_____	_____
0410	512	512SD20-0029 WARNING LIGHT TY. B	480.000 DAY	_____	_____	_____	_____
0420	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	40.000 LF	_____	_____	_____	_____
0430	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0440	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0450	603	603SD20-0002 TEMPORARY SEED	4.600 LB	_____	_____	_____	_____
0460	603	603SD20-0003 REGULAR SEED	38.000 LB	_____	_____	_____	_____
0470	603	603SD20-0004 OVERSEEDING	31.000 LB	_____	_____	_____	_____
0480	603	603SD20-0005 LEGUME SEED	3.000 LB	_____	_____	_____	_____
0490	603	603SD20-0006 LEGUME OVERSEEDING	2.000 LB	_____	_____	_____	_____
0500	603	603SD20-0007 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	97.000 SY	_____	_____	_____	_____
0510	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	864.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000118431B20      Oversight/State Project No.: 0749-056-752, B620  
 Order No.: A67      Federal Project No.: BROS-056-7(031)

Contractor: \_\_\_\_\_

SECTION: 0001      REGULAR BID ITEMS

Cat Alt Set ID:      Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0520	603	603SD20-0014 FERTILIZER NITROGEN - N	10.000 LB	_____	_____	_____	_____
0530	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	13.000 LB	_____	_____	_____	_____
0540	603	603SD20-0016 FERTILIZER POTASSIUM - K	7.000 LB	_____	_____	_____	_____
0550	603	603SD20-0017 LIME	0.470 TON	_____	_____	_____	_____
0560	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	163.000 SY	_____	_____	_____	_____
0570	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	72.000 SY	_____	_____	_____	_____
0580	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	6.000 EA	_____	_____	_____	_____
0590	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	3.000 EA	_____	_____	_____	_____
0600	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	84.000 LF	_____	_____	_____	_____
0610	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	7.000 EA	_____	_____	_____	_____
0620	701	701SD20-0001 SIGN PANEL	17.000 SF	_____	_____	_____	_____
0630	702	702SD20-0003 ROAD EDGE DEL. ED-2	12.000 EA	_____	_____	_____	_____
<b>Section: 0001</b>				<b>Total:</b>		_____	
				<b>Total Bid:</b>		_____	