

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 CONST REC DOCS SWM FACILITY 2 SWM FACILITIES	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	23.000 EA				
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	302	302SD20-0013 ENDWALL EW-12	23.000 EA				
0060	302	302SD20-0018 12" PIPE	36.000 LF				
0070	302	302SD20-0023 15" PIPE	165.000 LF				
0080	302	302SD20-0027 15" STORM SEWER PIPE	1,208.000 LF				
0090	302	302SD20-0028 18" PIPE	73.000 LF				
0100	302	302SD20-0030 18" CONC. PIPE	43.000 LF				
0110	302	302SD20-0037 24" PIPE	40.000 LF				
0120	302	302SD20-0039 24" CONC. PIPE	38.000 LF				
0130	302	302SD20-0041 24" STORM SEWER PIPE	123.000 LF				
0140	302	302SD20-0047 30" PIPE	78.000 LF				

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0132 23" X 14" ELLIPTICAL PIPE	18.000 LF	_____	_____	_____	_____
0160	302	302SD20-0197 12" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0170	302	302SD20-0198 15" END SECTION ES-1 OR 2	2.000 EA	_____	_____	_____	_____
0180	302	302SD20-0199 15" END SECTION ES-1	8.000 EA	_____	_____	_____	_____
0190	302	302SD20-0201 18" END SECTION ES-1	5.000 EA	_____	_____	_____	_____
0200	302	302SD20-0205 24" END SECTION ES-1	5.000 EA	_____	_____	_____	_____
0210	302	302SD20-0209 30" END SECTION ES-1	2.000 EA	_____	_____	_____	_____
0220	302	302SD20-0221 23" X 14" END SECTION ES-1A	2.000 EA	_____	_____	_____	_____
0230	302	302SD20-0311 DROP INLET DI-3B,L=4'	3.000 EA	_____	_____	_____	_____
0240	302	302SD20-0312 DROP INLET DI-3B,L=6'	5.000 EA	_____	_____	_____	_____
0250	302	302SD20-0313 DROP INLET DI-3B,L=8'	1.000 EA	_____	_____	_____	_____
0260	302	302SD20-0314 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
0270	302	302SD20-0315 DROP INLET DI-3B,L=12'	1.000 EA	_____	_____	_____	_____
0280	302	302SD20-0316 DROP INLET DI-3B,L=14'	1.000 EA	_____	_____	_____	_____
0290	302	302SD20-0446 DROP INLET DI-5	3.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0300	302	302SD20-0655 DROP INLET DI-13 TY.I	1.000 EA	_____	_____	_____	_____
0310	302	302SD20-0656 DROP INLET DI-13 TY.II	2.000 EA	_____	_____	_____	_____
0320	302	302SD20-0662 MANHOLE MH-1 OR 2	21.900 LF	_____	_____	_____	_____
0330	302	302SD20-0663 FRAME & COVER MH-1	4.000 EA	_____	_____	_____	_____
0340	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	12.600 LF	_____	_____	_____	_____
0350	303	303SD20-0001 REGULAR EXCAVATION	9,114.000 CY	_____	_____	_____	_____
0360	303	303SD20-0007 BORROW EXCAVATION	17,114.000 CY	_____	_____	_____	_____
0370	303	303SD20-0021 TEMPORARY DIVERSION DIKE	356.000 LF	_____	_____	_____	_____
0380	303	303SD20-0022 CHECK DAM ROCK TY. I	18.000 EA	_____	_____	_____	_____
0390	303	303SD20-0023 CHECK DAM ROCK TY. II	56.000 EA	_____	_____	_____	_____
0400	303	303SD20-0029 SILTATION CONTROL EXCAVATION	3,104.000 CY	_____	_____	_____	_____
0410	303	303SD20-0030 INLET PROTECTION TYPE A	6.000 EA	_____	_____	_____	_____
0420	303	303SD20-0031 INLET PROTECTION TYPE B	16.000 EA	_____	_____	_____	_____
0430	303	303SD20-0032 GEOTEXTILE FABRIC	473.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0440	303	303SD20-0033 TEMP. SILT FENCE TYPE B	872.000 LF	_____	_____	_____	_____
0450	303	303SD20-0034 TEMP. SILT FENCE TYPE A	8,874.000 LF	_____	_____	_____	_____
0460	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	2,339.000 CY	_____	_____	_____	_____
0470	307	307SD20-0004 CEM. STAB. AGGR. BASE. MATL. TY. I NO. 21A	1,506.000 TON	_____	_____	_____	_____
0480	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	4,374.000 TON	_____	_____	_____	_____
0490	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	93.000 TON	_____	_____	_____	_____
0500	309	309SD20-0001 AGGR. MATL. NO. 1	93.000 TON	_____	_____	_____	_____
0510	315	315SD20-0003 ASPHALT CONCRETE TY. SM-12.5E CONST	3,408.000 TON	_____	_____	_____	_____
0520	315	315SD20-0004 ASPHALT CONCRETE TY. IM-19.0A CONST	64.000 TON	_____	_____	_____	_____
0530	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	8,117.000 TON	_____	_____	_____	_____
0540	315	315SD20-0007 ASPHALT CONCRETE TY. SM-9.5A CONST	123.000 TON	_____	_____	_____	_____
0550	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	4,986.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0560	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	3,601.000 LF	_____	_____	_____	_____
0570	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	400.000 SY	_____	_____	_____	_____
0580	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	187.000 TON	_____	_____	_____	_____
0590	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	13,320.000 LF	_____	_____	_____	_____
0600	316	316SD20-0013 CONT.REINF.HYDR.CONC. PAVE. 11" REINFORCED W/6X6-W4XW4	369.000 SY	_____	_____	_____	_____
0610	404	404SD20-0017 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. MAINT.	40.000 CY	_____	_____	_____	_____
0620	406	406SD20-0011 CR REINF. STEEL CL. I SPR. STRUCT. MAINT.	3,080.000 LB	_____	_____	_____	_____
0630	ATTD	413SX20-0005 REM. PORT.OF EX.STR. CONCRETE MEDIAN (BRIDGE)	LUMP SUM	LUMP SUM	_____	_____	_____
0640	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	32.000 TON	_____	_____	_____	_____
0650	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	666.000 TON	_____	_____	_____	_____
0660	501	501SD20-0004 UNDERDRAIN UD-4	9,915.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	501	501SD20-0006 CROSSDRAIN CD-1	117.000 LF	_____	_____	_____	_____
0680	501	501SD20-0009 OUTLET PIPE	623.000 LF	_____	_____	_____	_____
0690	ATTD	501SX20-0001 UNDERDRAIN MODIFIED OUTLET PIPE 6"	70.000 LF	_____	_____	_____	_____
0700	ATTD	501SX20-0001 UNDERDRAIN MODIFIED UD- 4 6"	2,263.000 LF	_____	_____	_____	_____
0710	502	502SD20-0003 PAVED DITCH PG-2A	18.000 SY	_____	_____	_____	_____
0720	502	502SD20-0011 CURB, STD. CG-2	135.000 LF	_____	_____	_____	_____
0730	502	502SD20-0012 CURB, RADIAL CG-2	132.000 LF	_____	_____	_____	_____
0740	502	502SD20-0014 CURB, STD. CG-3	205.000 LF	_____	_____	_____	_____
0750	502	502SD20-0015 CURB, RADIAL CG-3	559.000 LF	_____	_____	_____	_____
0760	502	502SD20-0020 CURB, ASPHALT MC-3B	230.000 LF	_____	_____	_____	_____
0770	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	848.000 LF	_____	_____	_____	_____
0780	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	614.000 LF	_____	_____	_____	_____
0790	502	502SD20-0053 MEDIAN STRIP MS-1	383.000 SY	_____	_____	_____	_____
0800	502	502SD20-0056 MEDIAN STRIP MS-1A	1,098.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0810	502	502SD20-0058 MEDIAN STRIP MS-2	1,120.000 LF	_____	_____	_____	_____
0820	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	12.600 CY	_____	_____	_____	_____
0830	505	505SD20-0011 GUARDRAIL GR-MGS1	1,718.000 LF	_____	_____	_____	_____
0840	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	166.000 LF	_____	_____	_____	_____
0850	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	72.000 LF	_____	_____	_____	_____
0860	505	505SD20-0016 RADIAL GUARDRAIL GR- MGS1, 9' POST	200.000 LF	_____	_____	_____	_____
0870	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	5.000 EA	_____	_____	_____	_____
0880	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	7.000 EA	_____	_____	_____	_____
0890	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	5.000 EA	_____	_____	_____	_____
0900	505	505SD20-0053 FIXED OBJECT ATTACH. GR- FOA-2 TY. I	2.000 EA	_____	_____	_____	_____
0910	505	505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II	2.000 EA	_____	_____	_____	_____
0920	505	505SD20-0066 CABLE BARRICADE CR-1	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	2,040.000 LF	_____	_____	_____	_____
0940	507	507SD20-0001 FENCE FE-W1	517.000 LF	_____	_____	_____	_____
0950	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	2.000 EA	_____	_____	_____	_____
0960	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	2.000 EA	_____	_____	_____	_____
0970	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	700.000 LF	_____	_____	_____	_____
0980	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	9,452.000 SY	_____	_____	_____	_____
0990	509	509SD20-0001 FLOWABLE BACKFILL	83.000 CY	_____	_____	_____	_____
1000	510	510SX20-0016 REMOVE EXIST. FENCE EXISTING FENCE	534.000 LF	_____	_____	_____	_____
1010	510	510SX20-0028 REMOVE EXIST. ENDWALL NS REMOVE EXIST. ENDWALL	8.000 EA	_____	_____	_____	_____
1020	510	510SX20-0038 REMOVE EXIST. CONCRETE MEDIAN (ROADWAY)	660.000 SY	_____	_____	_____	_____
1030	510	510SX20-0039 REMOVE EXIST. PIPE	183.000 LF	_____	_____	_____	_____
1040	511	511SD20-0001 ALLAYING DUST	1,095.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1050	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL-3, >=40 MPH	2.000 EA	_____	_____	_____	_____
1060	512	512SD20-0013 TYPE 3 BARRICADE 8'	4.000 EA	_____	_____	_____	_____
1070	512	512SD20-0014 TEMPORARY SIGN	4,091.000 SF	_____	_____	_____	_____
1080	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	4,380.000 HR	_____	_____	_____	_____
1090	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	155,338.000 DAY	_____	_____	_____	_____
1100	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	35,040.000 HR	_____	_____	_____	_____
1110	512	512SD20-0026 ELECTRONIC ARROW BOARD	4,380.000 HR	_____	_____	_____	_____
1120	512	512SD20-0027 FLAGGER SERVICE	2,850.000 HR	_____	_____	_____	_____
1130	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	2,150.000 LF	_____	_____	_____	_____
1140	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	2,500.000 LF	_____	_____	_____	_____
1150	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	110,987.000 LF	_____	_____	_____	_____
1160	512	512SD20-0050 TEMP. PVMT MRKG TY. A, 24"	1,245.000 LF	_____	_____	_____	_____
1170	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	48.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	512	512SX20-0005 TEMP. PVMT MRKG TY. D, CL III, 4" WITH CONTRAST	14,077.000 LF	_____	_____	_____	_____
1190	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
1200	ATTD	514SX20-0001 FIELD OFFICE TYPE 1 MODIFIED	23.000 MO	_____	_____	_____	_____
1210	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	21,146.000 SY	_____	_____	_____	_____
1220	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____
1230	ATTD	523SP20-0002 STORM WATER MANAGEMENT LOW PERMEABILITY LINER	1,695.000 SY	_____	_____	_____	_____
1240	602	602SD20-0001 TOPSOIL CLASS A 2"	8.560 ACRE	_____	_____	_____	_____
1250	ATTD	602SX20-0006 TOPSOIL SWM LINER COVER MATERIAL	288.000 CY	_____	_____	_____	_____
1260	603	603SD20-0002 TEMPORARY SEED	856.000 LB	_____	_____	_____	_____
1270	603	603SD20-0003 REGULAR SEED	2,381.000 LB	_____	_____	_____	_____
1280	603	603SD20-0004 OVERSEEDING	1,840.000 LB	_____	_____	_____	_____
1290	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	38,297.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1300	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	54,922.000 SY	_____	_____	_____	_____
1310	603	603SD20-0014 FERTILIZER NITROGEN - N	856.000 LB	_____	_____	_____	_____
1320	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	599.000 LB	_____	_____	_____	_____
1330	603	603SD20-0016 FERTILIZER POTASSIUM - K	599.000 LB	_____	_____	_____	_____
1340	603	603SD20-0017 LIME	47.000 TON	_____	_____	_____	_____
1350	ATTD	605SX20-0013 LANDSCAPE PERMANENT VEGETATIVE COVER	LUMP SUM	LUMP SUM	_____	_____	_____
1360	605	605SX20-0018 PLANT OR TREE RED CEDAR	5.000 EA	_____	_____	_____	_____
1370	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	2,485.000 SY	_____	_____	_____	_____
1380	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	155.000 SY	_____	_____	_____	_____
1390	606	606SD20-0006 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 2	147.000 SY	_____	_____	_____	_____
1400	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	15.720 SY	_____	_____	_____	_____
1410	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	71.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1420	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	7.000 EA	_____	_____	_____	_____
1430	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	2.000 EA	_____	_____	_____	_____
1440	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	26.000 EA	_____	_____	_____	_____
1450	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	450.000 LF	_____	_____	_____	_____
1460	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	115.000 LF	_____	_____	_____	_____
1470	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	395.000 LF	_____	_____	_____	_____
1480	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	22.000 EA	_____	_____	_____	_____
1490	700	700SD20-0041 CONC. FOUND. STP-1, TY. D	62.000 EA	_____	_____	_____	_____
1500	700	700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE	11.000 CY	_____	_____	_____	_____
1510	700	700SD20-0144 8 CONDUCTOR CABLE	3,725.000 LF	_____	_____	_____	_____
1520	700	700SD20-0148 8 CONDUCTOR CABLE EGC	1,425.000 LF	_____	_____	_____	_____
1530	700	700SD20-0149 CONC. FOUND. LF-1, TY. A	11.000 EA	_____	_____	_____	_____
1540	700	700SD20-0157 LIGHTING POLE LP-2 TYPE E	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1550	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
1560	700	700SD20-0178 JUNCTION BOX JB-S2	7.000 EA	_____	_____	_____	_____
1570	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	4.000 EA	_____	_____	_____	_____
1580	700	700SD20-0192 BORED CONDUIT 3"	250.000 LF	_____	_____	_____	_____
1590	700	700SD20-0194 CONDUIT PVC 2"	1,545.000 LF	_____	_____	_____	_____
1600	700	700SD20-0197 TRENCH EXCAVATION ECI-1	1,545.000 LF	_____	_____	_____	_____
1610	700	700SD20-0200 SIGN POST STP-2, 4", 8 GAUGE	170.000 LF	_____	_____	_____	_____
1620	700	700SD20-0201 CONCRETE FOUNDATION STP-2, TYPE A	3.000 EA	_____	_____	_____	_____
1630	700	700SD20-0207 CONCRETE FOUNDATION STP-2, TYPE G	3.000 EA	_____	_____	_____	_____
1640	700	700SD20-0208 CONCRETE FOUNDATION STP-2, TYPE H	2.000 EA	_____	_____	_____	_____
1650	700	700SD20-0209 CONCRETE FOUNDATION STP-2, TYPE I	1.000 EA	_____	_____	_____	_____
1660	700	700SD20-0214 CONCRETE FOUNDATION STP-2, TYPE N	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01 Oversight/State Project No.: 0017-030-879, C501
 Order No.: A70 Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1670	ATTD	700SX20-0003 SIGN STRUCTURE, OVERHEAD CANT. OVERHEAD CANT.	1.000 EA	_____	_____	_____	_____
1680	ATTD	700SX20-0014 LIGHTING ELECTRICAL SERVICE SE-5 (RDO)	LUMP SUM	LUMP SUM	_____	_____	_____
1690	ATTD	700SX20-0021 TRAFFIC SIGN RELOCATE EXISTING 1 POST GROUND MOUNT SIGHT STRUCTURE ST-1	1.000 EA	_____	_____	_____	_____
1700	701	701SD20-0001 SIGN PANEL	1,568.000 SF	_____	_____	_____	_____
1710	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	18,100.000 LF	_____	_____	_____	_____
1720	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	1,400.000 LF	_____	_____	_____	_____
1730	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	300.000 LF	_____	_____	_____	_____
1740	704	704SD20-0009 TYPE B CLASS I PVMT LINE MRKG 12"	300.000 LF	_____	_____	_____	_____
1750	704	704SD20-0010 TYPE B CLASS I PVMT LINE MRKG 24"	200.000 LF	_____	_____	_____	_____
1760	704	704SD20-0030 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 4"	2,000.000 LF	_____	_____	_____	_____
1770	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	170.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1780	704	704SD20-0036 PVMT MSG. MARK. "ONLY" TY B, CL II, 6'	3.000 EA	_____	_____	_____	_____
1790	704	704SD20-0045 PVMT SYMB MRKG THRU ARROW TY B, CL II	1.000 EA	_____	_____	_____	_____
1800	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	13.000 EA	_____	_____	_____	_____
1810	704	704SD20-0051 DBL TURN ARR. THRU/LT OR RT TY B, CL II	1.000 EA	_____	_____	_____	_____
1820	704	704SD20-0066 SYMB MRKG FISH HOOK, LFT TY B CL II	2.000 EA	_____	_____	_____	_____
1830	704	704SD20-0075 SYM MRKG FISH HOOK THRU/RGHT TY B CL II	2.000 EA	_____	_____	_____	_____
1840	704	704SD20-0085 PVMT SYMB MRKG YIELD 2' X 3' TY A	68.000 EA	_____	_____	_____	_____
1850	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	19.000 EA	_____	_____	_____	_____
1860	704	704SD20-0106 PVMT MSG. MARK. "ONLY" TY A, 8'	19.000 EA	_____	_____	_____	_____
1870	704	704SD20-0125 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 8"	200.000 LF	_____	_____	_____	_____
1880	ATTD	704SX20-0002 PAVEMENT MARKING PVMT. MSG. MARK. "WEST" TY. B, CL. II	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120748C01

Oversight/State Project No.: 0017-030-879, C501

Order No.: A70

Federal Project No.: HSIP-030-7(116)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1890	ATTD	704SX20-0002 PAVEMENT MARKING PVMT. MSG. MARK. "YIELD" TY. A, 8"	12.000 EA	_____	_____	_____	_____
1900	ATTD	704SX20-0002 PAVEMENT MARKING PVMT. MSG. MARK. SHIELD TY. B, CL II	1.000 EA	_____	_____	_____	_____
1910	ATTD	704SX20-0002 PAVEMENT MARKING PVMT. SYMB. MRKG. SI TURN ARR. U-TURN ARR. U-TURN TY. B, CL II	3.000 EA	_____	_____	_____	_____
1920	ATTD	704SX20-0004 PAVEMENT MARKING FISH HOOK THR TY B, CL II	4.000 EA	_____	_____	_____	_____
1930	ATTD	704SX20-0004 PAVEMENT MARKING PVMT. SYMB MRKG FISH HOOK, THRU TY A	4.000 EA	_____	_____	_____	_____
1940	ATTD	704SX20-0005 PAVE. MESSAGE MARKING PVMT. MSG. MARK. "TO" TY. B, CL II	1.000 EA	_____	_____	_____	_____
1950	ATTD	704SX20-0005 PAVE. MESSAGE MARKING PVMT. MSG. MARK. "YIELD" TY. B, CL II	10.000 EA	_____	_____	_____	_____
1960	705	705SD20-0003 CONTROL CENTER CCW-1 TYPE C	1.000 EA	_____	_____	_____	_____
1970	ATTD	705SX20-0001 LUMINAIRE 133W LED POLE- MOUNT	11.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	
				Total Bid:		_____	