

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	12.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	ATTD	302SD20-0002 BEDDING MATL. AGGR. NO. 57	176.900 TON				
0050	302	302SD20-0004 CONCRETE CLASS A4 BOX CULVERT	16.900 CY				
0060	302, 406	302SD20-0005 REINF. STEEL	1,467.000 LB				
0070	302	302SD20-0030 18" CONC. PIPE	288.000 LF				
0080	302	302SD20-0032 18" STORM SEWER PIPE	1,028.000 LF				
0090	302	302SD20-0041 24" STORM SEWER PIPE	24.000 LF				
0100	302	302SD20-0200 18" END SECTION ES-1 OR 2	2.000 EA				
0110	302	302SD20-0239 DROP INLET DI-2A	1.000 EA				
0120	302	302SD20-0242 DROP INLET DI-2B,L=6'	2.000 EA				
0130	302	302SD20-0243 DROP INLET DI-2B,L=8'	2.000 EA				
0140	302	302SD20-0309 DROP INLET DI-3A	2.000 EA				

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501

Order No.: A66

Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0312 DROP INLET DI-3B,L=6'	3.000 EA	_____	_____	_____	_____
0160	302	302SD20-0314 DROP INLET DI-3B,L=10'	2.000 EA	_____	_____	_____	_____
0170	302	302SD20-0321 DROP INLET DI-3BB,L=6'	1.000 EA	_____	_____	_____	_____
0180	302	302SD20-0329 DROP INLET DI-3C,L=6'	1.000 EA	_____	_____	_____	_____
0190	302	302SD20-0446 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0200	302	302SD20-0662 MANHOLE MH-1 OR 2	28.500 LF	_____	_____	_____	_____
0210	302	302SD20-0663 FRAME & COVER MH-1	6.000 EA	_____	_____	_____	_____
0220	303	303SD20-0001 REGULAR EXCAVATION	2,341.000 CY	_____	_____	_____	_____
0230	303	303SD20-0007 BORROW EXCAVATION	2,391.000 CY	_____	_____	_____	_____
0240	303	303SD20-0013 GEOTEXTILE EMBANKMENT STAB.	130.000 SY	_____	_____	_____	_____
0250	303	303SD20-0017 MINOR STR. EXCAV. BOX CULVERT	8.900 CY	_____	_____	_____	_____
0260	303	303SD20-0018 SLOPE DRAIN	1.000 EA	_____	_____	_____	_____
0270	303	303SD20-0022 CHECK DAM ROCK TY. I	19.000 EA	_____	_____	_____	_____
0280	303	303SD20-0023 CHECK DAM ROCK TY. II	19.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501

Order No.: A66

Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	303	303SD20-0028 DEWATERING BASIN EC-8	1.000 EA	_____	_____	_____	_____
0300	303	303SD20-0029 SILTATION CONTROL EXCAVATION	440.000 CY	_____	_____	_____	_____
0310	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0320	303	303SD20-0031 INLET PROTECTION TYPE B	16.000 EA	_____	_____	_____	_____
0330	303	303SD20-0032 GEOTEXTILE FABRIC	229.000 SY	_____	_____	_____	_____
0340	303	303SD20-0033 TEMP. SILT FENCE TYPE B	630.000 LF	_____	_____	_____	_____
0350	303	303SD20-0034 TEMP. SILT FENCE TYPE A	566.000 LF	_____	_____	_____	_____
0360	ATTD	303SX20-0008 GEOTEXTILE GEOSYNTHETIC REINFORCEMENT	114.000 SY	_____	_____	_____	_____
0370	ATTD	303SX20-0013 UTILITY TEST PIT ASPHALT CONCRETE	5.000 EA	_____	_____	_____	_____
0380	ATTD	303SX20-0017 REINFORCED SOIL SLOPE TY. A 1H:2V	1,955.000 SF	_____	_____	_____	_____
0390	305	305SD20-0010 AGGR. MATL. NO. 1	909.000 TON	_____	_____	_____	_____
0400	ATTD	305SP20-0006 MANUAL SHOULDERS RESTORATION	35.000 LF	_____	_____	_____	_____
0410	308	308SD20-0001 AGGR. MATL. NO. 1	3.800 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	308	308SD20-0006 AGGR. MATL. NO. 21A OR 21B	98.600 TON	_____	_____	_____	_____
0430	308	308SD20-0007 AGGR. MATL. NO. 21B	91.000 TON	_____	_____	_____	_____
0440	309	309SD20-0010 AGGR. BASE MATL. TY. I NO. 21B	730.000 TON	_____	_____	_____	_____
0450	315	315SD20-0005 ASPHALT CONCRETE TY. IM-19.0D CONST	169.000 TON	_____	_____	_____	_____
0460	315	315SD20-0008 ASPHALT CONCRETE TY. SM-9.5D CONST	1,141.000 TON	_____	_____	_____	_____
0470	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	444.000 TON	_____	_____	_____	_____
0480	315	315SX20-0011 SAW-CUT ASPH CONC FULL DEPTH	2,286.000 LF	_____	_____	_____	_____
0490	316	316SX20-0010 SAW-CUT HYDR.CEM.CONC.PAVE. .	14.000 LF	_____	_____	_____	_____
0500	ATTD	402SX20-0002 TEMP SUPPORT OF EXCAVATION TEMPORARY SHORING	LUMP SUM	LUMP SUM	_____	_____	_____
0510	403	403SD20-0005 STEEL PILES 10"	423.000 LF	_____	_____	_____	_____
0520	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	133.000 TON	_____	_____	_____	_____
0530	414	414SD20-0007 DRY RIPRAP CL. AI	81.000 SY	_____	_____	_____	_____
0540	502	502SD20-0011 CURB, STD. CG-2	631.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	502	502SD20-0012 CURB, RADIAL CG-2	292.000 LF	_____	_____	_____	_____
0560	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	428.000 LF	_____	_____	_____	_____
0570	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	176.000 LF	_____	_____	_____	_____
0580	502	502SX20-0008 COMB. CURB & GUTTER .	76.000 LF	_____	_____	_____	_____
0590	503	503SD20-0002 R/W MONUMENT RM-2	12.000 EA	_____	_____	_____	_____
0600	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	12.100 CY	_____	_____	_____	_____
0610	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	16.000 SY	_____	_____	_____	_____
0620	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	385.000 SY	_____	_____	_____	_____
0630	504	504SD20-0014 HANDRAIL HR-1 TYPE II	115.000 LF	_____	_____	_____	_____
0640	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	1.000 EA	_____	_____	_____	_____
0650	505	505SD20-0011 GUARDRAIL GR-MGS1	307.000 LF	_____	_____	_____	_____
0660	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	13.000 LF	_____	_____	_____	_____
0670	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	74.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0680	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	1.000 EA	_____	_____	_____	_____
0690	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	1.000 EA	_____	_____	_____	_____
0700	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	362.000 LF	_____	_____	_____	_____
0710	506	506SD20-0002 RETAINING WALL RW-3	27.000 CY	_____	_____	_____	_____
0720	506	506SD20-0007 RETAINING WALL EXCAVATION	76.000 CY	_____	_____	_____	_____
0730	507	507SD20-0027 HIGH VISIBILITY FENCE, 4 FEET	294.000 LF	_____	_____	_____	_____
0740	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	995.000 SY	_____	_____	_____	_____
0750	509	509SD20-0001 FLOWABLE BACKFILL	15.600 CY	_____	_____	_____	_____
0760	510	510SD20-0038 ADJUST EXIST. VALVE & BOX	2.000 EA	_____	_____	_____	_____
0770	510	510SX20-0040 REMOVE EXIST. MAST ARM	1.000 EA	_____	_____	_____	_____
0780	511	511SD20-0001 ALLAYING DUST	730.000 HR	_____	_____	_____	_____
0790	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	330.000 LF	_____	_____	_____	_____
0800	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0810	512	512SD20-0013 TYPE 3 BARRICADE 8'	14.000 EA	_____	_____	_____	_____
0820	512	512SD20-0014 TEMPORARY SIGN	371.000 SF	_____	_____	_____	_____
0830	512	512SD20-0015 AGGREGATE MATERIAL NO. 25 OR 26	81.000 TON	_____	_____	_____	_____
0840	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	2,544.000 HR	_____	_____	_____	_____
0850	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	21,188.000 DAY	_____	_____	_____	_____
0860	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	6,048.000 HR	_____	_____	_____	_____
0870	512	512SD20-0027 FLAGGER SERVICE	600.000 HR	_____	_____	_____	_____
0880	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	142.000 LF	_____	_____	_____	_____
0890	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	19,787.000 LF	_____	_____	_____	_____
0900	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	285.000 SF	_____	_____	_____	_____
0910	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	730.000 DAY	_____	_____	_____	_____
0920	ATTD	512SX20-0040 POLICE PATROL UNIFORMED FLAGGERS	100.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	512	512SX20-0050 TEMP. TRAFFIC CONTROL SIGNAL INT. 1	LUMP SUM	LUMP SUM			
0940	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
0950	514	514SD20-0003 FIELD OFFICE TY.III	14.000 MO				
0960	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	7,906.000 SY				
0970	515	515SD20-0015 FLEXIBLE PAVEMENT PLANING ABOVE 4"	222.000 SY				
0980	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0990	520	520SD20-0002 3/4" WATER SERVICE LINE	165.000 LF				
1000	520	520SD20-0003 1" WATER SERVICE LINE	71.000 LF				
1010	520	520SD20-0006 2" WATER SERVICE LINE	12.000 LF				
1020	520	520SD20-0024 16" DI WATER MAIN	108.000 LF				
1030	520	520SD20-0041 16" BEND	6.000 EA				
1040	520	520SD20-0049 16" BRANCH	1.000 EA				
1050	520	520SD20-0057 16" PLUG OR CAP	1.000 EA				
1060	520	520SD20-0073 6" OFFSET EXIST.PIPE	11.000 LF				

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	520	520SD20-0096 16" GATE VALVE & BOX	1.000 EA	_____	_____	_____	_____
1080	520	520SD20-0167 5/8" WATER METER BOX & YOKE	2.000 EA	_____	_____	_____	_____
1090	520	520SX20-0008 SEWER UTILITY 16" SOLID SLEEVE	2.000 EA	_____	_____	_____	_____
1100	602	602SD20-0004 TOPSOIL CLASS B	532.000 CY	_____	_____	_____	_____
1110	603	603SD20-0002 TEMPORARY SEED	173.000 LB	_____	_____	_____	_____
1120	603	603SD20-0003 REGULAR SEED	288.000 LB	_____	_____	_____	_____
1130	603	603SD20-0004 OVERSEEDING	230.000 LB	_____	_____	_____	_____
1140	603	603SD20-0005 LEGUME SEED	14.000 LB	_____	_____	_____	_____
1150	603	603SD20-0006 LEGUME OVERSEEDING	12.000 LB	_____	_____	_____	_____
1160	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	5,990.000 SY	_____	_____	_____	_____
1170	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	6,546.000 SY	_____	_____	_____	_____
1180	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	239.000 LF	_____	_____	_____	_____
1190	603	603SD20-0014 FERTILIZER NITROGEN - N	115.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1200	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	81.000 LB	_____	_____	_____	_____
1210	603	603SD20-0016 FERTILIZER POTASSIUM - K	81.000 LB	_____	_____	_____	_____
1220	603	603SD20-0017 LIME	6.330 TON	_____	_____	_____	_____
1230	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	558.000 SY	_____	_____	_____	_____
1240	608	608SD20-0001 MOWING	20.000 HR	_____	_____	_____	_____
1250	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	16.000 LF	_____	_____	_____	_____
1260	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	44.000 LF	_____	_____	_____	_____
1270	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	10.000 LF	_____	_____	_____	_____
1280	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	3.000 EA	_____	_____	_____	_____
1290	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	4.000 EA	_____	_____	_____	_____
1300	700	700SD20-0060 ELECTRICAL SERVICE SE-5	1.000 EA	_____	_____	_____	_____
1310	700	700SD20-0067 PEDESTAL POLE PF-2, 12'	2.000 EA	_____	_____	_____	_____
1320	700	700SD20-0068 CONC. FOUND. PF-8	20.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1330	700	700SD20-0069 CONC. FOUND. PF-2	2.000 EA	_____	_____	_____	_____
1340	700	700SD20-0090 SIGNAL MAST ARM POLE MP-3, TY. A	1.000 EA	_____	_____	_____	_____
1350	700	700SD20-0093 SIGNAL MAST ARM POLE MP-3, TY. C	1.000 EA	_____	_____	_____	_____
1360	700	700SD20-0100 MAST ARM 49'	2.000 EA	_____	_____	_____	_____
1370	700	700SD20-0103 MAST ARM 70'	1.000 EA	_____	_____	_____	_____
1380	700	700SD20-0112 14/4 CONDUCTOR CABLE	2,475.000 LF	_____	_____	_____	_____
1390	700	700SD20-0114 14/7 CONDUCTOR CABLE	650.000 LF	_____	_____	_____	_____
1400	700	700SD20-0124 CAT 5E DIRECT BURIAL CABLE	625.000 LF	_____	_____	_____	_____
1410	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	1.000 EA	_____	_____	_____	_____
1420	700	700SD20-0178 JUNCTION BOX JB-S2	7.000 EA	_____	_____	_____	_____
1430	700	700SD20-0179 JUNCTION BOX JB-S3	1.000 EA	_____	_____	_____	_____
1440	700	700SD20-0181 ELECT. SER. GRD. ELECTRODE 10'	5.000 EA	_____	_____	_____	_____
1450	700	700SD20-0191 BORED CONDUIT 2"	230.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1460	700	700SD20-0192 BORED CONDUIT 3"	330.000 LF	_____	_____	_____	_____
1470	700	700SD20-0194 CONDUIT PVC 2"	1,100.000 LF	_____	_____	_____	_____
1480	700	700SD20-0195 CONDUIT PVC 3"	30.000 LF	_____	_____	_____	_____
1490	700	700SD20-0197 TRENCH EXCAVATION ECI-1	1,075.000 LF	_____	_____	_____	_____
1500	700	700SD20-0199 TEST BORE	2.000 EA	_____	_____	_____	_____
1510	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION ATC CABINET 4-DOOR CONFIGURATION	1.000 EA	_____	_____	_____	_____
1520	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION ATC CABINET TYPE II 16- OUTPUTS	1.000 EA	_____	_____	_____	_____
1530	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION INSTALL VIDEO DETECTION SYSTEM, TYPE II	1.000 EA	_____	_____	_____	_____
1540	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION INSTALL VIDEO SENSOR UNIT, TYPE II	4.000 EA	_____	_____	_____	_____
1550	703	700SX20-0022 CONC FOUNDATION CF-5	1.000 EA	_____	_____	_____	_____
1560	701	701SD20-0001 SIGN PANEL	149.000 SF	_____	_____	_____	_____
1570	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	36.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1580	703	703SD20-0011 PEDESTRIAN ACTUATION PA-2	2.000 EA	_____	_____	_____	_____
1590	703	703SD20-0023 EVP DETECTION SYSTEM 4-WAY	1.000 EA	_____	_____	_____	_____
1600	703	703SD20-0024 EVP DETECTOR CABLE	625.000 LF	_____	_____	_____	_____
1610	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	7.000 EA	_____	_____	_____	_____
1620	703	703SD20-0037 HANGER ASSEMBLY SMB-2, ONE WAY	2.000 EA	_____	_____	_____	_____
1630	703	703SD20-0044 REMOVE EXISTING POLE	1.000 EA	_____	_____	_____	_____
1640	703	703SD20-0045 REMOVE EXISTING FOUNDATION	2.000 EA	_____	_____	_____	_____
1650	703	703SD20-0047 REMOVE EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
1660	703	703SD20-0053 UNINTERRUPT. PWR SUPPLY TYPE 2	1.000 EA	_____	_____	_____	_____
1670	703	703SD20-0054 UNINTERRUPT. PWR SUPPLY BATTERY PAC	1.000 EA	_____	_____	_____	_____
1680	703	703SD20-0060 PEDESTRIAN SIGNAL HEAD SP-8	2.000 EA	_____	_____	_____	_____
1690	704	704SD20-0002 TYPE A PVMT LINE MRKG 6"	4,351.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120697C01 Oversight/State Project No.: 0114-060-873, C501
 Order No.: A66 Federal Project No.: STP-5150(252)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1700	704	704SD20-0003 TYPE A PVMT LINE MRKG 8"	10,261.000 LF	_____	_____	_____	_____
1710	704	704SD20-0005 TYPE A PVMT LINE MRKG 24"	100.000 LF	_____	_____	_____	_____
1720	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	6,050.000 LF	_____	_____	_____	_____
1730	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	3,900.000 LF	_____	_____	_____	_____
1740	704	704SD20-0013 TYPE B CLASS II PVMT LINE MRKG 8"	100.000 LF	_____	_____	_____	_____
1750	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	115.000 LF	_____	_____	_____	_____
1760	704	704SD20-0046 PVMT SYMB MRKG SGL TURN ARROW TY A	10.000 EA	_____	_____	_____	_____
1770	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	14.000 EA	_____	_____	_____	_____
1780	704	704SD20-0111 PVMT MSG. MARK. "SCHOOL" TY B, CL II, 8'	1.000 EA	_____	_____	_____	_____

Section: 0001 Total: _____

Total Bid: _____