

Schedule of Items

Proposal ID: C0000124001C01

Oversight/State Project No.: U000-103-247, C501

Order No.: A61

Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0025 15" CONC. PIPE	26.000 LF	_____	_____	_____	_____
0020	302	302SD20-0242 DROP INLET DI-2B,L=6'	1.000 EA	_____	_____	_____	_____
0030	302	302SD20-0244 DROP INLET DI-2B,L=10'	1.000 EA	_____	_____	_____	_____
0040	302	302SD20-0329 DROP INLET DI-3C,L=6'	1.000 EA	_____	_____	_____	_____
0050	302	302SD20-0662 MANHOLE MH-1 OR 2	6.400 LF	_____	_____	_____	_____
0060	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0070	303	303SD20-0004 GRADING	LUMP SUM	LUMP SUM	_____	_____	_____
0080	303	303SD20-0029 SILTATION CONTROL EXCAVATION	108.000 CY	_____	_____	_____	_____
0090	303	303SD20-0031 INLET PROTECTION TYPE B	9.000 EA	_____	_____	_____	_____
0100	303	303SD20-0034 TEMP. SILT FENCE TYPE A	372.000 LF	_____	_____	_____	_____
0110	308	308SD20-0007 AGGR. MATL. NO. 21B	142.000 TON	_____	_____	_____	_____
0120	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	54.000 TON	_____	_____	_____	_____
0130	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	14.000 TON	_____	_____	_____	_____
0140	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	355.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124001C01 Oversight/State Project No.: U000-103-247, C501
 Order No.: A61 Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	501	501SD20-0004 UNDERDRAIN UD-4	108.000 LF	_____	_____	_____	_____
0160	501	501SD20-0009 OUTLET PIPE	8.000 LF	_____	_____	_____	_____
0170	502	502SD20-0011 CURB, STD. CG-2	216.000 LF	_____	_____	_____	_____
0180	502	502SD20-0012 CURB, RADIAL CG-2	91.000 LF	_____	_____	_____	_____
0190	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	141.000 LF	_____	_____	_____	_____
0200	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	108.000 LF	_____	_____	_____	_____
0210	503	503SD20-0001 R/W MONUMENT RM-1	9.000 EA	_____	_____	_____	_____
0220	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	9.000 SY	_____	_____	_____	_____
0230	504	504SD20-0003 HYDR. CEMENT CONC. SIDEWALK 4"	220.000 SY	_____	_____	_____	_____
0240	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	45.000 LF	_____	_____	_____	_____
0250	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	39.000 SY	_____	_____	_____	_____
0260	510	510SX20-0026 REMOVE EXIST. DROP INLET REMOVE DROP INLET	1.000 EA	_____	_____	_____	_____
0270	510	510SX20-0029 RESET EXIST. JUNCTION BOX	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124001C01 Oversight/State Project No.: U000-103-247, C501
 Order No.: A61 Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	510	510SX20-0031 MODIFY EXIST. MODIFY EXISTING CONTROLLER	1.000 EA	_____	_____	_____	_____
0290	510	510SX20-0031 MODIFY EXIST. MODIFY EXISTING JUNCTION BOX	4.000 EA	_____	_____	_____	_____
0300	510	510SX20-0033 ADJUST EXIST. DROP INLET ADJUST DROP INLET	1.000 EA	_____	_____	_____	_____
0310	510	510SX20-0046 ADJUST EXIST. ADJUST EXISTING VIDEO DETECTION ZONE	1.000 EA	_____	_____	_____	_____
0320	511	511SD20-0001 ALLAYING DUST	101.000 HR	_____	_____	_____	_____
0330	512	512SD20-0013 TYPE 3 BARRICADE 8'	1.000 EA	_____	_____	_____	_____
0340	512	512SD20-0014 TEMPORARY SIGN	445.000 SF	_____	_____	_____	_____
0350	512	512SD20-0018 PEDESTRIAN BARRICADE DEVICE	84.000 LF	_____	_____	_____	_____
0360	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	7,416.000 DAY	_____	_____	_____	_____
0370	512	512SD20-0027 FLAGGER SERVICE	150.000 HR	_____	_____	_____	_____
0380	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	153.000 SF	_____	_____	_____	_____
0390	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000124001C01 Oversight/State Project No.: U000-103-247, C501
 Order No.: A61 Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM			
0410	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"-2"	452.000 SY				
0420	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0430	602	602SD20-0004 TOPSOIL CLASS B	32.000 CY				
0440	603	603SD20-0002 TEMPORARY SEED	8.000 LB				
0450	603	603SD20-0003 REGULAR SEED	32.000 LB				
0460	603	603SD20-0004 OVERSEEDING	26.000 LB				
0470	603	603SD20-0007 HYDRAULIC EROSION CONTROL PRODUCT TYPE 1	484.000 SY				
0480	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	387.000 SY				
0490	603	603SD20-0014 FERTILIZER NITROGEN - N	8.000 LB				
0500	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	6.000 LB				
0510	603	603SD20-0016 FERTILIZER POTASSIUM - K	6.000 LB				
0520	603	603SD20-0017 LIME	0.440 TON				

Schedule of Items

Proposal ID: C0000124001C01 Oversight/State Project No.: U000-103-247, C501
 Order No.: A61 Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	ATTD	605SX20-0013 LANDSCAPE LANDSCAPING ALLOWANCE	LUMP SUM	LUMP SUM			
0540	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	3.000 EA				
0550	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA				
0560	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	75.000 LF				
0570	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	6.000 EA				
0580	700	700SD20-0066 PEDESTAL POLE PF-2, 10'	4.000 EA				
0590	700	700SD20-0069 CONC. FOUND. PF-2	4.000 EA				
0600	700	700SD20-0110 14/2 CONDUCTOR CABLE	725.000 LF				
0610	700	700SD20-0114 14/7 CONDUCTOR CABLE	745.000 LF				
0620	700	700SD20-0148 8 CONDUCTOR CABLE EGC	110.000 LF				
0630	700	700SD20-0178 JUNCTION BOX JB-S2	1.000 EA				
0640	700	700SD20-0195 CONDUIT PVC 3"	85.000 LF				
0650	700	700SD20-0197 TRENCH EXCAVATION ECI-1	85.000 LF				
0660	701	701SD20-0001 SIGN PANEL	53.000 SF				

Schedule of Items

Proposal ID: C0000124001C01 Oversight/State Project No.: U000-103-247, C501
 Order No.: A61 Federal Project No.: STP-5103(140)

Contractor: _____

SECTION: 0001 REGULAR BID ITEMS

Cat Alt Set ID: Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	703	703SD20-0011 PEDESTRIAN ACTUATION PA-2	4.000 EA	_____	_____	_____	_____
0680	703	703SD20-0036 HANGER ASSEMBLY SMB-1, ONE WAY	4.000 EA	_____	_____	_____	_____
0690	703	703SD20-0060 PEDESTRIAN SIGNAL HEAD SP-8	4.000 EA	_____	_____	_____	_____
0700	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	200.000 LF	_____	_____	_____	_____
0710	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	188.000 LF	_____	_____	_____	_____
0720	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	2.000 EA	_____	_____	_____	_____
0730	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	7.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____