

Schedule of Items

Proposal ID: C0000115131C01

Oversight/State Project No.: 0211-069-814, M501

Order No.: A99

Federal Project No.: STP-069-8(049)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	303	303SD20-0001 REGULAR EXCAVATION	1,170.000 CY	_____	_____	_____	_____
0020	303	303SD20-0007 BORROW EXCAVATION	575.000 CY	_____	_____	_____	_____
0030	303	303SD20-0029 SILTATION CONTROL EXCAVATION	125.000 CY	_____	_____	_____	_____
0040	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,000.000 LF	_____	_____	_____	_____
0050	305	305SD20-0005 SELECT MATL. TY. I MIN. CBR- 30	909.000 TON	_____	_____	_____	_____
0060	305	305SD20-0012 AGGR.BASE MAT.TY. I NO.21A OR 21B	603.000 TON	_____	_____	_____	_____
0070	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	225.000 TON	_____	_____	_____	_____
0080	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	382.000 TON	_____	_____	_____	_____
0090	412	412SD20-0044 SAW CUTTING NS SAW CUT FULL DEPTH SAW CUT (3" DEPTH)	1,000.000 LF	_____	_____	_____	_____
0100	508	508SD20-0001 OBSCURING ROADWAY	1.000 UNIT	_____	_____	_____	_____
0110	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,030.000 SY	_____	_____	_____	_____
0120	511	511SD20-0001 ALLAYING DUST	200.000 HR	_____	_____	_____	_____
0130	512	512SD20-0014 TEMPORARY SIGN	800.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115131C01

Oversight/State Project No.: 0211-069-814, M501

Order No.: A99

Federal Project No.: STP-069-8(049)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	1,500.000 DAY	_____	_____	_____	_____
0150	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	500.000 HR	_____	_____	_____	_____
0160	512	512SD20-0027 FLAGGER SERVICE	500.000 HR	_____	_____	_____	_____
0170	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	500.000 DAY	_____	_____	_____	_____
0180	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0190	514	514SD20-0002 FIELD OFFICE TY.II	12.000 MO	_____	_____	_____	_____
0200	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN	LUMP SUM	LUMP SUM	_____	_____	_____
0210	602	602SX20-0005 TOPSOIL 3' TOPSOIL CLASS B	0.690 ACRE	_____	_____	_____	_____
0220	603	603SD20-0002 TEMPORARY SEED	69.000 LB	_____	_____	_____	_____
0230	603	603SD20-0003 REGULAR SEED	275.000 LB	_____	_____	_____	_____
0240	603	603SD20-0004 OVERSEEDING	220.000 LB	_____	_____	_____	_____
0250	603	603SD20-0014 FERTILIZER NITROGEN - N	69.000 LB	_____	_____	_____	_____
0260	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	48.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115131C01

Oversight/State Project No.: 0211-069-814, M501

Order No.: A99

Federal Project No.: STP-069-8(049)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	603	603SD20-0016 FERTILIZER POTASSIUM - K	48.000 LB	_____	_____	_____	_____
0280	603	603SD20-0017 LIME	3.780 TON	_____	_____	_____	_____
0290	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	40.000 LF	_____	_____	_____	_____
0300	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	4.000 EA	_____	_____	_____	_____
0310	700	700SD20-0068 CONC. FOUND. PF-8	35.000 CY	_____	_____	_____	_____
0320	700	700SD20-0090 SIGNAL MAST ARM POLE MP- 3, TY. A	1.000 EA	_____	_____	_____	_____
0330	700	700SD20-0096 SIGNAL MAST ARM POLE MP- 3, TY. E2	1.000 EA	_____	_____	_____	_____
0340	700	700SD20-0100 MAST ARM 49'	1.000 EA	_____	_____	_____	_____
0350	700	700SD20-0105 MAST ARM 75', CASE 2 LOADING	1.000 EA	_____	_____	_____	_____
0360	700	700SD20-0108 8/3 CONDUCTOR CABLE	195.000 LF	_____	_____	_____	_____
0370	700	700SD20-0112 14/4 CONDUCTOR CABLE	2,638.000 LF	_____	_____	_____	_____
0380	700	700SD20-0191 BORED CONDUIT 2"	112.000 LF	_____	_____	_____	_____
0390	700	700SD20-0192 BORED CONDUIT 3"	225.000 LF	_____	_____	_____	_____
0400	700	700SD20-0194 CONDUIT PVC 2"	50.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000115131C01

Oversight/State Project No.: 0211-069-814, M501

Order No.: A99

Federal Project No.: STP-069-8(049)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	700	700SD20-0195 CONDUIT PVC 3"	94.000 LF	_____	_____	_____	_____
0420	700	700SD20-0199 TEST BORE	4.000 EA	_____	_____	_____	_____
0430	ATTD	700SX20-0009 TRAFFIC SIGNALIZATION ANTENNA CABLE	390.000 LF	_____	_____	_____	_____
0440	701	701SD20-0001 SIGN PANEL	141.000 SF	_____	_____	_____	_____
0450	703	703SD20-0007 TRAF. SIG. HEAD SECT. 12" HVS BACKPLATE	30.000 EA	_____	_____	_____	_____
0460	703	703SD20-0015 VIDEO DETECTION CABLE	798.000 LF	_____	_____	_____	_____
0470	703	703SD20-0034 HANGER ASSEMBLY SM-3, ONE WAY	10.000 EA	_____	_____	_____	_____
0480	ATTD	703SX20-0003 DETECTOR MSDS HYBRID SENSOR	1.000 EA	_____	_____	_____	_____
0490	ATTD	703SX20-0003 DETECTOR MSDS VIDEO CAMERA	2.000 EA	_____	_____	_____	_____
0500	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	1,744.000 LF	_____	_____	_____	_____
0510	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	790.000 LF	_____	_____	_____	_____
0520	704	704SD20-0011 TYPE B CLASS II PVMT LINE MRKG 4"	444.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 6

Proposal ID: C0000115131C01

Oversight/State Project No.: 0211-069-814, M501

Order No.: A99

Federal Project No.: STP-069-8(049)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	79.000 LF	_____	_____	_____	_____
0540	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	13.000 EA	_____	_____	_____	_____
0550	807	807SD20-0003 5.8 GHZ WIRELESS BROADBAND RADIO	2.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____