

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____	_____
0020	ATTD	302SD20-0002 BEDDING MATL. AGGR. NO. 57	142.000 TON	_____	_____	_____	_____
0030	302	302SD20-0012 ENDWALL GRATE & FRAME EW-11A	2.000 EA	_____	_____	_____	_____
0040	302	302SD20-0013 ENDWALL EW-12	2.000 EA	_____	_____	_____	_____
0050	302	302SD20-0030 18" CONC. PIPE	110.000 LF	_____	_____	_____	_____
0060	302	302SD20-0032 18" STORM SEWER PIPE	169.000 LF	_____	_____	_____	_____
0070	302	302SD20-0041 24" STORM SEWER PIPE	26.000 LF	_____	_____	_____	_____
0080	302	302SD20-0204 24" END SECTION ES-1 OR 2	1.000 EA	_____	_____	_____	_____
0090	302	302SD20-0446 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0100	302	302SD20-0448 DROP INLET DI-7A	1.000 EA	_____	_____	_____	_____
0110	302	302SD20-0662 MANHOLE MH-1 OR 2	9.800 LF	_____	_____	_____	_____
0120	302	302SD20-0663 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0130	303	303SD20-0001 REGULAR EXCAVATION	2,510.000 CY	_____	_____	_____	_____
0140	303	303SD20-0010 EMBANKMENT	1,934.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0021 TEMPORARY DIVERSION DIKE	100.000 LF	_____	_____	_____	_____
0160	303	303SD20-0022 CHECK DAM ROCK TY. I	2.000 EA	_____	_____	_____	_____
0170	303	303SD20-0023 CHECK DAM ROCK TY. II	25.000 EA	_____	_____	_____	_____
0180	303	303SD20-0024 CHECK DAM SEDIMENT RETENTION ROLL 18"	7.000 EA	_____	_____	_____	_____
0190	303	303SD20-0029 SILTATION CONTROL EXCAVATION	392.520 CY	_____	_____	_____	_____
0200	303	303SD20-0030 INLET PROTECTION TYPE A	4.000 EA	_____	_____	_____	_____
0210	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,840.000 LF	_____	_____	_____	_____
0220	305	305SD20-0005 SELECT MATL. TY. I MIN. CBR- 30	1,648.000 TON	_____	_____	_____	_____
0230	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	497.000 SY	_____	_____	_____	_____
0240	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	2,396.000 TON	_____	_____	_____	_____
0250	315	315SD20-0003 ASPHALT CONCRETE TY. SM- 12.5E CONST	1,241.000 TON	_____	_____	_____	_____
0260	315	315SD20-0006 ASPHALT CONCRETE TY. IM- 19.0E CONST	578.000 TON	_____	_____	_____	_____
0270	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	963.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE (FULL DEPTH)	2,657.000 LF	_____	_____	_____	_____
0290	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	10.500 TON	_____	_____	_____	_____
0300	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	19.500 TON	_____	_____	_____	_____
0310	501	501SD20-0004 UNDERDRAIN UD-4	1,612.000 LF	_____	_____	_____	_____
0320	501	501SD20-0009 OUTLET PIPE	114.000 LF	_____	_____	_____	_____
0330	502	502SD20-0003 PAVED DITCH PG-2A	354.900 SY	_____	_____	_____	_____
0340	502	502SD20-0014 CURB, STD. CG-3	158.000 LF	_____	_____	_____	_____
0350	502	502SD20-0015 CURB, RADIAL CG-3	370.000 LF	_____	_____	_____	_____
0360	502	502SD20-0053 MEDIAN STRIP MS-1	154.000 SY	_____	_____	_____	_____
0370	502	502SD20-0058 MEDIAN STRIP MS-2	118.000 LF	_____	_____	_____	_____
0380	504	504SD20-0010 CONCRETE CLASS A-3 MISC TRUCK APRONS	122.000 CY	_____	_____	_____	_____
0390	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	2.000 EA	_____	_____	_____	_____
0400	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	290.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	1,602.000 SY	_____	_____	_____	_____
0420	510	510SX20-0031 MODIFY EXIST. DROP INLET	2.000 EA	_____	_____	_____	_____
0430	512	512SD20-0013 TYPE 3 BARRICADE 8'	11.000 EA	_____	_____	_____	_____
0440	512	512SD20-0014 TEMPORARY SIGN	1,297.000 SF	_____	_____	_____	_____
0450	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	2,272.000 HR	_____	_____	_____	_____
0460	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	15,715.000 DAY	_____	_____	_____	_____
0470	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	2,272.000 HR	_____	_____	_____	_____
0480	512	512SD20-0026 ELECTRONIC ARROW BOARD	2,072.000 HR	_____	_____	_____	_____
0490	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	17,953.000 LF	_____	_____	_____	_____
0500	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	4,275.000 LF	_____	_____	_____	_____
0510	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0520	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	7,771.000 SY	_____	_____	_____	_____
0530	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0540	602	602SD20-0004 TOPSOIL CLASS B	290.000 CY	_____	_____	_____	_____
0550	603	603SD20-0002 TEMPORARY SEED	7.000 LB	_____	_____	_____	_____
0560	603	603SD20-0003 REGULAR SEED	194.000 LB	_____	_____	_____	_____
0570	603	603SD20-0004 OVERSEEDING	155.000 LB	_____	_____	_____	_____
0580	603	603SD20-0005 LEGUME SEED	9.000 LB	_____	_____	_____	_____
0590	603	603SD20-0006 LEGUME OVERSEEDING	7.000 LB	_____	_____	_____	_____
0600	603	603SD20-0014 FERTILIZER NITROGEN - N	59.000 LB	_____	_____	_____	_____
0610	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	37.000 LB	_____	_____	_____	_____
0620	603	603SD20-0016 FERTILIZER POTASSIUM - K	37.000 LB	_____	_____	_____	_____
0630	603	603SD20-0017 LIME	2.660 TON	_____	_____	_____	_____
0640	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	379.300 SY	_____	_____	_____	_____
0650	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	13.000 EA	_____	_____	_____	_____
0660	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	198.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0670	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	48.000 LF	_____	_____	_____	_____
0680	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	128.000 LF	_____	_____	_____	_____
0690	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	209.100 LF	_____	_____	_____	_____
0700	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	35.000 EA	_____	_____	_____	_____
0710	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	10.000 EA	_____	_____	_____	_____
0720	701	701SD20-0001 SIGN PANEL	639.200 SF	_____	_____	_____	_____
0730	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	5,994.000 LF	_____	_____	_____	_____
0740	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	2,527.000 LF	_____	_____	_____	_____
0750	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	89.000 LF	_____	_____	_____	_____
0760	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	31.000 EA	_____	_____	_____	_____
0770	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	8.000 EA	_____	_____	_____	_____
0780	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	24.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119687C01B Oversight/State Project No.: 0058-012-792, C501

Order No.: A42

Federal Project No.: STP-012-4(063)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	704	704SX20-0002 PAVEMENT MARKING U-TURN ARROW, TY. B, CL. II	4.000 EA				
Section: 0001				Total:			
				Total Bid:			