

Schedule of Items

Proposal ID: C0000129131C01B

Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0002 CONST REC DOCS SWM FACILITY PERMANENT SWM FACILITIES	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	27.000 EA				
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	302	302SD20-0013 ENDWALL EW-12	13.000 EA				
0060	302	302SD20-0023 15" PIPE	42.000 LF				
0070	302	302SD20-0027 15" STORM SEWER PIPE	1,239.000 LF				
0080	302	302SD20-0032 18" STORM SEWER PIPE	453.000 LF				
0090	302	302SD20-0243 DROP INLET DI-2B,L=8'	7.000 EA				
0100	302	302SD20-0244 DROP INLET DI-2B,L=10'	5.000 EA				
0110	302	302SD20-0245 DROP INLET DI-2B,L=12'	1.000 EA				
0120	302	302SD20-0446 DROP INLET DI-5	2.000 EA				
0130	302	302SD20-0655 DROP INLET DI-13 TY.I	2.000 EA				
0140	302	302SD20-0662 MANHOLE MH-1 OR 2	12.400 LF				

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0663 FRAME & COVER MH-1	3.000 EA	_____	_____	_____	_____
0160	ATTD	302SX20-0022 DRAINAGE UNDERDRAIN INSPECTION PORT	3.000 EA	_____	_____	_____	_____
0170	303	303SD20-0001 REGULAR EXCAVATION	4,738.000 CY	_____	_____	_____	_____
0180	303	303SD20-0007 BORROW EXCAVATION	427.000 CY	_____	_____	_____	_____
0190	303	303SD20-0018 SLOPE DRAIN	2.000 EA	_____	_____	_____	_____
0200	303	303SD20-0019 EROSION CONTROL MULCH	6,340.000 SY	_____	_____	_____	_____
0210	303	303SD20-0023 CHECK DAM ROCK TY. II	29.000 EA	_____	_____	_____	_____
0220	303	303SD20-0024 CHECK DAM SEDIMENT RETENTION ROLL 18"	32.000 EA	_____	_____	_____	_____
0230	303	303SD20-0028 DEWATERING BASIN EC-8	5.000 EA	_____	_____	_____	_____
0240	303	303SD20-0029 SILTATION CONTROL EXCAVATION	1,408.000 CY	_____	_____	_____	_____
0250	303	303SD20-0030 INLET PROTECTION TYPE A	55.000 EA	_____	_____	_____	_____
0260	303	303SD20-0031 INLET PROTECTION TYPE B	15.000 EA	_____	_____	_____	_____
0270	303	303SD20-0033 TEMP. SILT FENCE TYPE B	1,117.000 LF	_____	_____	_____	_____
0280	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,726.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	3,008.000 CY	_____	_____	_____	_____
0300	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	2,248.000 TON	_____	_____	_____	_____
0310	309	309SD20-0001 AGGR. MATL. NO. 1	325.000 TON	_____	_____	_____	_____
0320	313	313SD20-0001 ASPH-STAB. OPEN-GRADED MATERIAL	1,121.000 TON	_____	_____	_____	_____
0330	315	315SD20-0003 ASPHALT CONCRETE TY. SM- 12.5E CONST	3,407.000 TON	_____	_____	_____	_____
0340	315	315SD20-0006 ASPHALT CONCRETE TY. IM- 19.0E CONST	3,411.000 TON	_____	_____	_____	_____
0350	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	118.000 TON	_____	_____	_____	_____
0360	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	3,992.000 LF	_____	_____	_____	_____
0370	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	592.000 SY	_____	_____	_____	_____
0380	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	141.000 TON	_____	_____	_____	_____
0390	ATTD	315SP20-0020 OTHER CEMENTITIOUS MATERIAL OTHER CEMENTITIOUS MATERIAL	522.000 TON	_____	_____	_____	_____
0400	ATTD	315SP20-0021 HYDRAULIC CEMENT HYDRAULIC CEMENT	522.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0410	ATTD	315SP20-0022 LIME LIME	522.000 TON	_____	_____	_____	_____
0420	ATTD	315SX20-0005 PAVEMENT LIQUID ASPHALT EMULSION	313.000 TON	_____	_____	_____	_____
0430	ATTD	315SX20-0005 PAVEMENT LIQUID ASPHALT FOAMED	191.000 TON	_____	_____	_____	_____
0440	ATTD	315SX20-0011 SAW-CUT ASPH CONC (FULL DEPTH)	13,985.000 LF	_____	_____	_____	_____
0450	ATTD	315SX20-0013 FULL DEPTH RECLAMATION (13")	14,262.000 SY	_____	_____	_____	_____
0460	ATTD	410SX20-0010 PIER PROTECTION SYSTEM 42", CONST	95.000 LF	_____	_____	_____	_____
0470	412	412SD20-0033 PATCHING TYPE B	5.110 SY	_____	_____	_____	_____
0480	414	414SD20-0004 EROSION CTRL. STONE CL. I, EC-1	4.700 SY	_____	_____	_____	_____
0490	414	414SD20-0012 DRY RIPRAP CL.I 26"	7,215.000 TON	_____	_____	_____	_____
0500	419	419SX20-0004 COMMUNICATION LINES CONDUIT SYSTEM (B606)	LUMP SUM	LUMP SUM	_____	_____	_____
0510	ATTD	419SX20-0006 DECK DRAINAGE SYSTEM (B606)	LUMP SUM	LUMP SUM	_____	_____	_____
0520	425	425SD20-0024 TYPE B HYDRO-DEMOLITION 4"	5.110 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	501	501SD20-0004 UNDERDRAIN UD-4	2,976.000 LF	_____	_____	_____	_____
0540	501	501SD20-0009 OUTLET PIPE	161.000 LF	_____	_____	_____	_____
0550	502	502SD20-0003 PAVED DITCH PG-2A	268.000 SY	_____	_____	_____	_____
0560	502	502SD20-0014 CURB, STD. CG-3	110.000 LF	_____	_____	_____	_____
0570	502	502SD20-0020 CURB, ASPHALT MC-3B	3,410.000 LF	_____	_____	_____	_____
0580	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	39.500 CY	_____	_____	_____	_____
0590	505	505SD20-0011 GUARDRAIL GR-MGS1	4,384.000 LF	_____	_____	_____	_____
0600	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	7,920.000 LF	_____	_____	_____	_____
0610	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	15.000 EA	_____	_____	_____	_____
0620	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	13.000 EA	_____	_____	_____	_____
0630	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	5.000 EA	_____	_____	_____	_____
0640	505	505SD20-0045 FIXED OBJECT ATTACH. GR- FOA-1 TY. I	1.000 EA	_____	_____	_____	_____
0650	505	505SD20-0046 FIXED OBJECT ATTACH. GR- FOA-1 TY. II	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B

Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	505	505SD20-0053 FIXED OBJECT ATTACH. GR- FOA-2 TY. I	1.000 EA	_____	_____	_____	_____
0670	505	505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II	1.000 EA	_____	_____	_____	_____
0680	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	2.000 EA	_____	_____	_____	_____
0690	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	4,174.000 LF	_____	_____	_____	_____
0700	ATTD	505SX20-0070 IMPACT ATTENUATOR (SPECIAL DESIGN IMPACT ATTEND. SER. TY. 2, 12)	1.000 EA	_____	_____	_____	_____
0710	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	481.000 SY	_____	_____	_____	_____
0720	510	510SX20-0031 MODIFY EXIST. DRAINAGE STRUCTURE	9.000 EA	_____	_____	_____	_____
0730	511	511SD20-0001 ALLAYING DUST	7,362.000 HR	_____	_____	_____	_____
0740	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	2,650.000 LF	_____	_____	_____	_____
0750	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	2.000 EA	_____	_____	_____	_____
0760	512	512SD20-0013 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0770	512	512SD20-0014 TEMPORARY SIGN	663.000 SF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0780	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,080.000 HR	_____	_____	_____	_____
0790	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	18,130.000 DAY	_____	_____	_____	_____
0800	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	2,100.000 HR	_____	_____	_____	_____
0810	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,360.000 HR	_____	_____	_____	_____
0820	512	512SD20-0029 WARNING LIGHT TY. B	425.000 DAY	_____	_____	_____	_____
0830	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	19,950.000 LF	_____	_____	_____	_____
0840	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	105.000 EA	_____	_____	_____	_____
0850	512	512SD20-0054 TEMP. PVMT MRKG TY. E, 6"	2,435.000 LF	_____	_____	_____	_____
0860	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	9,637.000 LF	_____	_____	_____	_____
0870	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	2,100.000 LF	_____	_____	_____	_____
0880	512	512SD20-0064 TEMP. PVMT MRKG TY. D, CL. III, 12"	490.000 LF	_____	_____	_____	_____
0890	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0900	514	514SD20-0001 FIELD OFFICE TY.I	27.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B

Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	15,056.000 SY	_____	_____	_____	_____
0920	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0930	602	602SD20-0004 TOPSOIL CLASS B	1,057.000 CY	_____	_____	_____	_____
0940	603	603SD20-0002 TEMPORARY SEED	262.000 LB	_____	_____	_____	_____
0950	603	603SD20-0003 REGULAR SEED	868.000 LB	_____	_____	_____	_____
0960	603	603SD20-0004 OVERSEEDING	694.000 LB	_____	_____	_____	_____
0970	603	603SD20-0005 LEGUME SEED	18.000 LB	_____	_____	_____	_____
0980	603	603SD20-0006 LEGUME OVERSEEDING	15.000 LB	_____	_____	_____	_____
0990	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	8,833.000 SY	_____	_____	_____	_____
1000	603	603SD20-0010 HYDRAULIC EROSION CONTROL PRODUCT TYPE 4	19,699.000 SY	_____	_____	_____	_____
1010	603	603SD20-0014 FERTILIZER NITROGEN - N	262.000 LB	_____	_____	_____	_____
1020	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	183.000 LB	_____	_____	_____	_____
1030	603	603SD20-0016 FERTILIZER POTASSIUM - K	183.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	603	603SD20-0017 LIME	14.410 TON				
1050	ATTD	605SX20-0013 LANDSCAPE PERMANENT VEGETATIVE COVER	LUMP SUM	LUMP SUM			
1060	606	606SD20-0003 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 3	2,200.000 SY				
1070	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	180.000 SY				
1080	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	3.000 EA				
1090	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA				
1100	700	700SD20-0013 RELOCATE EX. 2 POST GRND MOUNT SGN PANEL	2.000 EA				
1110	700	700SD20-0178 JUNCTION BOX JB-S2	2.000 EA				
1120	700	700SD20-0179 JUNCTION BOX JB-S3	2.000 EA				
1130	700	700SD20-0197 TRENCH EXCAVATION ECI-1	75.000 LF				
1140	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION JUNCTION BOX BRIDGE MOUNTED 30"X30"X24"	11.000 EA				
1150	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION JUNCTION BOX BRIDGE MOUNTED 8"X13"X24"	16.000 EA				

Schedule of Items

Proposal ID: C0000129131C01B Oversight/State Project No.: 0288-M11-022, B606, C501

Order No.: A97

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1160	700	700SX20-0016 RELOCATE EX. OVRHD SGN STR. SGN.PANEL RELOCATE TO GROUND MOUNT	2.000 EA	_____	_____	_____	_____
1170	700	700SX20-0017 REMOVE EXIST. OVERHEAD SIGN STRUCTURE SIGN	2.000 EA	_____	_____	_____	_____
1180	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	23,455.000 LF	_____	_____	_____	_____
1190	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	490.000 LF	_____	_____	_____	_____
1200	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	12,670.000 LF	_____	_____	_____	_____
1210	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	88.000 EA	_____	_____	_____	_____
1220	ATTD	801SX20-0001 COMMUNICATION EQUIP. PORTABLE CCTV CAMERA	2.000 EA	_____	_____	_____	_____
1230	ATTD	801SX20-0003 COMMUNICATION EQUIP. ATTACHED ITS CONDUIT FRE 2"	11,625.000 LF	_____	_____	_____	_____
1240	ATTD	801SX20-0003 COMMUNICATION EQUIP. ATTACHED ITS CONDUIT FRE 8"	3,950.000 LF	_____	_____	_____	_____
1250	812	812SD20-0004 BORED ITS CONDUIT HDPE 4"	75.000 LF	_____	_____	_____	_____
1260	812	812SD20-0007 ITS CONDUIT HDPE 2"	225.000 LF	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

Total Bid: _____.