

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	18.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	302	302SD20-0013 ENDWALL EW-12	1.000 EA				
0050	302	302SD20-0027 15" STORM SEWER PIPE	776.000 LF				
0060	302	302SD20-0039 24" CONC. PIPE	53.000 LF				
0070	302	302SD20-0041 24" STORM SEWER PIPE	209.000 LF				
0080	302	302SD20-0051 30" STORM SEWER PIPE	53.000 LF				
0090	302	302SD20-0240 DROP INLET DI-2AA	2.000 EA				
0100	302	302SD20-0241 DROP INLET DI-2B,L=4'	2.000 EA				
0110	302	302SD20-0242 DROP INLET DI-2B,L=6'	1.000 EA				
0120	302	302SD20-0311 DROP INLET DI-3B,L=4'	2.000 EA				
0130	302	302SD20-0312 DROP INLET DI-3B,L=6'	2.000 EA				
0140	302	302SD20-0313 DROP INLET DI-3B,L=8'	1.000 EA				

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	302	302SD20-0314 DROP INLET DI-3B,L=10'	1.000 EA	_____	_____	_____	_____
0160	302	302SD20-0321 DROP INLET DI-3BB,L=6'	1.000 EA	_____	_____	_____	_____
0170	302	302SD20-0337 DROP INLET DI-3CC,L=6'	2.000 EA	_____	_____	_____	_____
0180	302	302SD20-0447 DROP INLET DI-7	1.000 EA	_____	_____	_____	_____
0190	302	302SD20-0662 MANHOLE MH-1 OR 2	11.500 LF	_____	_____	_____	_____
0200	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0210	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	6.100 LF	_____	_____	_____	_____
0220	302	302SD20-0683 TEMP. SEDIMENT RISER PIPE 48"	6.100 LF	_____	_____	_____	_____
0230	303	303SD20-0001 REGULAR EXCAVATION	5,035.000 CY	_____	_____	_____	_____
0240	303	303SD20-0007 BORROW EXCAVATION	6,738.000 CY	_____	_____	_____	_____
0250	303	303SD20-0021 TEMPORARY DIVERSION DIKE	437.000 LF	_____	_____	_____	_____
0260	303	303SD20-0023 CHECK DAM ROCK TY. II	5.000 EA	_____	_____	_____	_____
0270	303	303SD20-0025 CHECK DAM SEDIMENT RETENTION ROLL 20"	3.000 EA	_____	_____	_____	_____
0280	303	303SD20-0028 DEWATERING BASIN EC-8	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0290	303	303SD20-0029 SILTATION CONTROL EXCAVATION	7,582.500 CY	_____	_____	_____	_____
0300	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0310	303	303SD20-0031 INLET PROTECTION TYPE B	14.000 EA	_____	_____	_____	_____
0320	303	303SD20-0032 GEOTEXTILE FABRIC	4,178.000 SY	_____	_____	_____	_____
0330	303	303SD20-0033 TEMP. SILT FENCE TYPE B	710.000 LF	_____	_____	_____	_____
0340	303	303SD20-0034 TEMP. SILT FENCE TYPE A	1,172.000 LF	_____	_____	_____	_____
0350	303	303SD20-0036 STORM WATER MAN. BASIN EXCAV.	1,756.000 CY	_____	_____	_____	_____
0360	308	308SD20-0007 AGGR. MATL. NO. 21B	5,003.000 TON	_____	_____	_____	_____
0370	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	164.000 TON	_____	_____	_____	_____
0380	310	310SD20-0001 TACK COAT	747.000 GAL	_____	_____	_____	_____
0390	315	315SD20-0002 ASPHALT CONCRETE TY. SM- 12.5D CONST	495.000 TON	_____	_____	_____	_____
0400	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	422.000 TON	_____	_____	_____	_____
0410	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	1,264.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0420	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE ASPHALT SAW- CUT	2,875.000 LF	_____	_____	_____	_____
0430	316	316SD20-0007 REINF. HYDR.CEM.CONC. PAVE. 8"	489.000 SY	_____	_____	_____	_____
0440	401	401SD20-0007 COFFERDAM 15' NON- ERODIBLE	1.000 EA	_____	_____	_____	_____
0450	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	138.300 TON	_____	_____	_____	_____
0460	414	414SD20-0008 DRY RIPRAP CL. AI	27.000 TON	_____	_____	_____	_____
0470	501	501SD20-0004 UNDERDRAIN UD-4	1,685.000 LF	_____	_____	_____	_____
0480	501	501SD20-0009 OUTLET PIPE	66.000 LF	_____	_____	_____	_____
0490	502	502SD20-0011 CURB, STD. CG-2	416.000 LF	_____	_____	_____	_____
0500	502	502SD20-0012 CURB, RADIAL CG-2	970.000 LF	_____	_____	_____	_____
0510	502	502SD20-0015 CURB, RADIAL CG-3	359.000 LF	_____	_____	_____	_____
0520	502	502SD20-0022 COMB. CURB & GUTTER, STD. CG-6	858.000 LF	_____	_____	_____	_____
0530	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	700.000 LF	_____	_____	_____	_____
0540	502	502SD20-0024 COMB. CURB & GUTTER, STD. CG-7	22.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0550	502	502SD20-0025 COMB. CURB & GUTTER, RAD. CG-7	102.000 LF	_____	_____	_____	_____
0560	502	502SD20-0053 MEDIAN STRIP MS-1	301.000 SY	_____	_____	_____	_____
0570	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	12.290 CY	_____	_____	_____	_____
0580	505	505SD20-0011 GUARDRAIL GR-MGS1	119.000 LF	_____	_____	_____	_____
0590	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	1.000 EA	_____	_____	_____	_____
0600	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	1.000 EA	_____	_____	_____	_____
0610	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	2.000 EA	_____	_____	_____	_____
0620	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	366.000 LF	_____	_____	_____	_____
0630	ATTD	505SP20-0013 BR-GR POST ATTACHMENT VARIOUS TYPES	2.000 EA	_____	_____	_____	_____
0640	507	507SD20-0005 FENCE FE-CL	580.000 LF	_____	_____	_____	_____
0650	507	507SD20-0014 GATE FE-CL 14'	1.000 EA	_____	_____	_____	_____
0660	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	4,015.000 SY	_____	_____	_____	_____
0670	511	511SD20-0001 ALLAYING DUST	209.000 HR	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0680	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	100.000 LF	_____	_____	_____	_____
0690	512	512SD20-0013 TYPE 3 BARRICADE 8'	17.000 EA	_____	_____	_____	_____
0700	512	512SD20-0014 TEMPORARY SIGN	2,329.000 SF	_____	_____	_____	_____
0710	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,016.000 HR	_____	_____	_____	_____
0720	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	21,659.000 DAY	_____	_____	_____	_____
0730	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	1,512.000 HR	_____	_____	_____	_____
0740	512	512SD20-0027 FLAGGER SERVICE	960.000 HR	_____	_____	_____	_____
0750	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	140.000 LF	_____	_____	_____	_____
0760	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	1,180.000 LF	_____	_____	_____	_____
0770	512	512SD20-0045 TEMP. PAVE. MARKER 2 WAY	227.000 EA	_____	_____	_____	_____
0780	512	512SD20-0061 TEMP. PVMT MRKG TY. D, CL. III, 4"	10,216.000 LF	_____	_____	_____	_____
0790	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	2,334.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0800	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	184.000 LF	_____	_____	_____	_____
0810	512	512SD20-0069 IMPACT ATTENUATOR IA-1	1.000 EA	_____	_____	_____	_____
0820	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
0830	514	514SD20-0001 FIELD OFFICE TY.I	18.000 MO	_____	_____	_____	_____
0840	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	1,832.000 SY	_____	_____	_____	_____
0850	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0860	602	602SD20-0004 TOPSOIL CLASS B	998.000 CY	_____	_____	_____	_____
0870	603	603SD20-0002 TEMPORARY SEED	180.000 LB	_____	_____	_____	_____
0880	603	603SD20-0003 REGULAR SEED	484.000 LB	_____	_____	_____	_____
0890	603	603SD20-0004 OVERSEEDING	387.000 LB	_____	_____	_____	_____
0900	603	603SD20-0005 LEGUME SEED	21.000 LB	_____	_____	_____	_____
0910	603	603SD20-0006 LEGUME OVERSEEDING	17.000 LB	_____	_____	_____	_____
0920	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	10,285.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0930	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	9,317.000 SY	_____	_____	_____	_____
0940	603	603SD20-0014 FERTILIZER NITROGEN - N	180.000 LB	_____	_____	_____	_____
0950	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	126.000 LB	_____	_____	_____	_____
0960	603	603SD20-0016 FERTILIZER POTASSIUM - K	126.000 LB	_____	_____	_____	_____
0970	603	603SD20-0017 LIME	10.000 TON	_____	_____	_____	_____
0980	605	605SD20-0001 BED PREPARATION (CONSTRUCTING PLANTING BEDS)	646.000 UNIT	_____	_____	_____	_____
0990	605	605SD20-0002 MULCHING (DOUBLE SHREDDED HARDWOOD BARK 3 INCH DEPTH)	54.000 CY	_____	_____	_____	_____
1000	605	605SX20-0018 PLANT OR TREE (ANDROPOGON GERARDII 'BLACKHAWKS' #1 CONT)	79.000 EA	_____	_____	_____	_____
1010	605	605SX20-0018 PLANT OR TREE (LIATRIS SPICATA #1 CONT)	89.000 EA	_____	_____	_____	_____
1020	605	605SX20-0018 PLANT OR TREE (LIRIOPE MUSCARI 'BIG BLUE' 2" PLUG 50 CELL)	1,529.000 EA	_____	_____	_____	_____
1030	605	605SX20-0018 PLANT OR TREE (NARCISSUS PSEUDONARCISSUS 'KING ALFRED' DN2 BULB)	269.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1040	605	605SX20-0018 PLANT OR TREE (RUDBECKIA FULGIDA 'GOLDSTURM' #1 CONT)	89.000 EA	_____	_____	_____	_____
1050	605	605SX20-0018 PLANT OR TREE (SCHIZACHYRIUM SCOPARIUM #1 CONT)	89.000 EA	_____	_____	_____	_____
1060	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	163.000 SY	_____	_____	_____	_____
1070	606	606SD20-0007 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 3	2,214.000 SY	_____	_____	_____	_____
1080	610	610SD20-0001 GABIONS	30.000 CY	_____	_____	_____	_____
1090	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	15.000 EA	_____	_____	_____	_____
1100	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1110	700	700SD20-0005 REMOVE EXISTING 3 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1120	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	1.000 EA	_____	_____	_____	_____
1130	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	210.000 LF	_____	_____	_____	_____
1140	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	102.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1150	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	88.000 LF	_____	_____	_____	_____
1160	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	156.000 LF	_____	_____	_____	_____
1170	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	30.000 EA	_____	_____	_____	_____
1180	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	11.000 EA	_____	_____	_____	_____
1190	700	700SD20-0200 SIGN POST STP-2, 4", 8 GAUGE	68.000 LF	_____	_____	_____	_____
1200	700	700SD20-0201 CONCRETE FOUNDATION STP-2, TYPE A	3.000 EA	_____	_____	_____	_____
1210	700	700SD20-0208 CONCRETE FOUNDATION STP-2, TYPE H	1.000 EA	_____	_____	_____	_____
1220	701	701SD20-0001 SIGN PANEL	651.000 SF	_____	_____	_____	_____
1230	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	1,830.000 LF	_____	_____	_____	_____
1240	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	1,401.000 LF	_____	_____	_____	_____
1250	704	704SD20-0008 TYPE B CLASS I PVMT LINE MRKG 8"	65.000 LF	_____	_____	_____	_____
1260	704	704SD20-0048 PVMT SYMB MRKG SGL TURN ARR. TY B CL II	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000123290C01

Oversight/State Project No.: 0617-037-804, C501

Order No.: B08

Federal Project No.: HIP-037-4(022)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1270	704	704SD20-0069 SYMB MRKG FISH HOOK LFT/THRU TY B CL II	2.000 EA	_____	_____	_____	_____
1280	704	704SD20-0085 PVMT SYMB MRKG YIELD 2' X 3' TY A	70.000 EA	_____	_____	_____	_____
1290	704	704SD20-0087 PVMT SYMB MRKG YIELD 2' X 3' TY B, CL II	20.000 EA	_____	_____	_____	_____
1300	704	704SD20-0108 PVMT MSG. MARK. "ONLY" TY B, CL II, 8'	1.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____