

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	105SP20-0003 CONSTRUCTION RECORD DOCUMENTS GRASS CHANNEL (SHEET 3) AND DETENTION BASIN (SHEET 84)	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0030	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	23.000 EA				
0040	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0050	302	302SD20-0013 ENDWALL EW-12	1.000 EA				
0060	302	302SD20-0023 15" PIPE	81.000 LF				
0070	302	302SD20-0025 15" CONC. PIPE	36.000 LF				
0080	302	302SD20-0028 18" PIPE	82.000 LF				
0090	302	302SD20-0030 18" CONC. PIPE	172.000 LF				
0100	302	302SD20-0037 24" PIPE	54.000 LF				
0110	302	302SD20-0039 24" CONC. PIPE	31.000 LF				
0120	302	302SD20-0047 30" PIPE	167.000 LF				
0130	302	302SD20-0057 36" PIPE	204.000 LF				

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	302	302SD20-0662 MANHOLE MH-1 OR 2	12.500 LF	_____	_____	_____	_____
0150	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0160	302	302SD20-0671 TEMP. DIVE. CHANNEL LINING CL. B	279.000 SY	_____	_____	_____	_____
0170	302	302SD20-0672 TEMP. DIVE. CHANNEL EXCAVATION	288.000 CY	_____	_____	_____	_____
0180	302	302SD20-0673 STORMWATER MAN.DRAIN.STR.SWM-1	7.000 LF	_____	_____	_____	_____
0190	ATTD	302SX20-0004 BEDDING MATL. AGGR. NO. 57	53.000 TON	_____	_____	_____	_____
0200	302	302SX20-0005 PRECAST BOX CULVERT DOUBLE 7' X 4'	20.000 LF	_____	_____	_____	_____
0210	302	302SX20-0005 PRECAST BOX CULVERT SINGLE 5' X 7'	38.000 LF	_____	_____	_____	_____
0220	302	302SX20-0013 PIPE TEMPORARY PIPE	191.000 LF	_____	_____	_____	_____
0230	ATTD	302SX20-0015 SPEC. DESIGN PERMANENT ROCK CHECK DAM	1.000 EA	_____	_____	_____	_____
0240	303	303SD20-0001 REGULAR EXCAVATION	5,688.000 CY	_____	_____	_____	_____
0250	303	303SD20-0016 MINOR STR. EXCAV. PIPE CULVERT	44.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	303	303SD20-0017 MINOR STR. EXCAV. BOX CULVERT	415.000 CY	_____	_____	_____	_____
0270	303	303SD20-0022 CHECK DAM ROCK TY. I	5.000 EA	_____	_____	_____	_____
0280	303	303SD20-0023 CHECK DAM ROCK TY. II	70.000 EA	_____	_____	_____	_____
0290	303	303SD20-0028 DEWATERING BASIN EC-8	5.000 EA	_____	_____	_____	_____
0300	303	303SD20-0029 SILTATION CONTROL EXCAVATION	2,276.000 CY	_____	_____	_____	_____
0310	303	303SD20-0030 INLET PROTECTION TYPE A	1.000 EA	_____	_____	_____	_____
0320	303	303SD20-0032 GEOTEXTILE FABRIC	132.000 SY	_____	_____	_____	_____
0330	303	303SD20-0034 TEMP. SILT FENCE TYPE A	10,423.000 LF	_____	_____	_____	_____
0340	ATTD	303SX20-0001 SOIL LIME FOR SOIL MODIFICATION	0.840 TON	_____	_____	_____	_____
0350	305	305SD20-0001 BORROW EXCAVATION	5,931.000 CY	_____	_____	_____	_____
0360	305	305SD20-0010 AGGR. MATL. NO. 1	187.000 TON	_____	_____	_____	_____
0370	305	305SD20-0011 AGGR. MATL. NO. 25 OR 26	2,970.000 TON	_____	_____	_____	_____
0380	305	305SD20-0013 AGGR. MATL. NO. 3	1,749.000 TON	_____	_____	_____	_____
0390	ATTD	305SX20-0003 AGGREGATE BASE MATERIAL NO. 10	4,191.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	315	315SD20-0008 ASPHALT CONCRETE TY. SM- 9.5D CONST	18.000 TON	_____	_____	_____	_____
0410	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	17.000 TON	_____	_____	_____	_____
0420	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	136.000 LF	_____	_____	_____	_____
0430	401	401SD20-0007 COFFERDAM	8.000 EA	_____	_____	_____	_____
0440	401	401SD20-0007 COFFERDAM (STR. 208)	2.000 EA	_____	_____	_____	_____
0450	401	401SD20-0007 COFFERDAM (STR. ORISKANY BOX)	2.000 EA	_____	_____	_____	_____
0460	401	401SD20-0007 COFFERDAM (STR. PARR BOX)	2.000 EA	_____	_____	_____	_____
0470	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. 071)	LUMP SUM	LUMP SUM		_____	_____
0480	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. 092)	LUMP SUM	LUMP SUM		_____	_____
0490	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. 208)	LUMP SUM	LUMP SUM		_____	_____
0500	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. 221)	LUMP SUM	LUMP SUM		_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. ORISKANY BOX)	LUMP SUM	LUMP SUM		_____	_____
0520	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. PARR BOX)	LUMP SUM	LUMP SUM		_____	_____
0530	407	407SD20-0019 STR.STEEL ROLLED BEAM ASTM A709 GRADE50 (STR. 071)	LUMP SUM	LUMP SUM		_____	_____
0540	407	407SD20-0019 STR.STEEL ROLLED BEAM ASTM A709 GRADE50 (STR. 092)	LUMP SUM	LUMP SUM		_____	_____
0550	407	407SD20-0019 STR.STEEL ROLLED BEAM ASTM A709 GRADE50 (STR. 208)	LUMP SUM	LUMP SUM		_____	_____
0560	407	407SD20-0019 STR.STEEL ROLLED BEAM ASTM A709 GRADE50 (STR. 221)	LUMP SUM	LUMP SUM		_____	_____
0570	ATTD	410SX20-0021 RAILING (STR. 071)	40.000 LF		_____	_____	_____
0580	ATTD	410SX20-0021 RAILING (STR. 092)	500.000 LF		_____	_____	_____
0590	ATTD	410SX20-0021 RAILING (STR. 135)	640.000 LF		_____	_____	_____
0600	ATTD	410SX20-0021 RAILING (STR. 208)	40.000 LF		_____	_____	_____
0610	ATTD	410SX20-0021 RAILING (STR. 221)	150.000 LF		_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0620	ATTD	411SX20-0004 RECOAT EX. STR. (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0630	ATTD	411SX20-0004 RECOAT EX. STR. (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0640	411	411SX20-0005 ENV. PROT. & HEALTH & SAFETY (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0650	411	411SX20-0005 ENV. PROT. & HEALTH & SAFETY (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0660	411	411SX20-0006 DISPOSAL OF MATERIAL (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0670	411	411SX20-0006 DISPOSAL OF MATERIAL (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____.	_____.
0680	412	412SD20-0013 CRACK REPAIR TYPE B (STR. 071)	80.000 LF	_____.		_____.	_____.
0690	412	412SD20-0013 CRACK REPAIR TYPE B (STR. 092)	160.000 LF	_____.		_____.	_____.
0700	412	412SD20-0013 CRACK REPAIR TYPE B (STR. 208)	90.000 LF	_____.		_____.	_____.
0710	412	412SD20-0013 CRACK REPAIR TYPE B (STR. 221)	300.000 LF	_____.		_____.	_____.
0720	412	412SD20-0013 CRACK REPAIR TYPE B (STR. ORISKANY BOX)	160.000 LF	_____.		_____.	_____.
0730	412	412SD20-0013 CRACK REPAIR TYPE B (STR. PARR BOX)	140.000 LF	_____.		_____.	_____.

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0740	412	412SD20-0045 BACK WALL RECONSTRUCTION (STR. 071)	40.000 LF	_____	_____	_____	_____
0750	412	412SD20-0045 BACK WALL RECONSTRUCTION (STR. 092)	110.000 LF	_____	_____	_____	_____
0760	412	412SD20-0045 BACK WALL RECONSTRUCTION (STR. 208)	30.000 LF	_____	_____	_____	_____
0770	412	412SD20-0045 BACK WALL RECONSTRUCTION (STR. 221)	40.000 LF	_____	_____	_____	_____
0780	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. 071)	10.000 SY	_____	_____	_____	_____
0790	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. 092)	10.000 SY	_____	_____	_____	_____
0800	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. 208)	20.000 SY	_____	_____	_____	_____
0810	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. 221)	30.000 SY	_____	_____	_____	_____
0820	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. ORISKANY BOX)	30.000 SY	_____	_____	_____	_____
0830	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. PARR BOX)	5.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0840	412	412SD20-0062 RECONSTRUCT BRIDGE SEAT TYPE A (STR. 071)	2.000 EA	_____	_____	_____	_____
0850	412	412SD20-0062 RECONSTRUCT BRIDGE SEAT TYPE A (STR. 208)	2.000 EA	_____	_____	_____	_____
0860	ATTD	412SX20-0009 BR.SUPERSTR. WID./REPAIR (RIVET REPLACEMENT STR. 092)	70.000 EA	_____	_____	_____	_____
0870	ATTD	412SX20-0017 BR. SUBSTR. WID./REPAIR (REPOINT MASONRY STR. 092)	360.000 LF	_____	_____	_____	_____
0880	ATTD	412SX20-0017 BR. SUBSTR. WID./REPAIR (SCOUR REPAIR STR. 208)	30.000 LF	_____	_____	_____	_____
0890	ATTD	412SX20-0017 BR. SUBSTR. WID./REPAIR (SCOUR REPAIR STR. ORISKANY BOX)	140.000 LF	_____	_____	_____	_____
0900	ATTD	412SX20-0017 BR. SUBSTR. WID./REPAIR (SCOUR REPAIR STR. PARR BOX)	64.000 LF	_____	_____	_____	_____
0910	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 071, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0920	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0930	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 135, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0940	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 208, TYPE B)	LUMP SUM	LUMP SUM		_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0950	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0960	413	413SX20-0004 MATERIAL DISPOSAL (STR. 071, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0970	413	413SX20-0004 MATERIAL DISPOSAL (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0980	413	413SX20-0004 MATERIAL DISPOSAL (STR. 208, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
0990	413	413SX20-0004 MATERIAL DISPOSAL (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
1000	413	413SX20-0005 REM. PORT.OF EX.STR. (STR. 071, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
1010	413	413SX20-0005 REM. PORT.OF EX.STR. (STR. 092, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
1020	413	413SX20-0005 REM. PORT.OF EX.STR. (STR. 208, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
1030	413	413SX20-0005 REM. PORT.OF EX.STR. (STR. 221, TYPE B)	LUMP SUM	LUMP SUM		_____	_____
1040	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	31.000 TON		_____	_____	_____
1050	414	414SD20-0003 EROSION CTRL. STONE CL. I, EC-1	226.000 TON		_____	_____	_____
1060	414	414SD20-0008 DRY RIPRAP CL. AI	622.000 TON		_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1070	414	414SD20-0012 DRY RIPRAP CL.I 26"	6.000 TON	_____	_____	_____	_____
1080	414	414SD20-0012 DRY RIPRAP CL.I 26" (STR. ORISKANY BOX)	47.000 TON	_____	_____	_____	_____
1090	414	414SD20-0012 DRY RIPRAP CL.I 26" (STR. PARR BOX)	26.000 TON	_____	_____	_____	_____
1100	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T (STR. 071)	30.000 SY	_____	_____	_____	_____
1110	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T (STR. 092)	70.000 SY	_____	_____	_____	_____
1120	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T (STR. 208)	30.000 SY	_____	_____	_____	_____
1130	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T (STR. 221)	90.000 SY	_____	_____	_____	_____
1140	418	418SD20-0005 LUMBER TREATED, SPR. STRUCT. MAINT. (STR. 071)	1.300 MFBM	_____	_____	_____	_____
1150	418	418SD20-0005 LUMBER TREATED, SPR. STRUCT. MAINT. (STR. 092)	20.000 MFBM	_____	_____	_____	_____
1160	418	418SD20-0005 LUMBER TREATED, SPR. STRUCT. MAINT. (STR. 208)	1.500 MFBM	_____	_____	_____	_____
1170	418	418SD20-0005 LUMBER TREATED, SPR. STRUCT. MAINT. (STR. 221)	4.700 MFBM	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1180	426	426SD20-0020 FIELD WELDING - FILLET WELD 5/16" (STR. 092)	450.000 LF	_____	_____	_____	_____
1190	426	426SD20-0020 FIELD WELDING - FILLET WELD 5/16" (STR. 221)	140.000 LF	_____	_____	_____	_____
1200	502	502SD20-0003 PAVED DITCH PG-2A	20.000 SY	_____	_____	_____	_____
1210	502	502SD20-0004 PAVED DITCH PG-5	172.000 SY	_____	_____	_____	_____
1220	502	502SD20-0011 CURB, STD. CG-2	56.000 LF	_____	_____	_____	_____
1230	502	502SD20-0014 CURB, STD. CG-3	96.000 LF	_____	_____	_____	_____
1240	502	502SD20-0015 CURB, RADIAL CG-3	58.000 LF	_____	_____	_____	_____
1250	502	502SD20-0023 COMB. CURB & GUTTER, RAD. CG-6	97.000 LF	_____	_____	_____	_____
1260	ATTD	502SX20-0010 SAW CUT H.C.C. ITEMS EXISTING CURB AND GUTTER	10.000 LF	_____	_____	_____	_____
1270	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	26.000 CY	_____	_____	_____	_____
1280	504	504SD20-0002 CG-12 DETECTABLE WARNING SURFACE	7.000 SY	_____	_____	_____	_____
1290	504	504SD20-0004 HYDR. CEMENT CONC. SIDEWALK 7"	32.000 SY	_____	_____	_____	_____
1300	505	505SD20-0011 GUARDRAIL GR-MGS1	131.250 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1310	505	505SD20-0014 RADIAL GUARDRAIL GR- MGS1	25.000 LF	_____	_____	_____	_____
1320	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
1330	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	205.000 LF	_____	_____	_____	_____
1340	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	87.000 EA	_____	_____	_____	_____
1350	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	10.000 EA	_____	_____	_____	_____
1360	507	507SD20-0005 FENCE FE-CL	412.000 LF	_____	_____	_____	_____
1370	507	507SD20-0012 GATE FE-CL 10'	2.000 EA	_____	_____	_____	_____
1380	ATTD	507SX20-0013 FENCE MODIFIED FE-W1 WOODEN POST	2,513.000 LF	_____	_____	_____	_____
1390	ATTD	507SX20-0019 GATE TRAIL GATE	17.000 EA	_____	_____	_____	_____
1400	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	160.000 SY	_____	_____	_____	_____
1410	ATTD	510SX20-0002 REMOVE COMB. CURB AND GUTTER	98.000 LF	_____	_____	_____	_____
1420	510	510SX20-0016 REMOVE EXIST. FENCE CHAIN LINK	413.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1430	ATTD	510SX20-0040 REMOVE EXIST. PIPE GATE	2.000 EA	_____	_____	_____	_____
1440	510	510SX20-0046 ADJUST EXIST. METER BOX	1.000 EA	_____	_____	_____	_____
1450	512	512SD20-0014 TEMPORARY SIGN	352.000 SF	_____	_____	_____	_____
1460	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,000.000 HR	_____	_____	_____	_____
1470	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	5,481.000 DAY	_____	_____	_____	_____
1480	512	512SD20-0027 FLAGGER SERVICE	500.000 HR	_____	_____	_____	_____
1490	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	262.000 LF	_____	_____	_____	_____
1500	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
1510	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	59.000 SY	_____	_____	_____	_____
1520	517	517SD20-0002 CONSTRUCTION SURVEYING MIN. PLAN	LUMP SUM	LUMP SUM	_____	_____	_____
1530	602	602SD20-0005 TOPSOIL CLASS A 2"	4.250 ACRE	_____	_____	_____	_____
1540	602	602SD20-0005 TOPSOIL CLASS B 2"	1.620 ACRE	_____	_____	_____	_____
1550	602	602SD20-0006 TOPSOIL 4" DEPTH, GRASS CHANNEL (SHEET 3) AND DETENTION BASIN (SHEET 84)	163.000 CY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1560	603	603SD20-0002 TEMPORARY SEED	1,163.000 LB	_____	_____	_____	_____
1570	603	603SD20-0003 REGULAR SEED	2,142.000 LB	_____	_____	_____	_____
1580	603	603SD20-0004 OVERSEEDING	1,714.000 LB	_____	_____	_____	_____
1590	603	603SD20-0005 LEGUME SEED	100.000 LB	_____	_____	_____	_____
1600	603	603SD20-0006 LEGUME OVERSEEDING	80.000 LB	_____	_____	_____	_____
1610	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	39,023.000 SY	_____	_____	_____	_____
1620	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	65,486.000 SY	_____	_____	_____	_____
1630	603	603SD20-0011 SEDIMENT RETENTION ROLL 18" MIN	2,416.000 LF	_____	_____	_____	_____
1640	603	603SD20-0014 FERTILIZER NITROGEN - N	870.000 LB	_____	_____	_____	_____
1650	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	633.000 LB	_____	_____	_____	_____
1660	603	603SD20-0016 FERTILIZER POTASSIUM - K	633.000 LB	_____	_____	_____	_____
1670	603	603SD20-0017 LIME	51.160 TON	_____	_____	_____	_____
1680	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	1,616.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1690	606	606SD20-0002 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 2	262.000 SY	_____	_____	_____	_____
1700	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	172.000 SY	_____	_____	_____	_____
1710	700	700SD20-0001 SIGN POST WOOD 4" X 4"	1,568.500 LF	_____	_____	_____	_____
1720	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	3.000 EA	_____	_____	_____	_____
1730	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	667.250 LF	_____	_____	_____	_____
1740	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	8.250 LF	_____	_____	_____	_____
1750	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	78.000 EA	_____	_____	_____	_____
1760	ATTD	700SX20-0010 TRAFFIC SIGNALIZATION SOLAR POWERED RECTANGULAR RAPID FLASHING BEACON	2.000 EA	_____	_____	_____	_____
1770	ATTD	700SX20-0021 TRAFFIC SIGN MILE MARKER POST	19.000 EA	_____	_____	_____	_____
1780	ATTD	700SX20-0021 TRAFFIC SIGN REMOVABLE BOLLARD	17.000 EA	_____	_____	_____	_____
1790	701	701SD20-0001 SIGN PANEL	951.710 SF	_____	_____	_____	_____
1800	704	704SD20-0012 TYPE B CLASS II PVMT LINE MRKG 6"	213.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 17

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1810	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	290.000 LF				
Section: 0001				Total:			

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0002

ADDITIVE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1820	303	303SD20-0029 SILTATION CONTROL EXCAVATION	168.000 CY	_____	_____	_____	_____
1830	303	303SD20-0034 TEMP. SILT FENCE TYPE A	983.000 LF	_____	_____	_____	_____
1840	305	305SD20-0013 AGGR. MATL. NO. 3	5.000 TON	_____	_____	_____	_____
1850	ATTD	305SX20-0003 AGGREGATE BASE MATERIAL NO. 10	308.000 TON	_____	_____	_____	_____
1860	ATTD	308SX20-0003 CRUSHER RUN AGGR. NO. 25 OR 26	6.000 TON	_____	_____	_____	_____
1870	401	401SD20-0007 COFFERDAM	1.000 EA	_____	_____	_____	_____
1880	ATTD	401SX20-0001 BRIDGE (TEMPORARY CONSTRUCTION ACCESS STR. 066)	LUMP SUM	LUMP SUM	_____	_____	_____
1890	407	407SD20-0019 STR. STEEL ROLLED BEAM ASTM A709 GRADE50 (STR. 066)	LUMP SUM	LUMP SUM	_____	_____	_____
1900	ATTD	410SX20-0021 RAILING (STR. 066)	530.000 LF	_____	_____	_____	_____
1910	ATTD	411SX20-0004 RECOAT EX. STR. (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
1920	411	411SX20-0005 ENV. PROT. & HEALTH & SAFETY (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
1930	411	411SX20-0006 DISPOSAL OF MATERIAL (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0002

ADDITIVE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1940	412	412SD20-0013 CRACK REPAIR TYPE B (STR. 066)	440.000 LF	_____	_____	_____	_____
1950	412	412SD20-0045 BACK WALL RECONSTRUCTION (STR. 066)	30.000 LF	_____	_____	_____	_____
1960	412	412SD20-0061 CONCRETE SUBSTRUCT. SURFACE REPAIR (STR. 066)	50.000 SY	_____	_____	_____	_____
1970	ATTD	412SX20-0009 BR.SUPERSTR. WID./REPAIR (REPLACE LATERAL BRACING STR. 066)	1.000 EA	_____	_____	_____	_____
1980	ATTD	412SX20-0009 BR.SUPERSTR. WID./REPAIR (RIVET REPLACEMENT STR. 066)	70.000 EA	_____	_____	_____	_____
1990	ATTD	412SX20-0017 BR. SUBSTR. WID./REPAIR (SCOUR REPAIR STR. 066)	6.000 LF	_____	_____	_____	_____
2000	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
2010	413	413SX20-0004 MATERIAL DISPOSAL (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
2020	413	413SX20-0005 REM. PORT.OF EX.STR. (STR. 066, TYPE B)	LUMP SUM	LUMP SUM	_____	_____	_____
2030	416	416SD20-0003 WATERPROOFING – EPOXY RESIN TYPE EP-3B/EP-3T (STR. 066)	60.000 SY	_____	_____	_____	_____
2040	418	418SD20-0005 LUMBER TREATED, SPR. STRUCT. MAINT. (STR. 066)	19.000 MFBM	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0002

ADDITIVE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2050	426	426SD20-0001 REPLACE BEARING (STR. 066)	2.000 EA	_____	_____	_____	_____
2060	426	426SD20-0020 FIELD WELDING - FILLET WELD 5/16" (STR. 066)	270.000 LF	_____	_____	_____	_____
2070	426	426SD20-0028 JACKING AND BLOCKING BEAM (STR. 066)	2.000 EA	_____	_____	_____	_____
2080	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	10.000 EA	_____	_____	_____	_____
2090	ATTD	507SX20-0013 FENCE MODIFIED FE-W1 WOODEN POST	208.000 LF	_____	_____	_____	_____
2100	ATTD	507SX20-0019 GATE TRAIL GATE	1.000 EA	_____	_____	_____	_____
2110	ATTD	510SX20-0040 REMOVE EXIST. PIPE GATE	1.000 EA	_____	_____	_____	_____
2120	602	602SD20-0005 TOPSOIL CLASS A 2"	0.100 ACRE	_____	_____	_____	_____
2130	602	602SD20-0005 TOPSOIL CLASS B 2"	0.040 ACRE	_____	_____	_____	_____
2140	603	603SD20-0002 TEMPORARY SEED	43.000 LB	_____	_____	_____	_____
2150	603	603SD20-0003 REGULAR SEED	81.000 LB	_____	_____	_____	_____
2160	603	603SD20-0004 OVERSEEDING	65.000 LB	_____	_____	_____	_____
2170	603	603SD20-0005 LEGUME SEED	4.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

SECTION: 0002

ADDITIVE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
2180	603	603SD20-0006 LEGUME OVERSEEDING	3.000 LB	_____	_____	_____	_____
2190	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	726.000 SY	_____	_____	_____	_____
2200	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	3,170.000 SY	_____	_____	_____	_____
2210	603	603SD20-0014 FERTILIZER NITROGEN - N	33.000 LB	_____	_____	_____	_____
2220	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	24.000 LB	_____	_____	_____	_____
2230	603	603SD20-0016 FERTILIZER POTASSIUM - K	24.000 LB	_____	_____	_____	_____
2240	603	603SD20-0017 LIME	1.910 TON	_____	_____	_____	_____
2250	700	700SD20-0001 SIGN POST WOOD 4" X 4"	69.000 LF	_____	_____	_____	_____
2260	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	14.000 LF	_____	_____	_____	_____
2270	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	2.000 EA	_____	_____	_____	_____
2280	ATTD	700SX20-0021 TRAFFIC SIGN MILE MARKER POST	1.000 EA	_____	_____	_____	_____
2290	ATTD	700SX20-0021 TRAFFIC SIGN REMOVABLE BOLLARD	1.000 EA	_____	_____	_____	_____
2300	701	701SD20-0001 SIGN PANEL	27.210 SF	_____	_____	_____	_____

Proposal ID: C0000122492C01

Oversight/State Project No.: TOCB-011-858, M501

Order No.: B02

Federal Project No.: HIP-011-2(038)

Contractor: _____

Section: 0002

Total: _____

Total Bid: _____