

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM		_____	_____
0020	302	302SD20-0013 ENDWALL EW-12	5.000 EA	_____	_____	_____	_____
0030	302	302SD20-0027 15" STORM SEWER PIPE	104.000 LF	_____	_____	_____	_____
0040	302	302SD20-0239 DROP INLET DI-2A	1.000 EA	_____	_____	_____	_____
0050	302	302SD20-0244 DROP INLET DI-2B,L=10'	1.000 EA	_____	_____	_____	_____
0060	302	302SD20-0245 DROP INLET DI-2B,L=12'	1.000 EA	_____	_____	_____	_____
0070	302	302SD20-0662 MANHOLE MH-1 OR 2	14.000 LF	_____	_____	_____	_____
0080	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA	_____	_____	_____	_____
0090	ATTD	302SX20-0022 DRAINAGE (LEVEL SPREADER 6"X6" WOOD POST)	1.000 EA	_____	_____	_____	_____
0100	303	303SD20-0001 REGULAR EXCAVATION	2,714.000 CY	_____	_____	_____	_____
0110	303	303SD20-0007 BORROW EXCAVATION	1,123.000 CY	_____	_____	_____	_____
0120	303	303SD20-0022 CHECK DAM ROCK TY. I	20.000 EA	_____	_____	_____	_____
0130	303	303SD20-0023 CHECK DAM ROCK TY. II	13.000 EA	_____	_____	_____	_____
0140	303	303SD20-0024 CHECK DAM SEDIMENT RETENTION ROLL 18"	2.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0029 SILTATION CONTROL EXCAVATION	2,953.000 CY	_____	_____	_____	_____
0160	303	303SD20-0031 INLET PROTECTION TYPE B	12.000 EA	_____	_____	_____	_____
0170	303	303SD20-0034 TEMP. SILT FENCE TYPE A	16,436.000 LF	_____	_____	_____	_____
0180	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	1,297.000 TON	_____	_____	_____	_____
0190	315	315SD20-0001 ASPHALT CONCRETE TY. SM- 12.5A CONST	324.000 TON	_____	_____	_____	_____
0200	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	610.000 TON	_____	_____	_____	_____
0210	315	315SD20-0009 ASPHALT CONCRETE TY. SM- 9.5E CONST	1,180.000 TON	_____	_____	_____	_____
0220	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	648.000 TON	_____	_____	_____	_____
0230	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	5,666.000 LF	_____	_____	_____	_____
0240	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	854.000 SY	_____	_____	_____	_____
0250	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	20.000 TON	_____	_____	_____	_____
0260	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	11,464.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	ATTD	315SX20-0007 ASPHALT CONCRETE - ASPHALT CONCRETE TY. BM- 25.0A CONST	1,045.000 TON	_____	_____	_____	_____
0280	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	2.000 TON	_____	_____	_____	_____
0290	414	414SD20-0012 DRY RIPRAP CL.I 26"	16.100 TON	_____	_____	_____	_____
0300	501	501SD20-0004 UNDERDRAIN UD-4	1,520.000 LF	_____	_____	_____	_____
0310	501	501SD20-0009 OUTLET PIPE	49.000 LF	_____	_____	_____	_____
0320	502	502SD20-0020 CURB, ASPHALT MC-3B	481.000 LF	_____	_____	_____	_____
0330	302, 504	504SD20-0001 CONCRETE CLASS A3 MISC.	1.700 CY	_____	_____	_____	_____
0340	504	504SD20-0005 GEOTEXTILE DRAINAGE FABRIC	20.800 SY	_____	_____	_____	_____
0350	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	3,393.000 LF	_____	_____	_____	_____
0360	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	4.000 EA	_____	_____	_____	_____
0370	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	5.000 EA	_____	_____	_____	_____
0380	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	7.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	505	505SD20-0047 FIXED OBJECT ATTACH. GR- FOA-3 TY. I	3.000 EA	_____	_____	_____	_____
0400	505	505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II	2.000 EA	_____	_____	_____	_____
0410	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	3,152.000 LF	_____	_____	_____	_____
0420	508	508SD20-0003 DEMO. OF PAVEMENT RIGID	528.000 SY	_____	_____	_____	_____
0430	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	2,641.000 SY	_____	_____	_____	_____
0440	510	510SX20-0039 REMOVE EXIST. (CONDUIT)	592.000 LF	_____	_____	_____	_____
0450	510	510SX20-0040 REMOVE EXIST. OVERHEAD SIGN STRUCTURE TRAFFIC	3.000 EA	_____	_____	_____	_____
0460	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	3.000 EA	_____	_____	_____	_____
0470	512	512SD20-0013 TYPE 3 BARRICADE 8'	2.000 EA	_____	_____	_____	_____
0480	512	512SD20-0014 TEMPORARY SIGN	1,950.000 SF	_____	_____	_____	_____
0490	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	4,822.000 HR	_____	_____	_____	_____
0500	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	23,824.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	10,110.000 HR	_____	_____	_____	_____
0520	512	512SD20-0026 ELECTRONIC ARROW BOARD	4,294.000 HR	_____	_____	_____	_____
0530	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	2,329.000 LF	_____	_____	_____	_____
0540	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	48,485.000 LF	_____	_____	_____	_____
0550	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	1,282.000 EA	_____	_____	_____	_____
0560	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	10,205.000 LF	_____	_____	_____	_____
0570	512	512SD20-0048 TEMP. PVMT MRKG TY. A, 8"	1,305.000 LF	_____	_____	_____	_____
0580	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	23,800.000 LF	_____	_____	_____	_____
0590	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	12,815.000 LF	_____	_____	_____	_____
0600	512	512SD20-0064 TEMP. PVMT MRKG TY. D, CL. III, 12"	5,105.000 LF	_____	_____	_____	_____
0610	512	512SD20-0065 TEMP. PVMT MRKG TY. D, CL. III, 24"	130.000 LF	_____	_____	_____	_____
0620	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0630	514	514SD20-0001 FIELD OFFICE TY.I	17.000 MO	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	8,049.000 SY	_____	_____	_____	_____
0650	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
0660	602	602SD20-0005 TOPSOIL CLASS B 2"	0.490 ACRE	_____	_____	_____	_____
0670	603	603SD20-0002 TEMPORARY SEED	49.000 LB	_____	_____	_____	_____
0680	603	603SD20-0003 REGULAR SEED	70.000 LB	_____	_____	_____	_____
0690	603	603SD20-0004 OVERSEEDING	56.000 LB	_____	_____	_____	_____
0700	603	603SD20-0005 LEGUME SEED	1.000 LB	_____	_____	_____	_____
0710	603	603SD20-0006 LEGUME OVERSEEDING	1.000 LB	_____	_____	_____	_____
0720	603	603SD20-0014 FERTILIZER NITROGEN - N	47.000 LB	_____	_____	_____	_____
0730	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	64.000 LB	_____	_____	_____	_____
0740	603	603SD20-0016 FERTILIZER POTASSIUM - K	32.000 LB	_____	_____	_____	_____
0750	603	603SD20-0017 LIME	2.200 TON	_____	_____	_____	_____
0760	606	606SD20-0005 ROLLED EROSION CTRL PRODUCT EC-3 TYPE 1	242.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	10.000 EA	_____	_____	_____	_____
0780	700	700SD20-0035 SIGN POST STP-1, 2 3/16", 10 GAUGE	12.000 LF	_____	_____	_____	_____
0790	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	60.000 LF	_____	_____	_____	_____
0800	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	15.000 LF	_____	_____	_____	_____
0810	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	1.000 EA	_____	_____	_____	_____
0820	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	4.000 EA	_____	_____	_____	_____
0830	700	700SD20-0056 CONC. FOUND. O/H SIGN STRUCTURE	165.000 CY	_____	_____	_____	_____
0840	700	700SD20-0174 ELECTRICAL SERVICE WORK PAD	2.000 EA	_____	_____	_____	_____
0850	700	700SD20-0199 TEST BORE	6.000 EA	_____	_____	_____	_____
0860	700	700SX20-0002 SIGN STRUCTURE, OVERHEAD SPAN 133 FT	1.000 EA	_____	_____	_____	_____
0870	700	700SX20-0002 SIGN STRUCTURE, OVERHEAD SPAN 74 FT	1.000 EA	_____	_____	_____	_____
0880	700	700SX20-0002 SIGN STRUCTURE, OVERHEAD SPAN 86 FT	1.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000119597C01B Oversight/State Project No.: 0076-964-927, C501

Order No.: A23

Federal Project No.: STP-5A27(864)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0890	ATTD	700SX20-0021 TRAFFIC SIGN SOLAR POWERED FLASHING BEACON WARNING SYSTEM	2.000 EA	_____	_____	_____	_____
0900	ATTD	700SX20-0021 TRAFFIC SIGN SOLAR POWERED SEQUENTIAL DYNAMIC CURVE WARNING SYSTEM (CHEVRON)	4.000 EA	_____	_____	_____	_____
0910	701	701SD20-0001 SIGN PANEL	2,000.000 SF	_____	_____	_____	_____
0920	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	10,205.000 LF	_____	_____	_____	_____
0930	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	1,305.000 LF	_____	_____	_____	_____
0940	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	565.000 LF	_____	_____	_____	_____
0950	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	147.000 EA	_____	_____	_____	_____
0960	704	704SX20-0001 PAVEMENT MARKING TYPE B CLASS VI PVMT LINE MRKG 24"	54.000 LF	_____	_____	_____	_____
0970	ATTD	705SX20-0002 LIGHTING #2 IN LINE SPLICES	12.000 EA	_____	_____	_____	_____
0980	ATTD	705SX20-0002 LIGHTING TAPE AND LABELS	36.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____