

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	108SP20-0001 BASELINE PROGRESS SCHEDULE	LUMP SUM	LUMP SUM			
0020	ATTD	108SP20-0002 PROGRESS SCHEDULE UPDATES	30.000 EA				
0030	301	301SD20-0001 CLEARING AND GRUBBING	LUMP SUM	LUMP SUM			
0040	302	302SD20-0013 ENDWALL EW-12	6.000 EA				
0050	302	302SD20-0027 15" STORM SEWER PIPE	180.000 LF				
0060	302	302SD20-0032 18" STORM SEWER PIPE	41.000 LF				
0070	302	302SD20-0041 24" STORM SEWER PIPE	69.000 LF				
0080	302	302SD20-0198 15" END SECTION ES-1 OR 2	1.000 EA				
0090	302	302SD20-0204 24" END SECTION ES-1 OR 2	1.000 EA				
0100	302	302SD20-0446 DROP INLET DI-5	1.000 EA				
0110	302	302SD20-0456 DROP INLET DI-10H TY. I,L=10'	1.000 EA				
0120	302	302SD20-0663 FRAME & COVER MH-1	1.000 EA				
0130	303	303SD20-0001 REGULAR EXCAVATION	17,293.000 CY				
0140	303	303SD20-0007 BORROW EXCAVATION	5,147.000 CY				

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0023 CHECK DAM ROCK TY. II	14.000 EA	_____	_____	_____	_____
0160	303	303SD20-0028 DEWATERING BASIN EC-8	2.000 EA	_____	_____	_____	_____
0170	303	303SD20-0029 SILTATION CONTROL EXCAVATION	1,084.000 CY	_____	_____	_____	_____
0180	303	303SD20-0030 INLET PROTECTION TYPE A	6.000 EA	_____	_____	_____	_____
0190	303	303SD20-0031 INLET PROTECTION TYPE B	14.000 EA	_____	_____	_____	_____
0200	303	303SD20-0033 TEMP. SILT FENCE TYPE B	334.000 LF	_____	_____	_____	_____
0210	303	303SD20-0034 TEMP. SILT FENCE TYPE A	5,028.000 LF	_____	_____	_____	_____
0220	305	305SD20-0005 SELECT MATL. TY. I MIN. CBR- 30	16,535.000 TON	_____	_____	_____	_____
0230	305	305SD20-0009 GEOTEXTILE SUBGRADE STAB.	26,728.000 SY	_____	_____	_____	_____
0240	307	307SD20-0002 CEM. STAB. AGGR. MATL. NO. 21A	4,425.000 TON	_____	_____	_____	_____
0250	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	8,948.000 TON	_____	_____	_____	_____
0260	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	4,567.000 TON	_____	_____	_____	_____
0270	315	315SD20-0009 ASPHALT CONCRETE TY. SM- 9.5E CONST	4,703.000 TON	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0280	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	7,595.000 TON	_____	_____	_____	_____
0290	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	12,168.000 LF	_____	_____	_____	_____
0300	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE (18 IN. DEPTH)	14,579.000 LF	_____	_____	_____	_____
0310	316	316SD20-0035 CONC. CL. A4 BRIDGE APPR. SLAB CONST.	153.800 CY	_____	_____	_____	_____
0320	316	316SD20-0036 REINF. STEEL BRIDGE APPR. SLAB CONST.	33,940.000 LB	_____	_____	_____	_____
0330	401	401SD20-0001 STRUCTURE EXCAVATION CONST.	4,931.000 CY	_____	_____	_____	_____
0340	401	401SD20-0002 SELECT BACKFILL ABUTMENT ZONE	6,361.000 TON	_____	_____	_____	_____
0350	401	401SD20-0004 GEOCOMPOSITE WALL DRAIN	373.000 SY	_____	_____	_____	_____
0360	401	401SD20-0007 COFFERDAM	6.000 EA	_____	_____	_____	_____
0370	ATTD	401SX20-0005 BRIDGE SUBSTRUCTURE ROCK SOCKET DRILLED SHAFT (48" DIA)	217.000 LF	_____	_____	_____	_____
0380	ATTD	401SX20-0005 BRIDGE SUBSTRUCTURE STANDARD EXCAV DRILLED SHAFT (48" DIA)	43.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0390	ATTD	401SX20-0008 BRIDGE SUBSTRUCTURE CROSSHOLE SONIC LOGGING (CSL) TESTING	48.000 EA	_____	_____	_____	_____
0400	ATTD	401SX20-0011 BRIDGE SUBSTRUCTURE TEMPORARY SHORING	LUMP SUM	LUMP SUM		_____	_____
0410	403	403SD20-0006 STEEL PILES 12"	1,373.000 LF	_____	_____	_____	_____
0420	403	403SD20-0007 STEEL PILES 14"	3,381.000 LF	_____	_____	_____	_____
0430	ATTD	403SX20-0016 PREBORING PILE 12" STEEL PILE	1,312.000 LF	_____	_____	_____	_____
0440	ATTD	403SX20-0016 PREBORING PILE 14" STEEL PILE	3,312.000 LF	_____	_____	_____	_____
0450	404	404SD20-0005 CONC. CL. A4 MOD. LOW SHRINK., SPR. STRUCT. CONST.	887.000 CY	_____	_____	_____	_____
0460	404	404SD20-0009 BRIDGE DECK GROOVING CONST.	3,138.000 SY	_____	_____	_____	_____
0470	404	404SD20-0010 COVER DEPTH SURVEY CONST.	3,138.000 SY	_____	_____	_____	_____
0480	404	404SD20-0011 CONCRETE CLASS A3, SUBSTRUCT. CONST.	1,195.100 CY	_____	_____	_____	_____
0490	406	406SD20-0005 CR REINF. STEEL CL. III SPR. STRUCT. CONST.	213,780.000 LB	_____	_____	_____	_____
0500	406	406SD20-0006 REINFORCING STEEL SUBSTRUCT. CONST.	140,810.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0510	407	407SD20-0014 STR.STEEL PLATE GIRDER ASTM A709 GRADE50	LUMP SUM	LUMP SUM			
0520	410	410SD20-0022 BRDG.MED.BARR.CAST-IN- PLACE CONC.F-SHAPE	232.000 LF				
0530	410	410SD20-0056 CONCRETE PARAPET BPB-4	468.000 LF				
0540	413	413SX20-0002 DISM.& REM. EX. STR. (STR. NO. 2053)	LUMP SUM	LUMP SUM			
0550	413	413SX20-0003 ENV.& WORKER PROTECT. (STR. NO. 2053)	LUMP SUM	LUMP SUM			
0560	413	413SX20-0004 MATERIAL DISPOSAL (STR. NO. 2053, TYPE B)	LUMP SUM	LUMP SUM			
0570	414	414SD20-0001 EROSION CTRL. STONE CL. A1, EC-1	4.200 TON				
0580	414	414SD20-0012 DRY RIPRAP CL.I 26"	3,929.000 TON				
0590	414	414SD20-0053 EROSION CONTROL RIPRAP	88.000 TON				
0600	414	414SD20-0057 DRY RIPRAP CL.II 38"	912.000 TON				
0610	430	430SX20-0001 NBIS ACCESS, UNDER BRIDGE (STR. NO. 2053)	3.000 DAY				
0620	501	501SD20-0004 UNDERDRAIN UD-4	2,547.000 LF				
0630	501	501SD20-0007 CROSSDRAIN CD-2	351.000 LF				

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0640	501	501SD20-0009 OUTLET PIPE	101.000 LF	_____	_____	_____	_____
0650	502	502SD20-0014 CURB, STD. CG-3	109.000 LF	_____	_____	_____	_____
0660	502	502SD20-0036 MEDIAN BARRIER MB-7D	621.000 LF	_____	_____	_____	_____
0670	502	502SD20-0044 MEDIAN BARRIER MB-8A TYPE I	1,283.000 LF	_____	_____	_____	_____
0680	502	502SD20-0045 MEDIAN BARRIER MB-8A TYPE II	700.000 LF	_____	_____	_____	_____
0690	505	505SD20-0004 INSTALL SALV. GUARDRAIL	25.000 LF	_____	_____	_____	_____
0700	505	505SD20-0008 ADJUST EXISTING GUARDRAIL BEAM	150.000 LF	_____	_____	_____	_____
0710	505	505SD20-0011 GUARDRAIL GR-MGS1	2,514.000 LF	_____	_____	_____	_____
0720	505	505SD20-0013 GUARDRAIL GR-MGS1, 9' POST	1,769.000 LF	_____	_____	_____	_____
0730	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	6.000 EA	_____	_____	_____	_____
0740	505	505SD20-0040 GUARDRAIL GR-10	25.000 LF	_____	_____	_____	_____
0750	505	505SD20-0054 FIXED OBJECT ATTACH. GR- FOA-2 TY. II	1.000 EA	_____	_____	_____	_____
0760	505	505SD20-0055 FIXED OBJECT ATTACH. GR- FOA-5	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0770	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	4,355.000 LF	_____	_____	_____	_____
0780	507	507SD20-0001 FENCE FE-W1	833.000 LF	_____	_____	_____	_____
0790	507	507SD20-0003 LINE BRACE UNIT FE-W1 OR FE-W2	6.000 EA	_____	_____	_____	_____
0800	507	507SD20-0004 CORNER BRACE UNIT FE-W1 OR FE-W2	5.000 EA	_____	_____	_____	_____
0810	508	508SD20-0004 DEMO. OF PAVEMENT FLEXIBLE	20,793.000 SY	_____	_____	_____	_____
0820	509	509SD20-0001 FLOWABLE BACKFILL	10.000 CY	_____	_____	_____	_____
0830	510	510SX20-0016 REMOVE EXIST. FENCE FENCE	794.000 LF	_____	_____	_____	_____
0840	510	510SX20-0031 MODIFY EXIST. CONV. EX. DROP INLET OT MANHOLE	1.000 EA	_____	_____	_____	_____
0850	510	510SX20-0033 ADJUST EXIST. DROP INLET MODIFY EXIST. CONCRETE MEDIAN BARRIER INLET	7.000 EA	_____	_____	_____	_____
0860	510	510SX20-0039 REMOVE EXIST. CONCRETE BARRIER	2,611.000 LF	_____	_____	_____	_____
0870	511	511SD20-0001 ALLAYING DUST	210.000 HR	_____	_____	_____	_____
0880	512	512SD20-0003 TRAFFIC BARRIER SERVICE MB-11A	13,997.000 LF	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0890	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	13.000 EA	_____	_____	_____	_____
0900	512	512SD20-0013 TYPE 3 BARRICADE 8'	5.000 EA	_____	_____	_____	_____
0910	512	512SD20-0014 TEMPORARY SIGN	1,408.000 SF	_____	_____	_____	_____
0920	512	512SD20-0023 TRUCK MOUNTED ATTENUATOR	1,958.000 HR	_____	_____	_____	_____
0930	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	94,122.000 DAY	_____	_____	_____	_____
0940	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	4,032.000 HR	_____	_____	_____	_____
0950	512	512SD20-0026 ELECTRONIC ARROW BOARD	1,810.000 HR	_____	_____	_____	_____
0960	512	512SD20-0027 FLAGGER SERVICE	672.000 HR	_____	_____	_____	_____
0970	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	5,812.000 LF	_____	_____	_____	_____
0980	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	1,052.000 EA	_____	_____	_____	_____
0990	512	512SD20-0062 TEMP. PVMT MRKG TY. D, CL. III, 6"	21,501.000 LF	_____	_____	_____	_____
1000	512	512SD20-0063 TEMP. PVMT MRKG TY. D, CL. III, 8"	42,064.000 LF	_____	_____	_____	_____
1010	ATTD	512SP20-0001 PORTABLE TEMPORARY RUMBLE STRIP ARRAY	28.000 DAY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1020	ATTD	512SX20-0040 POLICE PATROL LOCAL POLICE	320.000 HR	_____	_____	_____	_____
1030	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM		_____	_____
1040	514	514SD20-0001 FIELD OFFICE TY.I	30.000 MO	_____	_____	_____	_____
1050	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	35,111.000 SY	_____	_____	_____	_____
1060	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM		_____	_____
1070	603	603SD20-0002 TEMPORARY SEED	68.000 LB	_____	_____	_____	_____
1080	603	603SD20-0003 REGULAR SEED	303.000 LB	_____	_____	_____	_____
1090	603	603SD20-0004 OVERSEEDING	242.000 LB	_____	_____	_____	_____
1100	603	603SD20-0005 LEGUME SEED	13.000 LB	_____	_____	_____	_____
1110	603	603SD20-0006 LEGUME OVERSEEDING	10.000 LB	_____	_____	_____	_____
1120	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	1,997.000 SY	_____	_____	_____	_____
1130	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	7,405.000 SY	_____	_____	_____	_____
1140	603	603SD20-0014 FERTILIZER NITROGEN - N	94.000 LB	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1150	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	64.000 LB	_____	_____	_____	_____
1160	603	603SD20-0016 FERTILIZER POTASSIUM - K	64.000 LB	_____	_____	_____	_____
1170	603	603SD20-0017 LIME	4.900 TON	_____	_____	_____	_____
1180	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	12.000 EA	_____	_____	_____	_____
1190	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	3.000 EA	_____	_____	_____	_____
1200	700	700SD20-0012 RELOCATE EX. 1 POST GRND MOUNT SGN PANEL	16.000 EA	_____	_____	_____	_____
1210	700	700SD20-0013 RELOCATE EX. 2 POST GRND MOUNT SGN PANEL	4.000 EA	_____	_____	_____	_____
1220	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	123.000 LF	_____	_____	_____	_____
1230	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	120.000 LF	_____	_____	_____	_____
1240	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	23.000 EA	_____	_____	_____	_____
1250	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	19.000 EA	_____	_____	_____	_____
1260	700	700SD20-0200 SIGN POST STP-2, 4", 8 GAUGE	89.000 LF	_____	_____	_____	_____

Schedule of Items

Page: 12

Proposal ID: C0000120814B32

Oversight/State Project No.: 0066-030-543, B632

Order No.: A98

Federal Project No.: BFP-066-1(376)

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
1270	700	700SD20-0208 CONCRETE FOUNDATION STP-2, TYPE H	4.000 EA	_____	_____	_____	_____
1280	701	701SD20-0001 SIGN PANEL	283.000 SF	_____	_____	_____	_____
1290	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	1,944.000 LF	_____	_____	_____	_____
1300	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	17,544.000 LF	_____	_____	_____	_____
1310	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	1,548.000 LF	_____	_____	_____	_____
1320	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	69.000 EA	_____	_____	_____	_____
1330	510	704SP20-0001 REMOVAL OF SRPM	38.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____