

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	302	302SD20-0013 ENDWALL EW-12	9.000 EA	_____	_____	_____	_____
0020	302	302SD20-0041 24" STORM SEWER PIPE	24.000 LF	_____	_____	_____	_____
0030	302	302SD20-0132 23" X 14" ELLIPTICAL PIPE	92.000 LF	_____	_____	_____	_____
0040	302	302SD20-0205 24" END SECTION ES-1	1.000 EA	_____	_____	_____	_____
0050	302	302SD20-0221 23" X 14" END SECTION ES-1A	1.000 EA	_____	_____	_____	_____
0060	302	302SD20-0446 DROP INLET DI-5	1.000 EA	_____	_____	_____	_____
0070	302	302SD20-0449 DROP INLET DI-7B	1.000 EA	_____	_____	_____	_____
0080	302	302SD20-0663 FRAME & COVER MH-1	2.000 EA	_____	_____	_____	_____
0090	303	303SD20-0001 REGULAR EXCAVATION	4,500.000 CY	_____	_____	_____	_____
0100	303	303SD20-0022 CHECK DAM ROCK TY. I	30.000 EA	_____	_____	_____	_____
0110	303	303SD20-0023 CHECK DAM ROCK TY. II	372.000 EA	_____	_____	_____	_____
0120	303	303SD20-0029 SILTATION CONTROL EXCAVATION	3,062.000 CY	_____	_____	_____	_____
0130	303	303SD20-0030 INLET PROTECTION TYPE A	28.000 EA	_____	_____	_____	_____
0140	303	303SD20-0031 INLET PROTECTION TYPE B	23.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0150	303	303SD20-0034 TEMP. SILT FENCE TYPE A	15,192.000 LF	_____	_____	_____	_____
0160	305	305SD20-0001 BORROW EXCAVATION	24,500.000 CY	_____	_____	_____	_____
0170	308	308SD20-0012 AGGR. BASE MATL. TY. I NO. 21B	10,832.000 TON	_____	_____	_____	_____
0180	315	315SD20-0002 ASPHALT CONCRETE TY. SM- 12.5D CONST	79.000 TON	_____	_____	_____	_____
0190	315	315SD20-0003 ASPHALT CONCRETE TY. SM- 12.5E CONST	5,651.000 TON	_____	_____	_____	_____
0200	315	315SD20-0005 ASPHALT CONCRETE TY. IM- 19.0D CONST	5,426.000 TON	_____	_____	_____	_____
0210	315	315SD20-0010 ASPHALT CONCRETE BM-25.0	7,804.000 TON	_____	_____	_____	_____
0220	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	11,305.000 LF	_____	_____	_____	_____
0230	315	315SD20-0016 LIQUID ASPHALT COATING (RUMBLE STRIP)	2,094.000 SY	_____	_____	_____	_____
0240	315	315SD20-0018 ASPH.CONC.CURB BACKUP MATL. CONST	17.000 TON	_____	_____	_____	_____
0250	315	315SD20-0104 SAW-CUT ASPHALT CONCRETE FULL DEPTH	5,126.000 LF	_____	_____	_____	_____
0260	ATTD	315SX20-0004 PAVEMENT RUBBLIZED HYDRAULIC CEMENT CONCRETE	22,001.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0270	412	412SD20-0044 SAW CUTTING	1,224.000 LF	_____	_____	_____	_____
0280	501	501SD20-0004 UNDERDRAIN UD-4	5,356.000 LF	_____	_____	_____	_____
0290	501	501SD20-0007 CROSSDRAIN CD-2	48.000 LF	_____	_____	_____	_____
0300	501	501SD20-0009 OUTLET PIPE	1,482.000 LF	_____	_____	_____	_____
0310	501	501SX20-0001 UNDERDRAIN MODIFIED UD- 4, 6"	7,132.000 LF	_____	_____	_____	_____
0320	502	502SD20-0020 CURB, ASPHALT MC-3B	412.000 LF	_____	_____	_____	_____
0330	502	502SD20-0036 MEDIAN BARRIER MB-7D	801.000 LF	_____	_____	_____	_____
0340	502	502SD20-0040 MEDIAN BARRIER MB-12A	605.000 LF	_____	_____	_____	_____
0350	505	505SD20-0009 REMOVE EX. GUARDRAIL TERMINAL	7.000 EA	_____	_____	_____	_____
0360	505	505SD20-0011 GUARDRAIL GR-MGS1	930.000 LF	_____	_____	_____	_____
0370	505	505SD20-0017 GUARDRAIL TERMINAL GR- MGS2	4.000 EA	_____	_____	_____	_____
0380	505	505SD20-0018 GUARDRAIL END ANCHORAGE GR-MGS3	2.000 EA	_____	_____	_____	_____
0390	505	505SD20-0019 GUARDRAIL HEIGHT TRANSITION GR-MGS4	4.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0400	505	505SD20-0073 REMOVE EXISTING GUARDRAIL	3,120.000 LF	_____	_____	_____	_____
0410	507	507SX20-0019 GATE FE-G (24-FT)	1.000 EA	_____	_____	_____	_____
0420	508	508SD20-0001 OBSCURING ROADWAY	215.100 UNIT	_____	_____	_____	_____
0430	508	508SD20-0002 DEMO. OF PVMT. COMBINATION	53,820.000 SY	_____	_____	_____	_____
0440	509	509SD20-0001 FLOWABLE BACKFILL	29.000 CY	_____	_____	_____	_____
0450	510	510SX20-0026 REMOVE EXIST. DROP INLET .	2.000 EA	_____	_____	_____	_____
0460	510	510SX20-0031 MODIFY EXIST. DROP INLET	14.000 EA	_____	_____	_____	_____
0470	510	510SX20-0039 REMOVE EXIST. BARRIER	5,843.000 LF	_____	_____	_____	_____
0480	510	510SX20-0039 REMOVE EXIST. PIPE	16.000 LF	_____	_____	_____	_____
0490	510	510SX20-0040 REMOVE EXIST. CONCRETE ISLANDS/CANOPY FOOTINGS	30.000 EA	_____	_____	_____	_____
0500	510	510SX20-0040 REMOVE EXIST. IMPACT ATTENUATORS	29.000 EA	_____	_____	_____	_____
0510	511	511SD20-0001 ALLAYING DUST	260.000 HR	_____	_____	_____	_____
0520	512	512SD20-0007 IMPACT ATTEN.SER. TY. 1 TL- 3, >=40 MPH	11.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0530	512	512SD20-0013 TYPE 3 BARRICADE 8'	11.000 EA	_____	_____	_____	_____
0540	512	512SD20-0014 TEMPORARY SIGN	2,146.000 SF	_____	_____	_____	_____
0550	512	512SD20-0024 GROUP 2 CHANNELIZING DEVICES	62,910.000 DAY	_____	_____	_____	_____
0560	512	512SD20-0025 PORT.CHANGEABLE MESS. SIGN	14,400.000 HR	_____	_____	_____	_____
0570	512	512SD20-0026 ELECTRONIC ARROW BOARD	2,160.000 HR	_____	_____	_____	_____
0580	512	512SD20-0031 TRAFFIC BARRIER SER. CONC. MB-7D PC	13,011.000 LF	_____	_____	_____	_____
0590	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	72,565.000 LF	_____	_____	_____	_____
0600	512	512SD20-0044 TEMP. PAVE. MARKER 1 WAY	1,136.000 EA	_____	_____	_____	_____
0610	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	27,924.000 LF	_____	_____	_____	_____
0620	512	512SD20-0048 TEMP. PVMT MRKG TY. A, 8"	43,529.000 LF	_____	_____	_____	_____
0630	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	1,112.000 LF	_____	_____	_____	_____
0640	513	513SD20-0001 MOBILIZATION	LUMP SUM	LUMP SUM	_____	_____	_____
0650	515	515SD20-0004 FLEXIBLE PAVE.PLANING 0"- 2"	20,621.000 SY	_____	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0660	517	517SD20-0001 CONSTRUCTION SURVEYING CONSTR.	LUMP SUM	LUMP SUM			
0670	602	602SD20-0005 TOPSOIL CLASS B 2"	15.900 ACRE				
0680	603	603SD20-0002 TEMPORARY SEED	1,590.000 LB				
0690	603	603SD20-0003 REGULAR SEED	2,286.000 LB				
0700	603	603SD20-0004 OVERSEEDING	1,829.000 LB				
0710	603	603SD20-0005 LEGUME SEED	240.000 LB				
0720	603	603SD20-0008 HYDRAULIC EROSION CONTROL PRODUCT TYPE 2	92,565.000 SY				
0730	603	603SD20-0009 HYDRAULIC EROSION CONTROL PRODUCT TYPE 3	80,586.000 SY				
0740	603	603SD20-0014 FERTILIZER NITROGEN - N	636.000 LB				
0750	603	603SD20-0015 FERTILIZER PHOSPHOROUS - P	636.000 LB				
0760	603	603SD20-0016 FERTILIZER POTASSIUM - K	636.000 LB				
0770	603	603SD20-0017 LIME	31.800 TON				
0780	606	606SD20-0001 ROLLED EROSION CTRL PRODUCT EC-2 TYPE 1	6,251.000 SY				

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0790	700	700SD20-0003 REMOVE EXISTING 1 POST SIGN STRUCTURE	25.000 EA	_____	_____	_____	_____
0800	700	700SD20-0004 REMOVE EXISTING 2 POST SIGN STRUCTURE	19.000 EA	_____	_____	_____	_____
0810	700	700SD20-0007 REMOVE EXISTING 1 POST SIGN PANEL	28.000 EA	_____	_____	_____	_____
0820	700	700SD20-0028 VIA SIGN POST W18 X 35	62.000 LF	_____	_____	_____	_____
0830	700	700SD20-0033 VIA SIGN POST W16 X 40	67.000 LF	_____	_____	_____	_____
0840	700	700SD20-0034 SIGN POST STP-1, 2", 14 GAUGE	30.000 LF	_____	_____	_____	_____
0850	700	700SD20-0036 SIGN POST STP-1, 2 1/2", 10 GAUGE	77.000 LF	_____	_____	_____	_____
0860	700	700SD20-0037 SIGN POST STP-1, 2 1/2", 12 GAUGE	34.000 LF	_____	_____	_____	_____
0870	700	700SD20-0038 CONC. FOUND. STP-1, TY. A	7.000 EA	_____	_____	_____	_____
0880	700	700SD20-0039 CONC. FOUND. STP-1, TY. B	6.000 EA	_____	_____	_____	_____
0890	700	700SD20-0054 CONC. FOUND. SSP-VIA, 4' DIA. X 12' DEEP	6.000 EA	_____	_____	_____	_____
0900	ATTD	700SX20-0014 LIGHTING REMOVAL (ALLOWANCE)	LUMP SUM	LUMP SUM	_____	_____	_____

Schedule of Items

Proposal ID: C0000126660C01

Oversight/State Project No.: 0076-020-075, C501

Order No.: T01

Federal Project No.: NONE

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0910	700	700SX20-0017 REMOVE EXIST. OVERHEAD SIGN STRUCTURE .	3.000 EA	_____	_____	_____	_____
0920	700	700SX20-0018 REMOVE EXIST OVRHD SGN STR. SGN.PANEL .	3.000 EA	_____	_____	_____	_____
0930	701	701SD20-0001 SIGN PANEL	297.000 SF	_____	_____	_____	_____
0940	701	701SD20-0002 OVERLAY SIGN PANEL	276.700 SF	_____	_____	_____	_____
0950	704	704SD20-0027 TYPE B CLASS VI PVMT LINE MRKG 6"	26,880.000 LF	_____	_____	_____	_____
0960	704	704SD20-0029 TYPE B CLASS VI PVMT LINE MRKG 12"	1,093.000 LF	_____	_____	_____	_____
0970	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	70.000 EA	_____	_____	_____	_____
Section: 0001				Total:		_____	_____
				Total Bid:		_____	_____