

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                            | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|---------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                   |                                      | Dollars    | Cents | Dollars    | Cents |
| 0010                       | 301         | 301SD20-0002<br>CLEARING AND GRUBBING             | 0.040<br>ACRE                        | _____      | _____ | _____      | _____ |
| 0020                       | 302, 406    | 302SD20-0005<br>REINF. STEEL                      | 1,052.000<br>LB                      | _____      | _____ | _____      | _____ |
| 0030                       | 302         | 302SD20-0037<br>24" PIPE                          | 15.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0040                       | 302         | 302SD20-0041<br>24" STORM SEWER PIPE              | 133.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0050                       | 302         | 302SD20-0049<br>30" CONC. PIPE CLASS 3            | 11.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0060                       | 302         | 302SD20-0200<br>18" END SECTION ES-1 OR 2         | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0070                       | 302         | 302SD20-0204<br>24" END SECTION ES-1 OR 2         | 2.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0080                       | 302         | 302SD20-0447<br>DROP INLET DI-7                   | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0090                       | 303         | 303SD20-0001<br>REGULAR EXCAVATION                | 178.720<br>CY                        | _____      | _____ | _____      | _____ |
| 0100                       | 303         | 303SD20-0016<br>MINOR STR. EXCAV. PIPE<br>CULVERT | 47.000<br>CY                         | _____      | _____ | _____      | _____ |
| 0110                       | 303         | 303SD20-0023<br>CHECK DAM ROCK TY. II             | 16.000<br>EA                         | _____      | _____ | _____      | _____ |
| 0120                       | 303         | 303SD20-0029<br>SILTATION CONTROL<br>EXCAVATION   | 524.000<br>CY                        | _____      | _____ | _____      | _____ |
| 0130                       | 303         | 303SD20-0030<br>INLET PROTECTION TYPE A           | 3.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0140                       | 303         | 303SD20-0031<br>INLET PROTECTION TYPE B           | 4.000<br>EA                          | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                  | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|---------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                         |                                      | Dollars    | Cents | Dollars    | Cents |
| 0150                       | 303         | 303SD20-0034<br>TEMP. SILT FENCE TYPE A                 | 3,078.000<br>LF                      | _____      | _____ | _____      | _____ |
| 0160                       | 305         | 305SD20-0001<br>BORROW EXCAVATION MIN.<br>CBR-10        | 192.950<br>CY                        | _____      | _____ | _____      | _____ |
| 0170                       | 315         | 315SD20-0001<br>ASPHALT CONCRETE TY. SM-<br>12.5A CONST | 29.230<br>TON                        | _____      | _____ | _____      | _____ |
| 0180                       | 315         | 315SD20-0104<br>SAW-CUT ASPHALT<br>CONCRETE 2" DEPTH    | 243.730<br>LF                        | _____      | _____ | _____      | _____ |
| 0190                       | 315         | 315SD20-0104<br>SAW-CUT ASPHALT<br>CONCRETE FULL DEPTH  | 155.360<br>LF                        | _____      | _____ | _____      | _____ |
| 0200                       | 414         | 414SD20-0001<br>EROSION CTRL. STONE CL.<br>A1, EC-1     | 3.000<br>TON                         | _____      | _____ | _____      | _____ |
| 0210                       | 414         | 414SD20-0003<br>EROSION CTRL. STONE CL. I,<br>EC-1      | 13.000<br>TON                        | _____      | _____ | _____      | _____ |
| 0220                       | 502         | 502SD20-0011<br>CURB, STD. CG-2                         | 657.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0230                       | 502         | 502SD20-0012<br>CURB, RADIAL CG-2                       | 121.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0240                       | 502         | 502SD20-0023<br>COMB. CURB & GUTTER,<br>RAD. CG-6       | 5.000<br>LF                          | _____      | _____ | _____      | _____ |
| 0250                       | 502         | 502SX20-0008<br>COMB. CURB & GUTTER 1.5'<br>GUTTER PAN  | 113.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0260                       | 502         | 502SX20-0010<br>SAW CUT H.C.C. ITEMS FULL<br>DEPTH      | 105.490<br>LF                        | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                              | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|-----------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                     |                                      | Dollars    | Cents | Dollars    | Cents |
| 0270                       | 302, 504    | 504SD20-0001<br>CONCRETE CLASS A3 MISC.             | 11.000<br>CY                         | _____      | _____ | _____      | _____ |
| 0280                       | 504         | 504SD20-0002<br>CG-12 DETECTABLE<br>WARNING SURFACE | 28.000<br>SY                         | _____      | _____ | _____      | _____ |
| 0290                       | 504         | 504SD20-0003<br>HYDR. CEMENT CONC.<br>SIDEWALK 4"   | 835.000<br>SY                        | _____      | _____ | _____      | _____ |
| 0300                       | 507         | 507SD20-0027<br>HIGH VISIBILITY FENCE, 4<br>FEET    | 146.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0310                       | 508         | 508SD20-0004<br>DEMO. OF PAVEMENT<br>FLEXIBLE       | 8.730<br>SY                          | _____      | _____ | _____      | _____ |
| 0320                       | 510         | 510SD20-0050<br>ADJUST EXIST FRAME &<br>COVER       | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0330                       | ATTD        | 510SX20-0002<br>REMOVE COMB. CURB AND<br>GUTTER     | 243.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0340                       | ATTD        | 510SX20-0031<br>MODIFY EXIST. CONTROLLER<br>CABINET | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0350                       | ATTD        | 510SX20-0031<br>MODIFY EXIST. JUNCTION<br>BOX       | 4.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0360                       | 511         | 511SD20-0001<br>ALLAYING DUST                       | 215.000<br>HR                        | _____      | _____ | _____      | _____ |
| 0370                       | 512         | 512SD20-0014<br>TEMPORARY SIGN                      | 532.000<br>SF                        | _____      | _____ | _____      | _____ |
| 0380                       | 512         | 512SD20-0023<br>TRUCK MOUNTED<br>ATTENUATOR         | 1,720.000<br>HR                      | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                                              | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|-------------------------------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                                                     |                                      | Dollars    | Cents | Dollars    | Cents |
| 0390                       | 512         | 512SD20-0024<br>GROUP 2 CHANNELIZING<br>DEVICES                                     | 21,295.000<br>DAY                    | _____      | _____ | _____      | _____ |
| 0400                       | 512         | 512SD20-0025<br>PORT.CHANGEABLE MESS.<br>SIGN                                       | 3,624.000<br>HR                      | _____      | _____ | _____      | _____ |
| 0410                       | 512         | 512SD20-0026<br>ELECTRONIC ARROW BOARD                                              | 3,240.000<br>HR                      | _____      | _____ | _____      | _____ |
| 0420                       | 512         | 512SD20-0027<br>FLAGGER SERVICE                                                     | 200.000<br>HR                        | _____      | _____ | _____      | _____ |
| 0430                       | 512         | 512SD20-0042<br>ERADICATE LINEAR PVMT<br>MRKG                                       | 1,340.000<br>LF                      | _____      | _____ | _____      | _____ |
| 0440                       | 512         | 512SD20-0043<br>ERADICATE NONLINEAR<br>PVMT MRKG                                    | 496.000<br>SF                        | _____      | _____ | _____      | _____ |
| 0450                       | 512         | 512SD20-0046<br>TEMP. PVMT MRKG TY. A, 4"                                           | 160.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0460                       | 512         | 512SD20-0050<br>TEMP. PVMT MRKG TY. A, 24"                                          | 25.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0470                       | 512         | 512SD20-0052<br>TEMP. PVMT. SYMB. MRKG<br>SNGL TURN ARROW TY. A                     | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0480                       | ATTD        | 512SP20-0003<br>UNIFORMED FLAGGERS                                                  | 40.000<br>HR                         | _____      | _____ | _____      | _____ |
| 0490                       | ATTD        | 512SX20-0050<br>TEMP. TRAFFIC CONTROL<br>SIGNAL TEMPORARY VIDEO<br>DETECTION SYSTEM | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0500                       | 513         | 513SD20-0001<br>MOBILIZATION                                                        | LUMP SUM                             | LUMP SUM   | _____ | _____      | _____ |
| 0510                       | 514         | 514SD20-0002<br>FIELD OFFICE TY.II                                                  | 9.000<br>MO                          | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                                                           | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|--------------------------------------------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                                                                  |                                      | Dollars    | Cents | Dollars    | Cents |
| 0520                       | 515         | 515SD20-0004<br>FLEXIBLE PAVE.PLANING 0"-<br>2"                                                  | 266.000<br>SY                        | _____      | _____ | _____      | _____ |
| 0530                       | 516         | 516SD20-0002<br>DEMOLITION OF BUILDING<br>PARCEL 002 D900, D901,<br>D902, D903, D904, D905, D906 | LUMP SUM                             | LUMP SUM   |       | _____      | _____ |
| 0540                       | 517         | 517SD20-0001<br>CONSTRUCTION SURVEYING<br>CONSTR.                                                | LUMP SUM                             | LUMP SUM   |       | _____      | _____ |
| 0550                       | 520         | 520SD20-0002<br>3/4" WATER SERVICE LINE                                                          | 59.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0560                       | 520         | 520SD20-0167<br>5/8" WATER METER BOX &<br>YOKE                                                   | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0570                       | 602         | 602SD20-0005<br>TOPSOIL CLASS B 2"                                                               | 0.270<br>ACRE                        | _____      | _____ | _____      | _____ |
| 0580                       | 603         | 603SD20-0002<br>TEMPORARY SEED                                                                   | 27.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0590                       | 603         | 603SD20-0003<br>REGULAR SEED                                                                     | 50.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0600                       | 603         | 603SD20-0004<br>OVERSEEDING                                                                      | 40.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0610                       | 603         | 603SD20-0014<br>FERTILIZER NITROGEN - N                                                          | 27.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0620                       | 603         | 603SD20-0015<br>FERTILIZER PHOSPHOROUS<br>- P                                                    | 19.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0630                       | 603         | 603SD20-0016<br>FERTILIZER POTASSIUM - K                                                         | 19.000<br>LB                         | _____      | _____ | _____      | _____ |
| 0640                       | 603         | 603SD20-0017<br>LIME                                                                             | 1.500<br>TON                         | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                     | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                            |                                      | Dollars    | Cents | Dollars    | Cents |
| 0650                       | ATTD        | 605SX20-0017<br>SEED MIXTURE WETLANDS<br>MIX               | 0.050<br>LB                          | _____      | _____ | _____      | _____ |
| 0660                       | 606         | 606SD20-0002<br>ROLLED EROSION CTRL<br>PRODUCT EC-2 TYPE 2 | 125.000<br>SY                        | _____      | _____ | _____      | _____ |
| 0670                       | 606         | 606SD20-0005<br>ROLLED EROSION CTRL<br>PRODUCT EC-3 TYPE 1 | 35.000<br>SY                         | _____      | _____ | _____      | _____ |
| 0680                       | 608         | 608SD20-0001<br>MOWING                                     | 215.000<br>HR                        | _____      | _____ | _____      | _____ |
| 0690                       | 700         | 700SD20-0003<br>REMOVE EXISTING 1 POST<br>SIGN STRUCTURE   | 3.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0700                       | 700         | 700SD20-0034<br>SIGN POST STP-1, 2", 14<br>GAUGE           | 114.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0710                       | 700         | 700SD20-0036<br>SIGN POST STP-1, 2 1/2", 10<br>GAUGE       | 17.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0720                       | 700         | 700SD20-0037<br>SIGN POST STP-1, 2 1/2", 12<br>GAUGE       | 37.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0730                       | 700         | 700SD20-0038<br>CONC. FOUND. STP-1, TY. A                  | 14.000<br>EA                         | _____      | _____ | _____      | _____ |
| 0740                       | 700         | 700SD20-0040<br>CONC. FOUND. STP-1, TY. C                  | 2.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0750                       | 700         | 700SD20-0067<br>PEDESTAL POLE PF-2, 12'                    | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0760                       | 700         | 700SD20-0069<br>CONC. FOUND. PF-2                          | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0770                       | 700         | 700SD20-0109<br>12/1 CONDUCTOR CABLE                       | 1,252.000<br>LF                      | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                                      | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|-----------------------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                                             |                                      | Dollars    | Cents | Dollars    | Cents |
| 0780                       | 700         | 700SD20-0112<br>14/4 CONDUCTOR CABLE                                        | 2,524.000<br>LF                      | _____      | _____ | _____      | _____ |
| 0790                       | 700         | 700SD20-0120<br>14/2 CONDUCTOR CABLE<br>SHIELDED                            | 560.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0800                       | 700         | 700SD20-0178<br>JUNCTION BOX JB-S2                                          | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0810                       | 700         | 700SD20-0182<br>CONDUIT PVC 1"                                              | 40.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0820                       | 700         | 700SD20-0191<br>BORED CONDUIT 2"                                            | 200.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0830                       | 700         | 700SD20-0192<br>BORED CONDUIT 3"                                            | 380.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0840                       | 700         | 700SD20-0194<br>CONDUIT PVC 2"                                              | 102.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0850                       | 700         | 700SD20-0195<br>CONDUIT PVC 3"                                              | 60.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0860                       | 700         | 700SD20-0197<br>TRENCH EXCAVATION ECI-1                                     | 138.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0870                       | ATTD        | 700SX20-0010<br>TRAFFIC SIGNALIZATION APS<br>PEDESTRIAN ACTUATION<br>(PA-2) | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0880                       | ATTD        | 700SX20-0021<br>TRAFFIC SIGN<br>RETROREFLECTIVE<br>SIGNPOST STRIPS          | 5.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0890                       | 701         | 701SD20-0001<br>SIGN PANEL                                                  | 176.900<br>SF                        | _____      | _____ | _____      | _____ |
| 0900                       | 702         | 702SD20-0003<br>ROAD EDGE DEL. ED-2                                         | 2.000<br>EA                          | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                     | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|------------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                            |                                      | Dollars    | Cents | Dollars    | Cents |
| 0910                       | 703         | 703SD20-0034<br>HANGER ASSEMBLY SM-3,<br>ONE WAY           | 1.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0920                       | 703         | 703SD20-0039<br>HANGER ASSEMBLY SMB-3,<br>ONE WAY          | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0930                       | 703         | 703SD20-0042<br>LOOP SAW CUT 3/8"                          | 396.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0940                       | 703         | 703SD20-0043<br>LOOP SAW CUT 5/8"                          | 80.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0950                       | 703         | 703SD20-0049<br>RELOCATE EXISTING SIGNAL<br>HEAD           | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0960                       | 703         | 703SD20-0060<br>PEDESTRIAN SIGNAL HEAD<br>SP-8             | 6.000<br>EA                          | _____      | _____ | _____      | _____ |
| 0970                       | 704         | 704SD20-0006<br>TYPE B CLASS I PVMT LINE<br>MRKG 4"        | 420.000<br>LF                        | _____      | _____ | _____      | _____ |
| 0980                       | 704         | 704SD20-0007<br>TYPE B CLASS I PVMT LINE<br>MRKG 6"        | 10.000<br>LF                         | _____      | _____ | _____      | _____ |
| 0990                       | 704         | 704SD20-0015<br>TYPE B CLASS II PVMT LINE<br>MRKG 24"      | 490.000<br>LF                        | _____      | _____ | _____      | _____ |
| 1000                       | 704         | 704SD20-0043<br>PVMT SYMB MRKG THRU<br>ARROW TY A          | 3.000<br>EA                          | _____      | _____ | _____      | _____ |
| 1010                       | 704         | 704SD20-0046<br>PVMT SYMB MRKG SGL<br>TURN ARROW TY A      | 2.000<br>EA                          | _____      | _____ | _____      | _____ |
| 1020                       | 704         | 704SD20-0048<br>PVMT SYMB MRKG SGL<br>TURN ARR. TY B CL II | 2.000<br>EA                          | _____      | _____ | _____      | _____ |

## Schedule of Items

Proposal ID: C0000123958C01

Oversight/State Project No.: 0058-109-192, C501

Order No.: B19

Federal Project No.: TAP-5109(126)

Contractor: \_\_\_\_\_

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

| Proposal<br>Line<br>Number | Spec<br>No. | Item ID<br>Description                                    | Approximate<br>Quantity and<br>Units | Unit Price |       | Bid Amount |       |
|----------------------------|-------------|-----------------------------------------------------------|--------------------------------------|------------|-------|------------|-------|
|                            |             |                                                           |                                      | Dollars    | Cents | Dollars    | Cents |
| 1030                       | 704         | 704SD20-0051<br>DBL TURN ARR.THRU/LT OR<br>RT TY B, CL II | 2.000<br>EA                          | _____      | _____ | _____      | _____ |
| Section: 0001              |             |                                                           |                                      | Total:     |       | _____      | _____ |
|                            |             |                                                           |                                      | Total Bid: |       | _____      | _____ |