

Schedule of Items

Proposal ID: CM827PMH129943 Oversight/State Project No.: PM8H-034-27F, P401

Order No.: 809

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0010	ATTD	305SP20-0003 AGR. BASE MAT. TY. I OR II NO. 21A OR 21B	1,443.930 TON	_____	_____	_____	_____
0020	310	310SD20-0001 TACK COAT	23,575.000 GAL	_____	_____	_____	_____
0030	315	315SD20-0015 RUMBLE STRIP CYLINDRICAL ASPHALT	30,287.000 LF	_____	_____	_____	_____
0040	ATTD	315SP20-0006 PAVEMENT SHOULDER WEDGE PREP. CONST	7,254.000 LF	_____	_____	_____	_____
0050	315	315SP20-0051 ASPH. CONC. BMD P+VO SM- 12.5D	25,307.610 TON	_____	_____	_____	_____
0060	512	512SD20-0027 FLAGGER SERVICE	601.000 HR	_____	_____	_____	_____
0070	512	512SD20-0042 ERADICATE LINEAR PVMT MRKG	210.000 LF	_____	_____	_____	_____
0080	512	512SD20-0043 ERADICATE NONLINEAR PVMT MRKG	250.000 SF	_____	_____	_____	_____
0090	512	512SD20-0046 TEMP. PVMT MRKG TY. A, 4"	27,700.000 LF	_____	_____	_____	_____
0100	512	512SD20-0047 TEMP. PVMT MRKG TY. A, 6"	120,150.000 LF	_____	_____	_____	_____
0110	512	512SD20-0049 TEMP. PVMT MRKG TY. A, 12"	845.000 LF	_____	_____	_____	_____
0120	512	512SD20-0051 TEMP. PVMT. SYMB. MRKG THRU ARROW TY. A	6.000 EA	_____	_____	_____	_____
0130	512	512SD20-0052 TEMP. PVMT. SYMB. MRKG SNGL TURN ARROW TY. A	66.000 EA	_____	_____	_____	_____

Schedule of Items

Proposal ID: CM827PMH129943 Oversight/State Project No.: PM8H-034-27F, P401

Order No.: 809

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0140	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT FOR UPC 129943	LUMP SUM	LUMP SUM			
0150	ATTD	512SP20-0002 MAINTENANCE OF TRAFFIC MOT FOR UPC 129944	LUMP SUM	LUMP SUM			
0160	ATTD	512SX20-0006 TEMP. PVMT MRKG TEMP. SCHOOL	2.000 EA				
0170	515	515SD20-0011 FLEX. PAVE. TIE-IN PLANING 0"-2"	3,695.000 SY				
0180	515	515SD20-0013 FLEXIBLE PAVE.PLANING 0"- 2"	194,952.270 SY				
0190	704	704SD20-0001 TYPE A PVMT LINE MRKG 4"	14,500.000 LF				
0200	704	704SD20-0002 TYPE A PVMT LINE MRKG 6"	550.000 LF				
0210	704	704SD20-0006 TYPE B CLASS I PVMT LINE MRKG 4"	2,850.000 LF				
0220	704	704SD20-0007 TYPE B CLASS I PVMT LINE MRKG 6"	119,600.000 LF				
0230	704	704SD20-0011 TYPE B CLASS II PVMT LINE MRKG 4"	1,000.000 LF				
0240	704	704SD20-0015 TYPE B CLASS II PVMT LINE MRKG 24"	1,800.000 LF				
0250	704	704SD20-0031 TYPE B CLASS VI CONTRAST PVMT LINE MRKG 6"	570.000 LF				

Schedule of Items

Page: 4

Proposal ID: CM827PMH129943 Oversight/State Project No.: PM8H-034-27F, P401

Order No.: 809

Federal Project No.: PM08471

Contractor: _____

SECTION: 0001

REGULAR BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0260	ATTD	704SD20-0032 INLAID PAVEMENT MARKER ASPHALT	605.000 EA	_____	_____	_____	_____
0270	704	704SD20-0045 PVMY SYMB MRKG THRU ARROW TY B, CL II	6.000 EA	_____	_____	_____	_____
0280	704	704SD20-0048 PVMY SYMB MRKG SGL TURN ARR. TY B CL II	62.000 EA	_____	_____	_____	_____
0290	704	704SD20-0083 PVMY SYMB MRKG YIELD 1' X 1.5' TY B, CL I	24.000 EA	_____	_____	_____	_____
0300	704	704SD20-0108 PVMY MSG. MARK. "ONLY" TY B, CL II, 8'	1.000 EA	_____	_____	_____	_____
0310	704	704SD20-0124 PVMY MSG. MARK. "SCHOOL" TY B, CL II, 10'	1.000 EA	_____	_____	_____	_____
Section: 0001				Total:	_____	_____	_____

SECTION: 0002

ALTERNATE BID ITEMS

Cat Alt Set ID:

Cat Alt Mbr ID:

Proposal Line Number	Spec No.	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
				Dollars	Cents	Dollars	Cents
0320	ATTD	305SX20-0006 SELECT MATERIAL ALTERNATE SHOULDER MATERIAL	1.000 TON	_____	_____	_____	_____
Section: 0002				Total:	_____	_____	_____
				Total Bid:	_____	_____	_____